



महाराष्ट्र शासन राजपत्र

भाग एक-पुणे विभागीय पुरवणी

वर्ष - ७, अंक ४१]

गुरुवार ते बुधवार, ऑक्टोबर ११ - १७, २०१८ / आश्विन १९ - २५, शके १९४०

[पृष्ठे २६६

प्राधिकृत प्रकाशन

शासकीय / संकीर्ण अधिसूचना, नेमणुका, पदोन्नती इत्यादी

मुख्य कार्यकारी अधिकारी यांजकडून

झोपडपट्टी पुनर्वसन प्राधिकरण,

पुणे व पिंपरी-चिंचवड क्षेत्र, पुणे

झोपडपट्टी पुनर्वसन आदेश

जाहीर नोटीस

क्रमांक झोपुप्रा/सप्रा-२/झोपुआ/प्र. क्र. २५२/१०४०/२०१८.— ज्याअर्थी, महाराष्ट्र शासनाने महाराष्ट्र झोपडपट्टी (सुधारणा, निर्मूलन व पुनर्विकास) अधिनियम, १९७१ (प्रस्तुत आदेशात या अधिनियमाचा उल्लेख यापुढे सोयीकरिता "उपरोक्त अधिनियम" असा करणेत येत आहे) चे कलम ३-अ (१), (२) अन्वये पुणे व पिंपरी-चिंचवड महानगरपालिका क्षेत्राकरिता गृहनिर्माण विभागाकडील अधिसूचना क्रमांक झोपुयो-२००४/प्र. क्र. २१३/झोपसु-१, दिनांक ३० जून २००५ अन्वये झोपडपट्टी पुनर्वसन प्राधिकरणाची स्थापना केली आहे ;

आणि ज्याअर्थी, उक्त अधिनियमाच्या कलम ३-ब मधील तरतुदीनुसार पुणे व पिंपरी-चिंचवड महानगरपालिकांच्या क्षेत्रासाठी सर्वसाधारण झोपडपट्टी पुनर्वसन योजना या प्राधिकरणाकडून तयार करण्यात आलेली आहे. झोपडपट्टी पुनर्वसन प्राधिकरणाच्या मंजूरीने सदरची सर्वसाधारण झोपडपट्टी पुनर्वसन योजना महाराष्ट्र शासनाच्या राजपत्रात दिनांक १ डिसेंबर २००५ रोजी अंतिमतः प्रसिद्ध करण्यात आलेली आहे ;

आणि ज्याअर्थी, उपरोक्त उक्त अधिनियमातील तरतुदीनुसार अनुसूचीमध्ये नमूद केलेल्या मिळकतीवर झोपडपट्टी पुनर्वसन योजना राबविण्यासाठी झोपडपट्टी पुनर्वसन प्राधिकरणाकडे पुनर्वसनाचा प्रस्ताव दाखल झालेला आहे. या कार्यालयाकडील परिपत्रक क्रमांक झोपुप्रा/तांत्रिक/१८५९/२०१७, दिनांक २८ नोव्हेंबर २०१७ नुसार "ज्या खाजगी जागेवरील

झोपडपट्ट्या घोषित नाहीत, अशा झोपडपट्ट्यांच्या बाबतीत या कार्यालयाकडील आदेश क्रमांक २१५ मध्ये नमूद केलेल्या कार्यपद्धतीप्रमाणे झोपडपट्टीसदृश परिस्थितीबाबत अंतिम निर्णय घेतल्यानंतर, सदरचे क्षेत्र महाराष्ट्र झोपडपट्टी (सुधारणा, निर्मूलन व पुनर्विकास) अधिनियम, १९७१ मधील कलम ३ (क) अन्वये झोपडपट्टी पुनर्वसन क्षेत्र म्हणून प्रथम घोषित करणे आवश्यक राहिल. सदरचा आदेश झाल्यानंतरच योजनेच्या अनुषंगाने प्राथमिक सर्वेक्षणाचे जाहीर प्रकटन, पात्रता यादी (परिशिष्ट-२) व इतर अनुषंगिक कामे याबाबतची कार्यवाही करता येईल. अशी कार्यपद्धती निश्चित करण्यात आलेली आहे ;

आणि ज्याअर्थी, खालील अनुसूचीमध्ये नमूद केलेल्या मिळकतीवर झोपडपट्टी असलेने व ती घोषित नसलेमुळे उप आयुक्त परिमंडळ क्रमांक २, पुणे महानगरपालिका यांनी झोपडपट्टीसदृश परिस्थिती असलेला अहवाल, त्यांचेकडील कार्यालयीन पत्र जा. क्र. क्षेत्राप-२/१७४, दिनांक १४ जून २०१८ रोजी सादर केला आहे तसेच मान्य विकास आराखडा सन २०१६ नुसार खालील अनुसूचीमध्ये नमूद केलेले झोपडपट्टी व्याप्त क्षेत्र हे "झोपडपट्टी सुधार क्षेत्र" (Slum Improvement Zone) म्हणून समाविष्ट आहे ;

आणि ज्याअर्थी, महाराष्ट्र झोपडपट्टी (सुधारणा, निर्मूलन व पुनर्विकास) (सुधारणा) २०१७ मधील तरतुदी विचारात घेता झोपडपट्टी पुनर्वसन क्षेत्र घोषित करताना, "कोणतीही झोपडपट्टी पुनर्वसन योजना प्रसिद्ध झाल्यानंतर यथाशीघ्र, मुख्य कार्यकारी अधिकारी, कोणत्याही जमिनीच्या बाबतीत, मग ती पूर्वी झोपडपट्टी क्षेत्र म्हणून घोषित झालेली असो किंवा नसो, व ज्या सामुहिक आर्थिक कार्यक्षेत्राचा अंतर्भाव करता येईल ती जमीन, झोपडपट्टी पुनर्वसन क्षेत्र म्हणून घोषित केले जाणे समर्थनीय ठरविणारी परिस्थिती अस्तित्वात असल्याबद्दल त्याची खात्री पटल्यावर, कोणतीही सार्वजनिक प्राधिकरणे किंवा राज्य विधी मंडळाने अधिनियमित केलेल्या कोणत्याही

कायद्यान्वये गठित केलेल्या राज्य शासनाच्या स्थानिक संस्था यासह जमीन मालकांना ३० दिवसांची नोटीस आणि त्यांचे म्हणणे मांडण्याची वाजवी संधी दिल्यानंतर, राजपत्रात प्रसिद्ध केलेल्या आदेशाद्वारे आणि त्यानंतर ४५ दिवसांच्या आत अशी जमीन झोपडपट्टी पुनर्वसन क्षेत्र म्हणून घोषित करील" असे नमूद केले आहे ;

आणि ज्याअर्थी, दिनांक २१ ऑगस्ट २०१८ रोजी स्थानिक वर्तमानपत्रात तसेच महाराष्ट्र शासन राजपत्र भाग एक पुरवणीमध्ये दिनांक ऑगस्ट ३० ते सप्टेंबर ५, २०१८ रोजी पृष्ठ १३ व १४ मध्ये प्रसिद्धी करिता देणेत येवून खालील अनुसूचीमध्ये निर्दिष्ट क्षेत्राचे जमीन मालक अथवा मालकी हक्क प्राप्त असलेल्या व्यक्ती/संस्था यांना त्यांच्या ज्या काही सूचना/हरकती असतील त्या ३० दिवसांच्या आत सादर करणेस फर्माविण्यात आलेले आहे.

उक्त नोटीसीस अनुसरून या कार्यालयाकडे हरकती प्राप्त झालेल्या आहेत. प्राप्त हरकतीच्या अनुषंगाने संबंधितांना त्यांचे म्हणणे मांडण्याची संधी देणेत आलेली आहे. हरकतदार यांनी त्यांचे लेखी म्हणण्यात सदरील जागा राहण्याच्या दृष्टीने अतिशय योग्य आहे. आरोग्याची, सुरक्षिततेची कुठलीही समस्या नाही. सदर परिसरातील जागा याठिकाणी कुठल्याही प्रकारची झोपडपट्टी सदृश्य स्थिती नाही व तसेच अर्जदार हे भोगवटादार व भाडेकरू आहेत तशा भाडेपावत्याही आहेत, त्यामुळे सदर योजनेत लाभार्थी म्हणून आवश्यक तो लाभ देण्यात यावा व सदरचे घर, खोल्यांचा सर्व व्हावा व न्यायाप्रमाणे घर मिळावे इत्यादी मुद्दे नमूद केलेले आहेत. तथापि हरकतदार यांच्या लेखी म्हणण्यानुसार वस्तुस्थिती पाहता विकास आराखडा अभिप्राय पाहता सदर मिळकत ही मान्य विकास आराखडा २०१६ प्रमाणे स्तम इम्प्लुमेंट झोनमध्ये समाविष्ट असल्याचे दिसून येते. तसेच उप आयुक्त परिमंडळ क्रमांक २, पुणे महानगरपालिका यांनी पत्र जा. क्र. क्षेत्राप-२/९७४, दिनांक १४ जून २०१८ रोजी सदर ठिकाणी झोपडपट्टी सदृश्य परिस्थिती असलेमुळे तसा अहवाल या कार्यालयाकडे सादर केला आहे.

तसेच हरकतदार यांचे लेखी म्हणणे पाहता त्यामध्ये प्रामुख्याने पात्रतेबद्दल आक्षेप असल्याचे दिसून येते. त्याबाबत उपरोक्त परिपत्रकात नमूद केलेप्रमाणे प्रथमतः झोपडपट्टी पुनर्वसन आदेश प्रसिद्ध केलेनंतर सदर झोपडीधारकांची पात्रता निश्चित करणेत येईल. पात्रता यादी निश्चित करतेवेळी सदर अर्जदार अपात्र ठरलेस त्यांच्या पात्रतेविरुद्ध अपील दाखल करून व त्यावर सुनावणी घेऊन त्यांच्या पात्रतेबद्दल निर्णय घेणेत येईल ;

आणि ज्याअर्थी, स्थळपाहणी दरम्यान उक्त मिळकत क्षेत्राचे पूर्वेस मुळा नदी असून त्याचे पुरस्षेचे रेखांकन सदर मिळकतीमधून जात असल्याचे पुणे महानगरपालिकेच्या विकास आराखड्यानुसार दिसून येते. याबाबत दिनांक २५ मे २०१८ अन्वये मा. आयुक्त, पुणे यांचेकडे विषयांकित जागेतील झोपडपट्टी पुनर्वसन योजनेच्या नकाशा मंजुरी देणेकामी अभिप्राय प्राप्त अपेक्षितेले आहे. मनपाचे अभिप्राय प्राप्त झालेनंतरच झोपडपट्टी पुनर्वसन योजना राबविणेत येईल. त्यामुळे सक्षम अधिकाऱ्याच्या आवश्यक त्या परवानगीनंतर त्या क्षेत्रासाठीचे पुनर्वसन त्याच ठिकाणी अथवा त्याऐवजी

इतरत्र उपलब्ध बांधकाम योग्य क्षेत्रावर पुनर्वसन योजना राबविणे गरजेचे ठरेल. तसेच विकास नियंत्रण नियमावलीमधील नियम क्रमांक १३.३ च्या तरतुदीस अधीन राहून सदरचा आदेश प्रसिद्ध करण्यात येत आहे. सदरचे क्षेत्र हे झोपडपट्टी पुनर्वसन क्षेत्र म्हणून घोषित करणेकामी समर्थनिय ठरणारी परिस्थिती अस्तित्वात असल्याबद्दल माझी खात्री झालेली आहे.

त्याअर्थी, मी, पांडुरंग पोले, मुख्य कार्यकारी अधिकारी, झोपडपट्टी पुनर्वसन प्राधिकरण, पुणे व पिंपरी-चिंचवड क्षेत्र, पुणे महाराष्ट्र झोपडपट्टी (सुधारणा निर्मूलन व पुनर्विकास) अधिनियम, १९७१ चे कलम ३-क (१) अन्वये मला प्राप्त झालेल्या अधिकारान्वये अनुसूचित नमूद केलेले क्षेत्र हे झोपडपट्टी पुनर्वसन क्षेत्र म्हणून घोषित करित आहे.

सदरच्या आदेशामुळे बाधित होणाऱ्या कोणत्याही व्यक्तीस आदेश प्रसिद्ध झाल्यापासून चार आठवड्यांच्या आत महाराष्ट्र झोपडपट्टी (सुधारणा, निर्मूलन व पुनर्विकास) अधिनियम, १९७१ च्या कलम ३-क (२) अन्वये शिखर तक्रार निवारण समिती, महाराष्ट्र शासन, झोपडपट्टी पुनर्वसन प्राधिकरण, प्रशासकीय इमारत, ४ था मजला, अनंत काणेकर मार्ग, स्टेशन रोड, बांद्रा (पूर्व), मुंबई-४०० ०५१ यांचेकडे अपील दाखल करता येईल आणि उक्त अपीलावरील शिखर तक्रार निवारण समितीचा निर्णय अंतिम राहील.

अनुसूची

जमिनीचा तपशील	क्षेत्र
१	२
	चौ. मी.
स.नं. ५१, फा. प्लॉ. क्र. ५, मुळा रोड, संगमवाडी, शिवाजीनगर, पुणे.	४०६०.१०

चतुःसीमा

पूर्वेस.-- मुळा नदी.

पश्चिमेस.--लागू विद्यमान रस्ता.

दक्षिणेस.--फा. प्लॉ. नं. ५ पैकी निवासी सोसायटी.

उत्तरेस.-- स.नं. ५१ पै.

विकासकाचे नाव व संपूर्ण पत्ता : मे. अमर बालाजी कन्स्ट्रक्शन्स, सफल होम्स, "मनश्री", प्लॉट नं. ५८/५, डॉ. कलमाडी हायस्कूल समोर, डॉ. केतकर रोड, एरंडवणा, पुणे-४११ ००४.

सदरचा आदेश हा माझ्या सहीने व कार्यालयाच्या शिक्क्यासह देण्यात आली.

पांडुरंग पोले,

मुख्य कार्यकारी अधिकारी,
झोपडपट्टी पुनर्वसन प्राधिकरण,
पुणे व पिंपरी-चिंचवड क्षेत्र, पुणे.

पुणे, ३ ऑक्टोबर २०१८.

अध्यक्षा नगरपरिषद यांजकडून

विटा नगरपरिषद, विटा

महाराष्ट्र प्रादेशिक व नगररचना अधिनियम, १९६६ चे कलम ३७ अन्वये

क्रमांक वि.न.वि./३२३८/२०१८.--विटा शहर मंजूर विकास योजना (दुसरी सुधारित) महाराष्ट्र शासनाने नगरविकास विभागाकडील अधिसूचना क्रमांक टीपीएस/२००९/११३८/सीआर/१९६४/२००९/युडी-१३, दिनांक ३० ऑक्टोबर २००९ पासून अमलात आली आहे. विटा शहराच्या मूळ हद्दीच्या विकास योजनेमध्ये खालीलप्रमाणे फेरबदल करणेबाबत महाराष्ट्र प्रादेशिक व नगररचना अधिनियम, १९६६ चे कलम ३७ अन्वये विटा नगरपरिषदेने प्रस्तावित केलेले आहे.

परिशिष्ट

अ. क्र.	मंजूर विकास योजनेत दर्शविलेले आरक्षण/वापर	मंजूर विकास योजनेत करावयाचा बदल	कौन्सिल ठराव व दिनांक
१	२	३	४
१	नगरपरिषद हद्दीतील सि. स. नं. ४८७/७-ड व ४९८/९ मधील ०.६८ हेक्टर जागा आरक्षण क्रमांक १०६ (प्रायमरी स्कूल व प्ले ग्राऊंड) मध्ये समाविष्ट आहे.	नगरपरिषद हद्दीतील सि. स. नं. ४८७/७-ड व ४९८/९ मधील ०.६८ हेक्टर जागा आरक्षण क्रमांक १०६ (प्रायमरी स्कूल व प्ले ग्राऊंड) मध्ये समाविष्ट आहे. सदरचे आरक्षण वगळणे व जागा रहिवास विभागात समाविष्ट करणे.	कौन्सिल ठराव नंबर ३५, दिनांक ६ जून २०१८.

विटा शहराच्या मूळ हद्दीच्या विकास आराखड्यात करावयाचे वरील नियोजित फेरबदल दर्शविणारे नकाशे विटा नगरपरिषदेच्या बांधकाम विभाग कार्यालयात कामकाजाच्या दिवशी कार्यालयीन वेळेत नागरिकांना पहावयास मिळतील. विटा शहराच्या मूळ हद्दीच्या विकास आराखड्यात करावयाच्या उपरोक्त फेरबदलाच्या अनुषंगाने ज्या नागरिकांना सूचना व हरकती नोंदविण्याच्या असतील अशा नागरिकांनी ती सूचना महाराष्ट्र शासनाच्या राजपत्रात प्रसिद्ध झाल्यापासून तीस दिवसांचे आत अध्यक्षा, विटा नगरपरिषद, विटा यांच्याकडे लेखी स्वरूपात सादर कराव्यात.

सौ. प्रतिभाताई वैभव पाटील,
नगराध्यक्षा,
विटा नगरपरिषद, विटा.

विटा, २७ जुलै २०१८.

BY PRESIDENT, VITA MUNICIPAL COUNCIL, VITA

Notification

The Maharashtra Regional and Town Planning Act, 1966 under Section 37

क्रमांक वि.न.वि./३२३८/२०१८.--Vita City approved Development Plan (Second Revised) Maharashtra Government Notice No Urban Development Department No. TPS/2009/1138/CR/1964/2009/UD-13, has been inforce since 30th October 2009 Regarding changes in cities development plan as Vita Regional and Town Planning Act, 1966 under Section 37.

Schedule

Sr. No.	The Development Plan approved reservation/use	Changes to be approved development plan	Council Resolution No. and Date
1	2	3	4
1	In second revised sanctioned Development Plan of Vita under R. S. No. 487/7-D and	In second revised sanctioned Development Plan of Vita under R.S.No. 487/7-D and 498/9 land 0.60	Council Resolution No. 35, dated 6th June 2018.

Schedule--contd.

1	2	3	4
	498/9 land 0.60 Ha. Are included in Reservation No. 106 (Primary School and Playground).	Ha. Are deleted in Reservation No. 106 (Primary School and Play-ground) and included in Residential Zone.	

The above modification proposed by Vita Municipal Council notice is hereby given that, if any suggestion or objection to proposed modification, he should inform the same in writing to the President of Vita Municipal Council, Vita within one month from the date of publication of this notice in Maharashtra Government Gazette. A plan showing the modification is available for inspection in the office of the Vita Municipal Council during office hours.

Mrs. PRATIBHA VAIBHAV PATIL,

President,

Vita Municipal Council, Vita.

Vita, 27th July 2018.

विटा नगरपरिषद, विटा

महाराष्ट्र प्रादेशिक व नगररचना अधिनियम, १९६६ चे कलम ३७ अन्वये

क्रमांक वि.न.वि./३२३९/२०१८.--विटा शहर मंजूर विकास योजना (दुसरी सुधारित) महाराष्ट्र शासनाने नगरविकास विभागाकडील अधिसूचना क्रमांक टीपीएस/२००९/११३८/सीआर/१९६४/२००९/युडी-१३, दिनांक ३० ऑक्टोबर २००९ पासून अमलात आली आहे. विटा शहराच्या मूळ हद्दीच्या विकास योजनेमध्ये खालीलप्रमाणे फेरबदल करणेबाबत महाराष्ट्र प्रादेशिक व नगररचना अधिनियम, १९६६ चे कलम ३७ अन्वये विटा नगरपरिषदेने प्रस्तावित केलेले आहे.

परिशिष्ट

अ. क्र.	मंजूर विकास योजनेत दर्शविलेले आरक्षण/वापर	मंजूर विकास योजनेत करावयाचा बदल	कौन्सिल ठराव व दिनांक
१	२	३	४
१	नगरपरिषद हद्दीतील सि. स. नं. ५२४० मधील १८.६० गुंठे जागा आरक्षण क्रमांक ६७ (बगीचा) मध्ये समाविष्ट आहे.	नगरपरिषद हद्दीतील सि. स. नं. ५२४० मधील १८.६० गुंठे जागा आरक्षण क्रमांक ६७ (बगीचा) मध्ये समाविष्ट आहे. सदरचे आरक्षण वगळणे व जागा रहिवास विभागात समाविष्ट करणे.	कौन्सिल ठराव नंबर ६८, दिनांक ६ ऑगस्ट २०१८.

विटा शहराच्या मूळ हद्दीच्या विकास आराखड्यात करावयाचे वरील नियोजित फेरबदल दर्शविणारे नकाशे विटा नगरपरिषदेच्या बांधकाम विभाग कार्यालयात कामकाजाच्या दिवशी कार्यालयीन वेळेत नागरिकांना पहावयास मिळतील. विटा शहराच्या मूळ हद्दीच्या विकास आराखड्यात करावयाच्या उपरोक्त फेरबदलाच्या अनुषंगाने ज्या नागरिकांना सूचना व हरकती नोंदविण्याच्या असतील अशा नागरिकांनी ती सूचना महाराष्ट्र शासनाच्या राजपत्रात प्रसिद्ध झाल्यापासून तीस दिवसांचे आत अध्यक्षा, विटा नगरपरिषद, विटा यांच्याकडे लेखी स्वरूपात सादर कराव्यात.

सौ. प्रतिभाताई वैभव पाटील,

नगराध्यक्षा,

विटा नगरपरिषद, विटा.

विटा, २७ सप्टेंबर २०१८.

BY PRESIDENT, VITA MUNICIPAL COUNCIL, VITA**Notification***The Maharashtra Regional and Town Planning Act, 1966 under Section 37*

क्रमांक वि.न.वि./३२३९/२०१८.-Vita City approved Development Plan (Second Revised) Maharashtra Government Notice No. Urban Development Department No. TPS/2009/1138/CR/1964/2009/UD-13, has been inforce since 30th October 2009 Regarding changes in cities development plan as Vita Regional and Town Planning Act, 1966 under Section 37.

Schedule

Sr. No.	The Development Plan approved reservation/use	Changes to be approved development plan	Council Resolution No. and Date
1	2	3	4
1	In second revised sanctioned Development Plan of Vita under R. S. No. 5240 land 18.60 Gunthe are included in Reservation No. 67 (Garden)	In second revised sanctioned Development Plan of Vita under R.S.No. 5240 land 18.60 Gunthe are deleted in Reservation No. 67 (Garden).	Council Resolution No. 68, dated 6th August 2018.

The above modification proposed by Vita Municipal Council notice is hereby given that, if any suggestion or objection to proposed modification, he should inform the same in writing to the President of Vita Municipal Council, Vita within one month from the date of publication of this notice in Maharashtra Government Gazette. A plan showing the modification is available for inspection in the office of the Vita Municipal Council during office hours.

Mrs. PRATIBHA VAIBHAV PATIL,
President,
Vita Municipal Council, Vita.

Vita, 27th September 2018.

पोलीस उपआयुक्त (वाहतूक) यांजकडून**आदेश**

क्रमांक पोउआ/वाहतूक/७१/२०१८.- ज्याअर्थी, पुणे शहरातील खालील ठिकाणी वाहतूक सुरक्षित व सुरळीतपणे चालणे इष्ट आहे, त्याअर्थी, महाराष्ट्र शासन, गृह विभाग क्रमांक एमव्हीए-०१९६/८७१/सीआर-३७/टीआरए-२, दिनांक २७ सप्टेंबर १९९६ चे नोटिफिकेशननुसार मोटार वाहन कायदा, कलम ११५, ११६ (१), (ए), (बी), ११६ (४) आणि ११७ अन्वये मला प्राप्त झालेल्या अधिकाऱ्यांचा वापर करून तसेच प्राप्त हरकती व सूचनांचा विचार करून मी, तेजस्वी सातपुते, पोलीस उपआयुक्त, वाहतूक नियंत्रण शाखा, पुणे शहर, अत्यावश्यक सेवेतील वाहने (उदा. फायर ब्रिगेड, पोलीस वाहने, रुग्णवाहिका इत्यादी) खेरीज करून खालीलप्रमाणे अंतिम आदेश निर्गमित करित आहे. सदर ठिकाणी यापूर्वी पार्किंगबाबत असलेले निर्बंध रद्द समजण्यात येतील.

चतुःशृंगी वाहतूक विभाग, पुणे अंतर्गत

(१) सेनापती बापट रोड लगत रत्ना हॉस्पिटल समोरील लेनमध्ये गिरिधर बंगला ते साई मंदिर या येणारे रस्त्यावर नो-पार्किंग करण्यात येत आहे.

(२) दौलत गणपत मंगळवेढेकर चौक ते गिरिधर बंगल्यासमोरील डीपीपर्यंत समांतर पार्किंग करण्यात येत आहे.

तेजस्वी सातपुते,
पोलीस उपआयुक्त,
वाहतूक शाखा, पुणे शहर, पुणे.

पुणे, ३१ ऑगस्ट २०१८.

कार्यकारी अभियंता यांजकडून

अनुसूची--चालू

प्रकटन - ३

महाराष्ट्र सिंचन पद्धतीचे शेतकऱ्यांकडून व्यवस्थापन कायदा, २००५
(पाहा नियम ३.०)

अधिसूचना-३

क्रमांक भीवि-२/प्रशा-४/३७६२/२०१८.-ज्याअर्थी, महाराष्ट्र सिंचन पद्धतीचे शेतकऱ्यांकडून व्यवस्थापन कायदा, २००५ चे कलम ५.०, ६.०, ७.० व नियम क्रमांक ३.० नुसार असा निर्णय झाला आहे की, कालवा पाणीवापर संस्थांचे जलशास्त्रीय व प्रशासकीय सोईच्या दृष्टीने कार्यक्षेत्र निश्चिती करण्यासाठी मी, नारायण वासुदेव जोशी, कार्यकारी अभियंता, भीमा विकास विभाग क्रमांक २, सोलापूर खालीलप्रमाणे पाणीवापर संस्थांच्या अद्ययावत नकाशांच्या प्रमाणित प्रती, जमीनधारक आणि/किंवा कब्जेदार यांच्या नावाच्या याद्या ग्रामपंचायत कार्यालय, सिंचन शाखा, उपविभागीय कार्यालय, तहसीलदार कार्यालय आणि इतर महत्वाच्या सार्वजनिक ठिकाणी सूचना फलकावर माहितीसाठी प्रसिद्धी करीत आहे.

मी, नारायण वासुदेव जोशी, कार्यकारी अभियंता, असेही जाहीर करतो की, यापुढे कोणीही समुचित प्राधिकरणातर्फे कोणाही वैयक्तिक जमीनधारकाला किंवा कब्जेदार यांचे जमिनीस पाणी पुरविले जाणार नाही आणि सिंचन पद्धतीचे शेतकऱ्यांकडून व्यवस्थापन याखाली येणाऱ्या जमिनीच्या सर्व धारकांवर व भोगवटाधारकांवर पाणीवापर संस्थेमार्फत पाणीपुरवठा घेणे बंधनकारक असेल.

या प्रकटनामुळे बाधित झालेल्या कोणत्याही व्यक्तीस हे प्रकटन महाराष्ट्र शासन राजपत्रात प्रसिद्ध झाल्यापासून ३० दिवसांच्या आत अधीक्षक अभियंता व प्रशासक लाभक्षेत्र विकास प्राधिकरण, सोलापूर यांचेकडे अपील दाखल करता येईल.

सिंचन प्रकल्पाचे नाव : भीमा-उजनी प्रकल्प

कालव्याचे नाव : उजनी डावा कालवा

पाणीवापर संस्थेचे नाव : प्रस्तावित जलदेवता कालवा पाणीवापर संस्था, पांढरेवाडी, तालुका पंढरपूर, जिल्हा सोलापूर

उजनी डावा कालवा वितरिका क्रमांक ३६, सा. क्र. ८३/००० वरील मायनर क्रमांक १ व २, सरळदारे उजवा क्रमांक १ ते ७, सरळदारे डावे क्रमांक १ ते १३

अनुसूची

जिल्हा सोलापूर, तालुका पंढरपूर

गट नंबर	क्षेत्र
१	२
	हे. आर
गाव पांढरेवाडी	
६/१.	०.६०
१३/२/अ/२	०.३०

गट नंबर	क्षेत्र
१	२
	हे. आर
गाव पांढरेवाडी--चालू	
१५	०.८०
१७/१	१.१०
१७/२	१.६०
१८	१.४०
२१/१	२.१०
२१/१/१	०.८०
२१/१/२	१.४०
२१/२	१.२०
२७/अ/४	०.१०
३६३/ब/२	१.००
३८७	१.६०
३८८/१	१.६०
३८८/अ/१/२/२	१.६०
३८८/अ/२	१.१०
३८८/ब	१.२०
३८८/ब/१	०.६०
३८९/अ/१	०.४०
३८९/अ/३	१.१०
३८९/ब/२	०.१०
३९०/१	३.२०
३९०/२	१.१०
३९१/१	१.४०
३९१/२	०.३०
३९१/३	२.६०
३९३/२	०.६०
३९४/१	१.४०
३९४/२/अ/२	०.६०
३९४/२/ब	१.४०
३९५ पै.	०.७०
३९५ पै.	२.२०
३९७	०.६०
३९८/१	३.४०
३९९/१	२.२०
३९९/२ पै.	०.२०

अनुसूची--चालू		अनुसूची--चालू	
गट नंबर १	क्षेत्र २ हे. आर	गट नंबर १	क्षेत्र २ हे. आर
गाव पांढरेवाडी--चालू		गाव पांढरेवाडी--चालू	
४०१/अ/१	०.८०	४२२/३	१.००
४०१/अ/२	०.६०	४२२/४	०.३५
४०१/अ/अ	१.८०	४२६/१	०.२१
४०१/ब	०.२०	४२६/२	०.५०
४०२	०.५०	४२८/२	०.३०
४०३/२	०.२०	४३०/१/अ	१.६०
४०४/१/२	०.२०	४३०/अ/१/अ	१.५०
४०४/४	०.४०	४३०/अ/१/ब	१.००
४०४/अ/१	०.४०	४३०/अ/२/अ	०.८०
४०४/अ/२	०.५०	४३०/अ/२/ब	०.८०
४०४/ पै.	०.४०	४३०/ब/२	०.६०
४०६	१.४०	४३१/अ	०.८०
४०७/अ पै.	०.५०	४३१/ब	०.८०
४०७/अ/२	०.४०	४३१/ब पै.	०.८०
४०८/१/अ	०.८०	४३२	१.२०
४०८/१/ब	१.२०	४३३	०.६०
४०८/२	०.३०	४३३/ पै.	१.४५
४०९/२/अ/१	०.३०	४३४/ पै.	१.००
४१०/१	०.६०	४३४ पै.	१.१०
४११/२	०.६०	४३६/१ पै.	१.६०
४१२	२.१०	४३६/१/ब/ पै.	१.३०
४१२/२ पै.	१.६०	४३६/२/अ/१	२.२०
४१२/अ/२	०.४०	४३६/२/अ/२	२.५७
४१३	०.४०	४३६/२/ब/१	१.००
४१३/१/ब	०.७०	४३६/२/ब/१/२	१.२०
४१७/१	१.७०	४३६/२ पै.	१.२०
४१८/अ/२	०.६०	४३६/ब/२	१.४०
४१८/ब	०.३०	४३६ पै.	१.३०
४२० पै.	१.४०	४४०	२.२०
४२१/१	०.६०	४४१	२.२०
४२१/३	१.००	४४२/१	०.२०
४२१/ पै.	०.८६	४४२/१/अ	०.२०
४२२/१	०.५०	४४२/१/ब	०.२०
४२२/२	०.७०	४४२/१/ब/१	०.८०

अनुसूची--चालू		अनुसूची--चालू	
गट नंबर	क्षेत्र	गट नंबर	क्षेत्र
१	२	१	२
	हे. आर		हे. आर
गाव पांढरेवाडी--चालू		गाव पांढरेवाडी--चालू	
४४२/२	१.००	४८१/२	३.४०
४४३/२	०.७०	४८१/२ पै.	१.३०
४४४	१.१०	४८२	०.७०
४४५	२.२०	४८२/१	०.६५
४४६/२/३ पै.	१.३०	४८२/१/२	१.३०
४४६/२/४	०.८१	४८२/१/३	०.६५
४४६/२/२ पै.	०.६०	४८२/२	०.६०
४४७/१	२.४०	४८२/२/३	०.५०
४४७/२	०.५०	४८२/२/४	०.६०
४४८/१	२.३०	४८२/२ पै.	०.१०
४४८/२	०.५०	४८३	०.३०
४५७	१.४०	४८४/१	३.९०
४५८	३.४०	४८४/२	१.६०
४५९/१	१.२०	४८४/२/ पै.	१.४५
४५९/२	१.००	४८४/३ पै.	०.५०
४६०/१	०.२०	४८५/१	१.१०
४६०/२	२.००	४८५/२	१.००
४६०/२ पै.	२.००	४८५/३/१	०.६०
४६०/४	०.३५	४८५/३/२	०.५०
४६०/४ पै.	०.३०	४८६/१	२.३०
४६१	१.००	४८६/२	३.१०
४६२/१	१.१०	४८६/२	१.१०
४६३/१	१.२०	४८७ पै.	०.१०
४६३/ पै.	०.७०	४८८/१	१.१०
४६४/१	१.४०	४८८/२	१.१०
४६५/१/१	०.८०	४८९	०.७०
४६५/१/२	०.८०	४९०/१/१	०.८०
४६५/१/३	०.६०	४९०/१/२	०.७०
४६६	०.६०	४९०/१/३	०.८०
४६६/२	०.२०	४९०/२/अ/२	०.८०
४६९/१	१.२०	४९०/२/ब	०.६०
४६९/२/१	०.६०	४९०/२/ब/१	०.७०
४६९/२/२	०.६०	४९१/१	२.२०
४८१/१	३.२०	४९१/१/अ	०.१०

अनुसूची--चालू		अनुसूची--चालू	
गट नंबर १	क्षेत्र २ हे. आर	गट नंबर १	क्षेत्र २ हे. आर
गाव पांढरेवाडी--चालू		गाव भोसे--चालू	
४९१/१/ब	०.१०	३८९/अ/४	०.१०
४९१/२	१.१०	३८९/ब/१ पै.	१.५०
४९१/२ पै.	०.७०	३८९/ब/१	१.१०
४९१/३	१.६०	४०४/४	०.५०
४९२/अ/२	१.१०	४१३/१	१.१०
४९३/२	०.५०	४१३/पै./१	०.२०
४९३/३	१.६०	४१४	०.७०
४९४/२/अ	१.१०	४१५	१.००
४९४/२/अ/१	०.३०	४१६	०.८०
४९४/अ/२	१.१०	४२१	०.६०
४९५	०.६०	४३२	१.४०
४९६/१/अ	०.७०	४३३/५/२/अ	०.६०
४९६/१/ब	०.२०	४३३/५/२/ब	०.६०
४९७/१/अ	२.२०	६२३	०.१०
४९७/१/ब	१.४०	६२४	२.८५
४९७/२	१.८०	६२४/१/अ	०.५०
४९७/३	१.७०	६२४/१/ब	०.१०
४९९/२	१.२०	६२४/२	१.१०
५०३/१/ब	०.६०	६२६	२.५०
५०३/१ पै.	०.४०	६२८	२.४०
५०३/अ/२	२.६०	६२९/१	०.२०
५०४	०.८५	६२९/२	१.३०
५०७	०.३०	६२९/३	०.२०
५१०	०.१०	६३१/२/अ	२.१०
५१३ पै.	१.२०	६३१/४/ब	०.६०
एकूण		६३१/५	१.३०
गाव भोसे		६३२/१	१.१०
८६	१.००	६३२/२	०.६०
९५/२	२.४०	६३३	०.८०
९५/२/ब	२.१०	६३४	०.८०
९६/१	२.४०	६३४/२	०.४०
९६/ब	१.१०	६५४/१/अ	२.१०
१५१/ब	१.४०	६५४/१/ब	२.१०
३३४/१	०.२०	६५४/२	३.४०

अनुसूची--चालू		अनुसूची--चालू	
गट नंबर	क्षेत्र	गट नंबर	क्षेत्र
१	२	१	२
	हे. आर		हे. आर
गाव भोसे--चालू		गाव भोसे--चालू	
६५५	१.२०	७४३/ब	१.६०
६५६	०.८०	७६६	१.००
६५७/१/ब	०.६०	७६८	०.६०
६५९/अ	०.६०	७९५	१.१०
६६७	४.१०	७९६	२.५०
६६८	१.४०	७९८	१.२०
६७४/१/२	१.१०	७९९/१	१.१०
६७४/१/३	१.१०	८२०/२	०.४५
६७४/२/१	०.५०	एकूण	९१.१५
६७४/२/२	०.१०		
६७४/२/३	०.१०	गाव चिलाईवाडी	
६७४/२/४	०.१०	६१/अ/२	१.६०
६७४/२/५	०.३०	६२/२/अ/१	०.५०
६७४/२/६	०.२०	६२/२/अ/१/१	०.३०
६७४/३	१.८०	६२/२/ब/१/२	०.३०
६८६/१	२.२०	६२/२/ब/२/ब/२	०.३०
६८६/२	०.६०	७१/२/ पै.	१.००
६८६/३	१.४५	७१/अ/१/१	१.१०
६८६/४	०.६०	७१/अ/१/२/१	१.००
६८७/३	१.६०	७१/अ/१/अ/२	०.५०
६८८	१.२०	७१/अ/१/ब/१/१	०.५०
६८८/१/२	०.६०	७१/अ/१/ब/२/२	१.१०
६८८/४	०.६०	७१/ब/१	०.२०
६८८/५	०.६०	७१ पै.	०.२०
६८८/६	०.६०	७२/१	१.३०
७१३/१	१.६०	७२/२	१.१०
७१६/३	१.२०	७२/३	१.२०
७१९/२	०.५०	७२/अ	०.२०
७१९/२	०.८०	७३/१/ब	०.२०
७२०	०.८०	७३/२	१.१०
७२४	१.८०	७४	१.४०
७३५/२	१.२०	७५/१/२	०.४०
७४१/१	१.२०	७५/अ/५	०.२०
७४२ पै.	१.१०	७५/ब	०.६०
		७६/१	०.५०

अनुसूची--चालू		अनुसूची--चालू	
गट नंबर	क्षेत्र	गट नंबर	क्षेत्र
१	२	१	२
	हे. आर		हे. आर
गाव चिलाईवाडी--चालू		गाव चिलाईवाडी--चालू	
७६/१/१/अ	०.४०	१०३/अ/३	०.८०
७६/अ/१	१.१०	१०४/२/अ	१.४०
७६/ब	०.६०	१०४/२/ब	०.६०
७७	२.१०	१०५/२/ब	०.६०
७८/२/२	०.१०	१०५/पै.	०.३०
७९/१/२/ब	०.३०	६५९/अ	०.६०
७९/१/ पै.	०.१०	७६६	१.००
८१	०.४०	७६८	०.६०
८२	१.२०	७९५	१.१०
८२/ब/१	०.६०	७९६	२.५०
८४	१.१४	९५१/२/अ पै.	०.६०
८५/२	१.१०	एकूण	६७.२०
८६	२.४०		
८७/१	१.१०	गोषवारा	
९०	१.३०	गाव	क्षेत्र
९१	१.१०	पांढरेवाडी	२०५.८०
९३	२.४०	भोसे	९१.१५
९३/२	१.३०	चिलाईवाडी	६७.२०
९४/अ	०.३०	एकूण	३६४.१५
९४/ब	१.५०		
९५/२/ब	२.१०	नारायण वासुदेव जोशी,	
९५/२	२.४०		
९६/१	२.४०	कार्यकारी अभियंता,	
९६/२/अ/पै.	०.८०	भीमा विकास विभाग, क्रमांक २,	
९६/३/ब/२	१.२०	जिल्हा सोलापूर.	
९६/४	१.८०	सोलापूर, २५ सप्टेंबर २०१८.	
९६/अ/२/ब	०.९०		
९६/ब	१.२०	MMISF ACT, 2005	
९९/२/ब/२	०.६०		
१०१	२.६०	(See Sections 5.0, 6.0, 7.0 and	
१०१/१	०.७०	Rule 3.00)	
१०२	०.८६	(Notification III)	
१०२ पै.	०.७०	क्रमांक भीवि-२/प्रशा-४/३७६२/२०१८.—Whereas, it has	
१०३/अ/२	१.५०		
		been decided to delineate the Area of Operation	
		of Water User Associations (WUAs) on	
		Hydraulic basis and as per Administrative	
		Convenience under Sections 5.0, 6.0, 7.0 and	

Rule 3 of the MMISF Act, 2005 I, Narayan Vasudeo Joshi, Executive Engineer, Bhima Development Division No. 2, Solapur hereby delineate areas of Operation of following WUA's and direct that the certified copy of the updated map and list of landholders and/or occupiers of said WUA's shall be displayed on the notice board of the concerned Grampanchayat, Tahasil office, Irrigation Sections, Sub-Division and other prominent public places.

I, Narayan Vasudeo Joshi, Executive Engineer, Bhima Development Division No.2, Solapur also hereby declare that no water shall be supplied by the Appropriate Authority to an individual or occupier of such land and the system of supply of water through Water User Associations shall be binding on all the holders and occupiers of the lands under Maharashtra Management Irrigation System by Farmers.

Any Person affected by this Notification or part thereof, may file an appeal before Superintending Engineer, Command Area Development Authority, Solapur within 30 days from the date of Publication of this Notification in the Maharashtra Government Gazette.

Name of Project : Bhima (Ujjani) Project, Ujjani Left Bank Canal

Name of WUA : Proposed Jaldevata WUA, Pandharewadi, Dy. 36, Minor 1 and 2, Direct Outlet (Right Side) 1 to 7, Direct Outlet (Left Side) 1 to 7

Schedule

District Solapur, taluka Pandharpur

Gat Nos. 1	Area 2 Ha.
---------------	------------------

Village Pandharewadi

6/1.	0.60
13/2/A/2	0.30
15	0.80
17/1	1.10
17/2	1.60
18	1.40
21/1	2.10
21/1/1	0.80
21/1/2	1.40
21/2	1.20
27/A/4	0.10

Schedule—contd.

Gat Nos. 1	Area 2 Ha.
---------------	------------------

Village Pandharewadi—contd.

363/B/2	1.00
387	1.60
388/1	1.60
388/A/1/2/2	1.60
388/A/2	1.10
388/B	1.20
388/B/1	0.60
389/A/1	0.40
389/A/3	1.10
389/B/2	0.10
390/1	3.20
390/2	1.10
391/1	1.40
391/2	0.30
391/3	2.60
393/2	0.60
394/1	1.40
394/2/A/2	0.60
394/2/B	1.40
395Part	0.70
395 Part	2.20
397	0.60
398/1	3.40
399/1	2.20
399/2Part	0.20
401/A/1	0.80
401/A/2	0.60
401/A/A	1.80
401/B	0.20
402	0.50
403/2	0.20
404/1/2	0.20
404/4	0.40
404/A/1	0.40
404/A/2	0.50
404/Part	0.40
406	1.40
407/A Part	0.50
407/A/2	0.40

Schedule—contd.

Gat Nos. 1	Area 2 Ha.
Village Pandharewadi—contd.	
408/1/A	0.80
408/1/B	1.20
408/2	0.30
409/2/A/1	0.30
410/1	0.60
411/2	0.60
412	2.10
412/2 Part	1.60
412/A/2	0.40
413	0.40
413/1/B	0.70
417/1	1.70
418/A/2	0.60
418/B	0.30
420 Part	1.40
421/1	0.60
421/3	1.00
421/Part	0.86
422/1	0.50
422/2	0.70
422/3	1.00
422/4	0.35
426/1	0.21
426/2	0.50
428/2	0.30
430/1/A	1.60
430/A/1/A	1.50
430/A/1/B	1.00
430/A/2/A	0.80
430/A/2/B	0.80
430/B/2	0.60
431/A	0.80
431/B	0.80
431/B Part	0.80
432	1.20
433	0.60
433/Part	1.45
434/Part	1.00
434 Part	1.10

Schedule—contd.

Gat Nos. 1	Area 2 Ha.
Village Pandharewadi—contd.	
436/1 Part	1.60
436/1/B/Part	1.30
436/2/A/1	2.20
436/2/A/2	2.57
436/2/B/1	1.00
436/2/B/1/2	1.20
436/2 Part	1.20
436/B/2	1.40
436 Part	1.30
440	2.20
441	2.20
442/1	0.20
442/1/A	0.20
442/1/B	0.20
442/1/B/1	0.80
442/2	1.00
443/2	0.70
444	1.10
445	2.20
446/2/3 Part	1.30
446/2/4	0.81
446/2/2Part	0.60
447/1	2.40
447/2	0.50
448/1	2.30
448/2	0.50
457	1.40
458	3.40
459/1	1.20
459/2	1.00
460/1	0.20
460/2	2.00
460/2 Part	2.00
460/4	0.35
460/4Part	0.30
461	1.00
462/1	1.10
463/1	1.20
463/Part	0.70

Schedule—contd.

Gat Nos.	Area
1	2
	Ha.

Village Pandharewadi—contd.

464/1	1.40
465/1/1	0.80
465/1/2	0.80
465/1/3	0.60
466	0.60
466/2	0.20
469/1	1.20
469/2/1	0.60
469/2/2	0.60
481/1	3.20
481/2	3.40
481/2Part	1.30
482	0.70
482/1	0.65
482/1/2	1.30
482/1/3	0.65
482/2	0.60
482/2/3	0.50
482/2/4	0.60
482/2Part	0.10
483	0.30
484/1	3.90
484/2	1.60
484/2/Part	1.45
484/3 Part	0.50
485/1	1.10
485/2	1.00
485/3/1	0.60
485/3/2	0.50
486/1	2.30
486/2	3.10
486/2	1.10
487 Part	0.10
488/1	1.10
488/2	1.10
489	0.70
490/1/1	0.80
490/1/2	0.70
490/1/3	0.80

Schedule—contd.

Gat Nos.	Area
1	2
	Ha.

Village Pandharewadi—contd.

490/2/A/2	0.80
490/2/B	0.60
490/2/B/1	0.70
491/1	2.20
491/1/A	0.10
491/1/B	0.10
491/2	1.10
491/2 Part	0.70
491/3	1.60
492/A/2	1.10
493/2	0.50
493/3	1.60
494/2/A	1.10
494/2/A/1	0.30
494/A/2	1.10
495	0.60
496/1/A	0.70
496/1/B	0.20
497/1/A	2.20
497/1/B	1.40
497/2	1.80
497/3	1.70
499/2	1.20
503/1/B	0.60
503/1 Part	0.40
503/A/2	2.60
504	0.85
507	0.30
510	0.10
513 Part	1.20
Total	
205.80	
Village Bhose	
86	1.00
95/2	2.40
95/2/B	2.10
96/1	2.40
96/B	1.10
151/B	1.40

Schedule—contd.

Gat Nos. 1	Area 2 Ha.
Village Bhose—contd.	
334/1	0.20
389/A/4	0.10
389/B/1 Part	1.50
389/B/1	1.10
404/4	0.50
413/1	1.10
413/Part/1	0.20
414	0.70
415	1.00
416	0.80
421	0.60
432	1.40
433/5/2/A	0.60
433/5/2/B	0.60
623	0.10
624	2.85
624/1/A	0.50
624/1/B	0.10
624/2	1.10
626	2.50
628	2.40
629/1	0.20
629/2	1.30
629/3	0.20
631/2/A	2.10
631/4/B	0.60
631/5	1.30
632/1	1.10
632/2	0.60
633	0.80
634	0.80
634/2	0.40
654/1/A	2.10
654/1/B	2.10
654/2	3.40
655	1.20
656	0.80
657/1/B	0.60
659/A	0.60

Schedule—contd.

Gat Nos. 1	Area 2 Ha.
Village Bhose—contd.	
667	4.10
668	1.40
674/1/2	1.10
674/1/3	1.10
674/2/1	0.50
674/2/2	0.10
674/2/3	0.10
674/2/4	0.10
674/2/5	0.30
674/2/6	0.20
674/3	1.80
686/1	2.20
686/2	0.60
686/3	1.45
686/4	0.60
687/3	1.60
688	1.20
688/1/2	0.60
688/4	0.60
688/5	0.60
688/6	0.60
713/1	1.60
716/3	1.20
719/2	0.50
719/2	0.80
720	0.80
724	1.80
735/2	1.20
741/1	1.20
742 Part	1.10
743/B	1.60
766	1.00
768	0.60
795	1.10
796	2.50
798	1.20
799/1	1.10
820/2	0.45
Total	91.15

Schedule—contd.

Gat Nos. 1	Area 2 Ha.
Village Chilaiwadi	
61/A/2	1.60
62/2/A/1	0.50
62/2/A/1/1	0.30
62/2/B/1/2	0.30
62/2/B/2/B/2	0.30
71/2/ Part	1.00
71/A/1/1	1.10
71/A/1/2/1	1.00
71/A/1/A/2	0.50
71/A/1/B/1/1	0.50
71/A/1/B/2/2	1.10
71/B/1	0.20
71 Part	0.20
72/1	1.30
72/2	1.10
72/3	1.20
72/A	0.20
73/1/B	0.20
73/2	1.10
74	1.40
75/1/2	0.40
75/A/5	0.20
75/B	0.60
76/1	0.50
76/1/1/A	0.40
76/A/1	1.10
76/B	0.60
77	2.10
78/2/2	0.10
79/1/2/B	0.30
79/1/ Part	0.10
81	0.40
82	1.20
82/B/1	0.60
84	1.14
85/2	1.10
86	2.40
87/1	1.10
90	1.30
91	1.10
93	2.40
93/2	1.30
94/A	0.30
94/B	1.50

Schedule—contd.

Gat Nos. 1	Area 2 Ha.
Village Chilaiwadi—contd.	
95/2/B	2.10
95/2	2.40
96/1	2.40
96/2/A/Part	0.80
96/3/B/2	1.20
96/4	1.80
96/A/2/B	0.90
96/B	1.20
99/2/B/2	0.60
101	2.60
101/1	0.70
102	0.86
102 Part	0.70
103/A/2	1.50
103/A/3	0.80
104/2/A	1.40
104/2/B	0.60
105/2/B	0.60
105/Part	0.30
659/A	0.60
766	1.00
768	0.60
795	1.10
796	2.50
951/2/A Part	0.60
Total	67.20

Abstract

Village	Area
Pandharewadi	205.80
Bhose	91.15
Chilaiwadi	67.20
Total	364.15

NARAYAN VASUDEO JOSHI,

Executive Engineer,
Bhima Development Division No. 2,
district Solapur.

Solapur, 25th September 2018.

अध्यक्षा, नगरपरिषद यांजकडून

बारामती नगरपरिषद, बारामती

महाराष्ट्र प्रादेशिक व नगररचना अधिनियम, १९६६ चे कलम ३७ (१) अन्वये बारामती नगरपरिषद विकास आराखडा (दुसरा सुधारित)

जाहीर नोटिस

क्रमांक बानप/कार्या-१५/१०७८/२०१८.--ज्याअर्थी, बारामती नगरपरिषदेच्या मंजूर विकास आराखडा (दुसरा सुधारित) महाराष्ट्र शासनाने नोटिफिकेशन नंबर टीपीएस-१८११/९४१/सीआर-२७४/११/डी.पी. मंजुरी/युडी-१३, दिनांक १२ एप्रिल २०१२ व ई.पी. मंजुरी आदेश नंबर १८१३/१०७०/सीआर-२८४/१३/युडी-१३, दिनांक ४ मार्च २०१४ अन्वये मंजूर करण्यात आलेला आहे ;

आणि आता. उपरोक्त मंजूर सुधारित विकास योजनेमध्ये खालीलप्रमाणे फेरफार करणेबाबत महाराष्ट्र प्रादेशिक व नगर रचना अधिनियम, १९६६ चे कलम ३७ अन्वये नगरपरिषदेने प्रस्तावित केलेले आहे.

परिशिष्ट

अ. क्र.	मंजूर विकास आराखडा सद्यःस्थिती	मंजूर विकास आराखड्यात करावयाचा फेरबदल	कौन्सिल ठराव नंबर व दिनांक
१	२	३	४
१	मंजूर विकास योजनेमध्ये सर्व्हे नंबर ३६ पैकी यामध्ये आरक्षण क्रमांक ४३, एस.टी.पी., क्षेत्र ०.२३ हेक्टर.	मंजूर विकास योजनेतील आरक्षण क्रमांक ४३ (क्षेत्र ०.२३ हेक्टर), एस.टी.पी. चे आरक्षण वगळून सदर क्षेत्रावर दफनभूमीसाठी आरक्षण ठेवणे.	सर्वसाधारण सभा क्रमांक ६, दिनांक २ ऑगस्ट २०१८, ठराव नंबर ६६.

बारामती शहराच्या सुधारित (दुसरा सुधारित) विकास आराखड्यात करावयाचे वरील नियोजित फेरफार दर्शविणारे नकाशे बारामती नगरपरिषदेच्या कार्यालयात कामकाजाच्या दिवशी कार्यालयीन वेळेत नागरिकांना पाहावयास मिळतील.

बारामती शहराच्या सुधारित (दुसरा सुधारित) विकास आराखड्यात करावयाच्या उपरोक्त फेरबदलासंबंधी कोणास सूचना व हरकती करावयाच्या असतील, तर त्यांनी ही सूचना महाराष्ट्र शासनाच्या राजपत्रात प्रसिद्ध झालेपासून एक महिन्याच्या आत अध्यक्ष, बारामती नगरपरिषद, बारामती यांचेकडे लेखी स्वरूपात दाखल कराव्यात.

पौर्णिमा तावरे,

अध्यक्षा,

बारामती नगरपरिषद, बारामती.

बारामती, २४ सप्टेंबर २०१८.

BY PRESIDENT

BARAMATI MUNICIPAL COUNCIL, BARAMATI

Modification to the Sanctioned Development Plan (Second Revised) of Baramati Municipal Council Provided under Section 37 of the Maharashtra Regional and Town Planning Act, 1966.

Notice

क्रमांक बानप/कार्या-१५/१०७८/२०१८.—Whereas, Maharashtra Government under Notification No. TPS-1811/941/6/CR-274/11/DP Sanction/UD-13, dated 12th April 2012 and E.P. Sanction Order No. 1813/1070/CR-284/13/UD-13, dated 4th March 2014 has sanctioned the revised (Second Development) Plan of Baramati Municipal Council ;

and, now Baramati Municipal Council under Section 37 (1) of Maharashtra Regional and Town Planning Act, 1966 Intends of make the following modification in the said sanctioned Development Plan.

Schedule

Sr. No.	Present Position	Proposed Modification	Council Resolution No. and Date
1	2	3	4
1	Sanctioned Development Plan included S. No. 36 (part), Reservation No. 43, S.T.P. Area 0.23 Hect.	Sanctioned Development S. No. 36 (pt.) Reservation No. 43, S.T.P. Area 0.23 Hect. S.T.P. Deleted and same Area Reserved for Burial Ground.	General Metting No. 6, dated 2nd August 2018, Resolution No. 66.

The plan showing the above proposed modification to the sanctioned Development Plan of the Baramati Municipal Council is available for inspection during working hours on all working days in Baramati Municipal Council.

Suggestions and objections if any to the above proposed modification to the sanctioned Development Plan of Baramati (Second Revised) shall be communicated in writing to the president Baramati Municipal Council within one month (30 days) from the date of publications of the notice in the Maharashtra Government Gazette.

POURNIMA TAWARE,

President,

Baramati Municipal Council,

Baramati.

Baramati, 24th September 2018.

पोलीस उपआयुक्त (वाहतूक) यांजकडून

आदेश

क्रमांक पोउआ/वाहतूक/७३/२०१८.- ज्याअर्थी, पुणे शहरातील खालील ठिकाणी वाहतूक सुरक्षित व सुरळीतपणे चालणे इष्ट आहे, त्याअर्थी, महाराष्ट्र शासन, गृह विभाग क्रमांक एमव्हीए-०१९६/८७१/सीआर-३७/टीआरए-२, दिनांक २७ सप्टेंबर १९९६ चे नोटिफिकेशननुसार मोटार वाहन कायदा, कलम ११५, ११६ (१), (ए), (बी), ११६ (४) आणि ११७ अन्वये मला प्राप्त झालेल्या अधिकाऱांचा वापर करून तसेच प्राप्त हरकती व सूचनांचा विचार करून मी, तेजस्वी सातपुते, पोलीस उपआयुक्त, वाहतूक नियंत्रण शाखा, पुणे शहर, अत्यावश्यक सेवेतील वाहने (उदा. फायर ब्रिगेड, पोलीस वाहने, रुग्णवाहिका इत्यादी) खेरीज करून खालीलप्रमाणे अंतिम आदेश निर्गमित करित आहे. सदर ठिकाणी यापूर्वी पार्किंगबाबत असलेले निर्बंध रद्द समजण्यात येतील.

येरवडा वाहतूक विभाग, पुणे अंतर्गत

बिशप स्कूल ते वडगाव शेरी या ब्रम्हा सनसिटी रोडवर सुमारे १०० मीटर अंतरापर्यंत रोडचे दक्षिण बाजूस ब्रम्हा सनसिटी भिंतीलगत नो पार्किंग व रोडचे उत्तर बाजूस श्री शिवाजी महाराज उद्यान भिंतीलगत वन साईड पार्किंग करणेत येत आहे.

पुणे, ३१ ऑगस्ट २०१८.

आदेश

क्रमांक पोउआ/वाहतूक/७२/२०१८.- ज्याअर्थी, पुणे शहरातील खालील ठिकाणी वाहतूक सुरक्षित व सुरळीतपणे चालणे इष्ट आहे, त्याअर्थी, महाराष्ट्र शासन, गृह विभाग क्रमांक एमव्हीए-०१९६/८७१/सीआर-३७/टीआरए-२, दिनांक २७ सप्टेंबर १९९६ चे नोटिफिकेशननुसार मोटार वाहन कायदा, कलम ११५, ११६ (१), (ए), (बी), ११६ (४) आणि ११७ अन्वये मला प्राप्त झालेल्या अधिकाऱांचा वापर करून तसेच प्राप्त हरकती व सूचनांचा विचार करून मी, तेजस्वी सातपुते, पोलीस उपआयुक्त, वाहतूक नियंत्रण शाखा, पुणे शहर, अत्यावश्यक सेवेतील वाहने (उदा. फायर ब्रिगेड, पोलीस वाहने, रुग्णवाहिका इत्यादी) खेरीज करून खालीलप्रमाणे अंतिम आदेश निर्गमित करित आहे. सदर ठिकाणी यापूर्वी पार्किंगबाबत असलेले निर्बंध रद्द समजण्यात येतील.

चतुःशृंगी वाहतूक विभाग, पुणे अंतर्गत

मुंबई-बेंगलोर हायवेखालील राधा चौकापासून पाषाणचे दिशेने जाताना रेनॉल्ट शोरूम व क्षितिज हॉटेलजवळील दुसरा अंडरपास येथे अंडरपासचे पूर्व व पश्चिम दोन्ही बाजूंनी चारचाकी वाहनांना मनाई करण्यात येत आहे.
पुणे, ३१ ऑगस्ट २०१८.

क्रमांक पोउआ/वाहतूक/७४/२०१८.- ज्याअर्थी, पुणे शहरातील खालील ठिकाणी वाहतूक सुरक्षित व सुरळीतपणे चालणे इष्ट आहे, त्याअर्थी, महाराष्ट्र शासन, गृह विभाग क्रमांक एमव्हीए-०१९६/८७१/सीआर-३७/टीआरए-२, दिनांक २७ सप्टेंबर १९९६ चे नोटिफिकेशननुसार मोटार वाहन कायदा, कलम ११५, ११६ (१), (ए), (बी), ११६ (४) आणि ११७ अन्वये मला प्राप्त झालेल्या अधिकांरांचा वापर करून तसेच प्राप्त हरकती व सूचनांचा विचार करून मी, तेजस्वी सातपुते, पोलीस उपआयुक्त, वाहतूक नियंत्रण शाखा, पुणे शहर, अत्यावश्यक सेवेतील वाहने (उदा. फायर ब्रिगेड, पोलीस वाहने, रुग्णवाहिका इत्यादी) खेरीज करून खालीलप्रमाणे अंतिम आदेश निर्गमित करीत आहे. सदर ठिकाणी यापूर्वी पार्किंगबाबत असलेले निर्बंध रद्द समजण्यात येतील.

येरवडा वाहतूक विभाग, पुणे अंतर्गत

कॉमरझोन चौक ते पंचशीलनगर रोडचे दोन्ही बाजूस २०० मीटर अंतरापर्यंत नो-पार्किंग झोन करणेत येत आहे.

तेजस्वी सातपुते,
पोलीस उपआयुक्त,
वाहतूक शाखा, पुणे शहर, पुणे.

पुणे, ३१ ऑगस्ट २०१८.

पुढील अधिसूचना असाधारण राजपत्र म्हणून खाली दर्शविलेल्या दिनांकास प्रसिद्ध झाल्या आहेत.

शनिवार, एप्रिल ०७, २०१८ / चैत्र १७, शके १९४०

नगर विकास विभाग

मंत्रालय, मुंबई-४०० ०३२

दिनांक २६ मार्च २०१८

महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६

अधिसूचना

क्रमांक टीपीएस-१८१७/१२४६/प्र.क्र. ४०/१८/नवि-१३.--ज्याअर्थी, शासनाने नगर विकास विभागाची अधिसूचना क्रमांक टीपीएस-१८१५/२२७/प्र.क्र. २६/१५/नवि-१३, दिनांक २५ नोव्हेंबर १९९७ अन्वये पुणे जिल्ह्याची प्रादेशिक योजना (यापुढे जिचा उल्लेख उक्त प्रादेशिक योजना असा करण्यात आला आहे.) महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ (यापुढे जिचा उल्लेख उक्त अधिनियम असा करण्यात आला आहे.) चे कलम १५ अन्वये मंजूर केली असून ती दिनांक १० फेब्रुवारी १९९८ पासून अंमलात आलेली असून उक्त प्रादेशिक योजनेत विकास नियंत्रण नियमावलीच्या तरतुदींचा समावेश करण्यात आलेला आहे;

आणि ज्याअर्थी, शासनाने उक्त प्रादेशिक योजनेतील पुणे व पिंपरी-चिंचवड महानगरपालिका हद्दी लागतच्या १० कि. मी. क्षेत्रासाठी विशेष नियमावली अधिसूचना क्रमांक टीपीएस-१८०९/६५०/प्र.क्र. १६५४/०९/नवि-१३, दिनांक २८ ऑगस्ट २००९ अन्वये मंजूर केली आहे;

आणि ज्याअर्थी, शासनाने राज्यातील सर्व मंजूर प्रादेशिक योजनांकरिता प्रमाणित विकास नियंत्रण व प्रोत्साहन नियमावली क्रमांक टीपीएस-१८१२/१५७/प्र.क्र. ७१/१२/पुनर्बांधणी क्रमांक ३४/१२/प्रा.यो/नवि-१३, दिनांक २१ नोव्हेंबर २०१३ अन्वये मंजूर केली असून ती दिनांक २१ नोव्हेंबर २०१३ पासून अंमलात आली आहे;

आणि ज्याअर्थी, महाराष्ट्र शासनाने दिनांक ३१ मार्च २०१५ ची अधिसूचना क्रमांक टीपीएस-१८१५/१२०४/१३/प्र.क्र. ८७/१५/नवि-१३ अन्वये उक्त अधिनियमाच्या कलम ४२-क, ४२-ग, व ४२-च अन्वये प्रदान केलेल्या शक्तीचा वापर करून पुणे महानगर क्षेत्रास, "पुणे महानगर विकास क्षेत्र" म्हणून उक्त अधिनियमाचे कलम ४२-क नुसार घोषित करून कलम ४२-ग नुसार या घोषित क्षेत्रासाठी पुणे महानगर प्रदेश क्षेत्र विकास प्राधिकरण गठित केले असून दिनांक ४ डिसेंबर २०१५ रोजीच्या अधिसूचनेद्वारे उक्त क्षेत्र विकास प्राधिकरणाची हद्द वाढवून सुधारित हद्दवाढ घोषित केली आहे. (यापुढे ज्याचा उल्लेख उक्त महानगर क्षेत्र असा करण्यात आला आहे);

आणि ज्याअर्थी, शासनाकडील दिनांक ३१ मार्च २०१५ ची अधिसूचना क्रमांक टीपीएस-१८१५/१२०४/१२/प्र.क्र. ८७/१५/नवि-१३ मधील (क) iii (क) मध्ये नमूद नुसार उक्त अधिनियमातील तरतुदीनुसार, जोपर्यंत उक्त प्राधिकरणाच्या क्षेत्रासाठी नव्याने विकास योजना तयार होत नाही तोपर्यंत पुणे जिल्ह्याच्या मंजूर प्रादेशिक योजनेचे प्रस्ताव त्या सोबतच्या विशेष नियमावलीसह तसेच प्रादेशिक योजनेकरिता मंजूर झालेली विकास नियंत्रण व प्रोत्साहनात्मक नियमावली तसेच त्यामधील वेळोवेळी लागू होणारे बदलासह लागू राहतील. (यापुढे जिचा उल्लेख "उक्त विकास नियंत्रण नियमावली" असा करण्यात आला आहे);

आणि ज्याअर्थी, महाराष्ट्र महानगर प्रदेश विकास प्राधिकरण अधिनियम, २०१६ मधील कलम ३ चे उप-कलम (१) मधील अधिकाराचा वापर करून नगर विकास विभागाकडील अधिसूचना क्रमांक पीआरडी-३३१६/प्र.क्र. ५४/नवि-७, दिनांक ११ जुलै २०१६ अन्वये उक्त महानगर क्षेत्रासाठी विशेष करून

त्या अधिसूचनेसोबत जोडलेल्या अनुसूचित नमूद केलेल्या क्षेत्राकरिता पुणे महानगर प्रदेश विकास प्राधिकरणाची स्थापना केलेली आहे (यापुढे जिचा निर्देश "उक्त विकास प्राधिकरण" असा करण्यात आला आहे);

आणि जाअर्थी, महाराष्ट्र शासन निर्णय क्रमांक टीपीएस-१८१७/प्र.क्र. १७३/१७/नवि-१३, दिनांक १८ जानेवारी २०१८ अन्वये उक्त विकास प्राधिकरणाची उक्त अधिनियमाचे कलम ४० (१) अन्वये विशेष नियोजन प्राधिकरण म्हणून उक्त महानगर क्षेत्रासाठी नियुक्त केलेली आहे;

आणि ज्याअर्थी, उक्त विकास प्राधिकरणास एकाच वेळी वेगवेगळे विनियम विचारात घ्यावे लागतात ही वस्तुस्थिती असल्यामुळे व तसेच विकास योजना तयार करण्यास काही कालावधी लागण्याची शक्यता असल्यामुळे विहित मुदतीमध्ये एक समार्क विकास नियंत्रण नियमावली तयार करून शासनास पुढील कार्यवाहीसाठी सादर करणेबाबत, नगर विकास विभागाने दिनांक २४ मे २०१६ व दिनांक १८ नोव्हेंबर २०१६ रोजीचे पत्र क्रमांक टीपीएस-१८१५/१४५/१५/प्र.क्र. ४५/१५/नवि-१३ अन्वये उक्त प्राधिकरणास निर्देश दिले व त्यानुसार उक्त प्राधिकरणाने पुणे महानगर विकास क्षेत्राच्या हद्दीकरिता सर्वकष सुधारित एक समार्क विकास नियंत्रण नियमावली तयार करून दिनांक १६ ऑगस्ट २०१७ रोजीचे पत्रान्वये शासनास पुढील कार्यवाहीसाठी सादर केलेली आहे;

आणि ज्याअर्थी, उक्त बाबी विचारात घेता व संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे यांचेशी विचार विनियम करून उक्त विकास नियंत्रण नियमावली पूर्णपणे बदलून त्याऐवजी सोबतची सुधारित विकास नियंत्रण नियमावली लागू करणे आवश्यक झाले असल्याचे शासनाचे मत झालेले आहे (यापुढे ज्यांचा उल्लेख "उक्त फेरबदल" असा करण्यात आला आहे.);

आणि ज्याअर्थी, आता उक्त अधिनियमाच्या कलम २० पोट-कलम (३) मधील तरतुदीप्रमाणे प्रस्तावित फेरबदल करण्याचा हेतू शासन याद्वारे घोषित करीत असून प्रस्तावित फेरबदलाच्या अनुषंगाने काही सूचना/हरकती द्यावयाच्या असतील तर त्या नागरिकांनी ही सूचना महाराष्ट्र शासन राजपत्रात प्रसिद्ध झाल्याच्या दिनांकापासून ३० (तीस) दिवसांच्या आत महानगर आयुक्त, पुणे महानगर प्रदेश विकास प्राधिकरण, औंध, पुणे-४११ ००७ यांचे नावे लेखी स्वरूपात पाठवाव्यात. प्राप्त होणाऱ्या सूचना/हरकतीवर सुनावणी देणेसाठी व त्यावरील अहवाल शासनास सादर करण्यासाठी महानगर आयुक्त, पुणे महानगर प्रदेश विकास प्राधिकरण, पुणे यांना प्राधिकृत करण्यात येत आहे. प्रस्तावित फेरबदलाची नोटिस महाराष्ट्र शासनाच्या राजपत्रात प्रसिद्ध झाल्यापासून ३० (तीस) दिवसांच्या आत प्राधिकृत अधिकारी यांचेकडे प्राप्त झालेल्या सूचना/हरकतींचाच शासनाकडून विचार केला जाईल. उक्त फेरबदल उक्त अधिनियमाच्या कलम २० (४) अन्वये मंजूर केलेल्या दिनांकापासून लागू होईल.

प्रस्तुतची सूचना तसेच प्रस्तावित फेरबदल दर्शविणाऱ्या नियमावलीचा संघ नागरिकांच्या अवलोकनार्थ कामकाजाच्या दिवशी कार्यालयीन वेळेत खालील कार्यालयात उपलब्ध करण्यात यावा.

- (१) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- (२) महानगर आयुक्त, पुणे महानगर प्रदेश विकास प्राधिकरण, पुणे.
- (३) सहसंचालक, नगररचना, पुणे विभाग, पुणे.

सदर अधिसूचना शासनाच्या www.maharashtra.gov.in (कायदे व नियम) या संकेतस्थळावर प्रसिद्ध करण्यात आली आहे.

महाराष्ट्राचे राज्यपाल यांच्या आदेशानुसार व नावाने,

रा. म. पवार,

अवर सचिव, महाराष्ट्र शासन.

URBAN DEVELOPMENT DEPARTMENT

Mantralaya, Mumbai-400 032

dated 26th March 2018

Maharashtra Regional and Town Planning Act, 1966

Notification

No. TPS-1817/1246/CR-40/18/UD-13.—Whereas, the Regional Plan of "Pune District" (hereinafter referred to as "the said Regional Plan") has been sanctioned u/s-15 of Maharashtra Regional and Town Planning Act 1966 (hereinafter referred to as "the said Act") by Government in Urban Development Department vide its Notification No. TPS-1895/227/CR-26/95/UD-13, Dated- 25th November 1997 and has come into force with effect from 10th February 1998, which includes the provisions of the Development Control Regulations;

And whereas, the special regulations for the areas within 10 Km. distance from boundaries of Pune and Pimpri-Chinchwad Municipal Corporation has been sanctioned by Government vide its Notification No. TPS-1809/650/CR-1654/09/UD-13, Dated-28th August 2009;

And whereas, State Government has sanctioned the standardized development control and promotion Regulations for Regional Plan Areas in Maharashtra *vide* its Notification No. TPS-1812/157/CR-71/12/ Reconstruction No. 34/12/RP/UD-13, Dated-21st November 2013 and has come into force with effect from 21st November 2013;

And whereas, the Government of Maharashtra, *vide* Notification No. TPS/1204/13/CR-87/15/UD-13, dated the 31st March 2015 issued in exercise of the powers conferred by sections 42A, 42C and 42F of the said Act, declared the Pune Metropolitan Area as "Pune Metropolitan Development Area" u/s 42A of the said Act, and u/s 42C thereof constituted "Pune Metropolitan Area Region Development Authority" (hereinafter referred to as "the said Area Development Authority"), and *vide* the Government Notification dated 04th December 2015 revised the limits of the said Area Development Authority;

And whereas, as per clause (C) iii (c) of Government Notification No. TPS-1815/1204/13/CR-87/15/UD-13 dated 31st March, 2015, the development proposals and special regulations of the sanctioned Regional Plan along with Development control and promotion Regulations modified from time to time shall be applicable within the area of the said Authority till the finalization of Development plan (hereinafter referred to as "the said Development Control Regulations");

And whereas, in exercise of the powers conferred by sub-section (1) of section 3 of the said Metropolitan Development Authority Act, 2016 the Government *vide* Notification of Urban Development Department No. PRD-3316/CR-54/UD-7, dated 11th July, 2016 has established Metropolitan Region Development Authority to be called "the Pune Metropolitan Region Development Authority" (hereinafter referred to as "the said Development Authority") for the Metropolitan Area more specifically described in the Schedule appended thereto;

And whereas, the Government of Maharashtra *vide* its notification No. TPS-1817/CR-173/17/UD-13, Dated-18/01/2018, declared the said Development Authority as a "Special Planning Authority" under section 40 (1) of MRTP, Act-1966;

And whereas, the said Development Authority has to consider different regulations and the Development Plan for the Pune Metropolitan Region is yet to be prepared; the Government has issued directives Dated 24th May 2016 & 18th November 2016 to the said authority to prepare uniform Development Control Regulations within stipulated time and accordingly the authority has submitted a set of comprehensive and uniform Revised Development Control Regulations to the Government for further action;

And whereas, In view of above and after consulting the Director of Town Planning, Maharashtra State, the Government is of the opinion that the said Development Control Regulation should be replaced by the Revised Development Control and Promotion Regulations attached here with (Hereinafter referred to as the said modification);

Now therefore, in accordance with the provisions contained in sub-section (3) of the section 20 of the said Act, the Government hereby, publishes this notice for inviting suggestions and / or objections, in respect of the said modifications attached with this notice, from the general public within one month from the date of publication of the notice in the official Gazette. The suggestions and / or objections shall be addressed to the Metropolitan Commissioner, Pune Metropolitan Regional Development Authority, Aundh, Pune-411 007 who is hereby appointed to hear the suggestions and / or objections which may be received within the aforesaid period and to submit the report to the Government. Only the suggestions and / or objections received within the aforesaid stipulated period shall be considered by the Government. **The said modification shall be applicable from the date of sanction u/s 20 (4) of the said Act.**

A copy of the said modification as mentioned in this notice along with set of regulations shall be kept open for inspection by the general public in the following offices:-

- 1) Director of Town Planning, Maharashtra State, Pune.
- 2) Metropolitan Commissioner, PMRDA, Pune.
- 3) Joint Director of Town Planning, Pune Division, Pune.

This Notification shall also be published on the Government website www.maharashtra.gov.in (कायदे व नियम).

By order and in the name of the Governor of Maharashtra,

R. M. PAWAR,

Under Secretary to Government.

**PUNE METROPOLITAN REGIONAL DEVELOPMENT
AUTHORITY**



PUNEMETROPOLIS

DRAFT

**DEVELOPMENT CONTROL AND
PROMOTION REGULATIONS FOR
PUNE METROPOLITAN REGION
DEVELOPMENT AUTHORITY
(PMRDA)
(DCPR-2018)**

March 2018

**Metropolitan Commissioner,
PMRDA**

DEVELOPMENT CONTROL AND PROMOTION REGULATIONS -2018 FOR PUNE METROPOLITAN REGIONAL DEVELOPMENT AUTHORITY		
Regulation no.	INDEX Contents	Page No.
PART - I ADMINISTRATION		
1.0	Short Title, Extent and Commencement	1
2.0	Definitions	2
3.0	Applicability of Regulations	12
4.0	Interpretation	12
5.0	Development Permission & Commencement Certificate	13
6.0	Procedure for Obtaining Development Permission / Building Permission / Commencement Certificate	14
7.0	Procedure During Construction	23
8.0	Inspection	24
9.0	Unsafe Buildings	24
10.0	Offences and Penalties	24
11.0	Amendment to Appendices	25
12.0	Provision with respect to NBC	25
PART – II GENERAL LAND DEVELOPMENT REQUIREMENTS		
13.0	Sites not Eligible for construction of Building	26
14.0	Means of Access	28
15.0	Regulations for Land Sub -Division and Layout	30
16.0	Land Use Classification and Permissible Uses	36
17.0	Open Space, Area and Height Limitations	37
17.11	Parking, Loading and Unloading Spaces	40
18.0	Requirements of Parts of Buildings	46
Part – III LAND USE CLASSIFICATION AND PERMISSIBLE USES		
19.1	Residential Zone – R1	64
19.2	Residential Zone – R2	65
19.3	Slum Improvement Zone - Deleted	68
19.4	Commercial Zone	68
19.5	Central Business District Zone - Deleted	68
19.6	Industrial Zone	68
19.7	Agriculture Zone / No Development Zone	71
19.8	Green Belt	75
19.9	Hill Top & Hill Slope Zone in PMR	76
19.10	Public / Semi-Public Zone	76
19.11	Traffic And Transportation Zone - Deleted	77
19.12	Defence Zone	77
19.13	Forest Zone	77
19.14	Restrictive Zone	77
19.15	Afforestation Zone	77
PART – IV GENERAL BUILDING REQUIREMENTS – SETBACK, MARGINAL DISTANCE, HEIGHT AND PERMISSIBLE FSI		
20.0	General	79
20.1	Regulations for Congested area	79
20.2	Regulations for Outside Congested Area	80
20.2.1	Marginal distances for residential building height 15 m. and below	80
20.2.2	Marginal distances for other buildings	83
20.3	Permissible FSI	85
20.4	Industrial Building	86
20.5	FSI of Green Belt	86

PART – V		
HIGHER FSI FOR CERTAIN USERS		
21.0	General	87
21.1	Permissible Marginal Spaces, Permissible Basic FSI, Additional FSI for Buildings in Non-Congested Area	88
21.2	Entitlement of FSI for road widening or construction of new roads / surrender of Reserved land	96
21.3	Development/ re-development for construction of staff quarters of the State Government or its statutory bodies or PMRDA on private lands	96
21.4	Development / re-development of Housing Schemes by MHADA	97
21.5	Redevelopment of Existing Buildings belonging to EWS /LIG group	101
21.6	Redevelopment of Old /Dilapidated and Dangerous Building	101
21.7	Redevelopment of Existing Buildings	103
21.8	Transit Oriented Development (TOD)	103
21.9	Development of Housing for EWS/LIG/PMAY	107
21.10	Regulation for development of IT establishment	108
21.11	Regulation for Development of Bio-Technology Park	110
21.12	Development of Public Toilet	111
PART VI		
FIRE PROTECTION REQUIREMENTS		
22.1	General	112
22.2	Construction Materials	112
22.3	Lifts	112
22.4	Basement	113
22.5	Service Ducts/Shafts	115
22.6	Refuse Chutes	115
22.7	Refuge Area	115
22.8	Electrical Services	115
22.9	Gas Supply	116
22.10	Illumination of Means of Exit	116
22.11	Stand-by Electric Generator	116
22.12	Transformer	116
22.13	Air Conditioning	117
22.14	Provision of Boiler and Boiler Room	118
22.15	Provision of First Aid and Fire Fighting Appliance	118
22.16	Fire Alarm System	118
22.17	Lightening Protection of Buildings	118
22.18	Fire Control Room	119
22.19	Housekeeping	119
22.20	Fire Drills and Fire Orders	119
22.21	Compartmentation	119
22.22	Material for Interior Decoration and Furnishing	119
22.23	Fire Escape Chutes / Controlled Lowering Device for Evacuation	119
22.24	Fire Check Floor	120
22.25	Fire Infrastructure Charges	120
22.26	Fire Officer for hotels, business and mercantile buildings with height more than 30m	120
PART – VII		
STRUCTURAL SAFETY, WATER SUPPLY, DRAINAGE & SANITARY REQUIREMENTS, OUTDOOR DISPLAY STRUCTURES		
23.0	Structural Design	121
24.0	Quality of Materials and Workmanship	121
25.0	Alternative Materials, Methods of Design and Construction and Tests	121
26.0	Building Services	122
27.0	Water Supply, Drainage and Sanitary Requirements	122
28.0	Drainage and Sanitary Requirements	124
29.0	Signage and Outdoor Display Structures	125
PART – VIII		

SPECIAL PROVISIONS IN CERTAIN BUILDINGS		
30.0	Provisions of Facilities for Differentially Abled Persons	126
31.0	Installation of Solar assisted Water Heating (SWH) System/ Roof Top Photovoltaic (RTPV) System	126
32.0	Rain Water Harvesting	126
33.0	Regulations for Waste Water Recycling	128
34.0	Solid Waste Management	130
35.0	Incentives for Green Buildings	130
PART – IX SPECIAL SCHEMES/ ACTIVITIES		
36.0	Integrated Township Projects	131
37.0	Regulation for Inclusive Housing	145
38.0	Tourism Development	146
39.0	Innovative Development Proposals	150
40.1	Research and Development Centers	150
40.2	Ropeway Projects	150
40.3	Planetarium / Astronomical / Astrophysical Facilities / Projects	150
40.4	Trekking Routes / Nature Trails / Nature Walks	150
40.5	Proposed Town Planning Scheme (TPS) Area	151
41.0	Special Regulations	151
41.1	Tourist Resorts / Holiday Homes / Township in Hill Station Type Areas	151
41.2	Development within 10 kms from Tamhini Ghat	151
42.0	Commercial use of Lands owned by Zilla Parishad, Panchayat Samiti & Gram Panchayat	151
43.0	Conservation of Heritage Buildings / Precincts / Natural Features	151
44.0	Mining or Quarrying Operations	156
45.0	Erection of Mobile Towers	156
PART – X ACQUISITION / DEVELOPMENT OF RESERVED SITES IN REGIONAL / DEVELOPMENT PLAN		
46.0	Transferable Development Rights (TDR)	157
47.0	Vesting of Land	161
PART XI SUPPLEMENTARY AND MISCELLANEOUS PROVISIONS		
48.0	Clarification	162
49.0	Power to Delegate	162
50.0	Appeals - Deleted	162

LIST OF APPENDIX		
Appendix No.	APPENDICES	Page No.
Appendix A-1	Application form for Construction of building or Layout of building or group housing.	164
Appendix A-2	Application form for Sub-Division of land as plotted layout.	172
Appendix B	Form for supervision.	176
Appendix C	Qualification and duties, responsibilities etc. of Licensed Technical Personnel or Architect for preparation of Schemes for Development Permission and Supervision.	177
Appendix D-1	Form for Sanction of building permit / commencement certificate.	180
Appendix D-2	Form for Tentative Approval for demarcation of land / sub-division of land.	181
Appendix D-3	Form for Final approval of building permit/sub-division of layout.	182
Appendix E-1	Form for Refusal of sanction to Building Permit / Commencement Certificate.	183
Appendix E-2	Form for Refusal of sanction to the Land Sub-division / Layout.	184
Appendix-F	Form for Intimation of Completion of Work upto Plinth Level	185
Appendix-G	Form of approval / disapproval of development work upto Plinth Level	186
Appendix-H	Form for Completion Certificate.	187
Appendix-I	Form for Occupancy Certificate.	188
Appendix-J	Form for Refusal of Occupancy Certificate.	189
Appendix-K	Form of Indemnity for Part Occupancy Certificate.	190
Appendix-L	Service Industries	191
Appendix-M	Sanitation Requirements	196
Appendix-N	Provisions for Barrier Free Access	212
Appendix-O	Regulations for Erection of Mobile Towers	216
Appendix-P	Site Visit Report	224
Appendix-Q	Site Visit Certificate	226
Appendix-R	Regulations for Lonavala-Karla-Malavali Planning Area	228
Appendix-S	Regulations for Kune-Pangaloli-Kurwande Planning Area	230
Appendix-T	Regulations For Development Of Tourism And Hospitality Services Under Community Nature Conservancy Around Wild Life Sanctuaries And National Parks Of RP Of Pune Region.	232
Appendix-U	Approvals of Building Permission on Fast Track based on Risk Based categorization.	234
Annexure I	Typical Road Cross-Sections	237

PART-I ADMINISTRATION

1.0 SHORT TITLE, EXTENT, AND COMMENCEMENT

1.1 These Regulations shall be called as —Development Control and Promotion Regulations for **Pune Metropolitan Region (PMR), 2018, referred to herein after as these Regulations.**

1.2 Extent- These Regulations shall apply to the building activities and development works on lands within the **PMR under the jurisdiction of Pune Metropolitan Regional Development Authority (PMRDA).**

1.3(a) These Regulations shall come into force from the date of notification.

1.3(b) Repeal: These shall replace existing building bye-laws applicable in PMR Area, standardized development control and promotional regulations for regional plan areas in Pune, Maharashtra, Special Regulation related to areas falling under 10 kms from Pune and Pimpri Chinchwad Municipal Corporations, development control rules / regulations of A, B and C municipal councils and the development control regulations of regional plan of Pune region with amendments made to them from time to time, and any guidelines/directions issued by any authorities in the past.

1.4 Provisions in Regional Plan:
Land use zoning provisions in the sanctioned Regional Plan of Pune shall govern unless otherwise specifically mentioned in these regulations. Special Provisions or Express Provisions made or Special Regulations as mentioned in Sanctioned Regional Plan which are not covered under these regulations shall prevail.

1.5 Conflicts in provisions: If there is any conflict between the provisions in sanctioned Regional Plan along with the provisions in the sanctioned Development Control and Promotion Regulations for Regional Plan area in Maharashtra and Development Control and Promotion Regulations for Pune Metropolitan Region (PMR) in that case, the matter shall be referred to the Director of Town Planning M.S., whose decision shall be final. Wherever, there is a discrepancy between the National Building Code and these Regulations, then in such cases these Regulations shall prevail.

1.6 Savings: Notwithstanding anything contained in these regulations, any development permission granted or any development proposal for which any action is taken under the erstwhile Regulations shall be valid and continue to be so valid, unless otherwise specified in these Regulations.

Provided that, permission granted earlier shall be eligible for renewal as per provisions of the Act. Provided further that, the words 'action taken' in this regulation shall also include the issuance of Demand note for granting the development permission;

Provided also that, it shall be permissible for the owner to –

a) either continue to develop the project under the erstwhile regulations in toto and for that limited purpose erstwhile regulation shall remain in force, or


b) apply for grant of revised permission under the new regulations, if the project is on-going and the occupation certificate, has not been granted fully.

2.0 DEFINITIONS:

2.1 General

- 2.1.1** In these Regulations, unless the context otherwise requires, the definitions given hereunder shall have meaning indicated against each of them.
- 2.1.2** Words and expressions that are not defined in these regulations shall have the same meaning or sense as in any of following Acts.
- The Maharashtra Regional and Town Planning Act, 1966.
 - National Building Code (2005 or amended from time to time); however, these regulations shall prevail in case of any overlaps/conflicts.
 - Maharashtra Metropolitan Region Development Authority Act, 2017.
- 2.2** “Act”- Act in these Regulations shall mean the Maharashtra Regional and Town Planning Act, 1966;
- 2.3** “Annual Statements of Rates” means *ASR* published by Inspector General of Registration, Maharashtra State, Pune;
- 2.4** “Authority” means Metropolitan Commissioner of PMRDA unless otherwise specified;
- 2.5** “Alteration” means any change in existing authorized building or change from one occupancy to another, or a structural change, such as an addition to the area or height, or the removal of part of a building, or any change to the structure, such as the construction of, cutting into or removal of any wall, column, beam, joist, floor, roof or other support or a change to or closing of any required means of ingress (entry) or egress (exit) as provided under these regulations. However, modification in respect of gardening, white washing, painting, plastering, pointing, paving and retailing shall not be deemed to be alteration;
- 2.6** “Advertising Sign” means any surface or structure with characters, letters or illustrations applied thereto and displayed in any manner whatsoever outdoor for purposes of advertising or to give information regarding or to attract the public to any place for public performance, article or merchandise whatsoever, or is attached to, or forms a part of building, or is connected with any building or is fixed to a tree or to the ground or to any pole, screen, fence or hoarding or displayed in space, in or over any waterbody;
- 2.7** “Accessory Building” means a building separate from the main building on a plot and containing one or more rooms for accessory use such as servant quarters, garage, store rooms etc;
- 2.8** “Accessory / Ancillary Use” means any use of the premises subordinate to the principal use and incidental to the principal use;
- 2.9** “Amenity”-Includes open spaces, parks, recreational facilities and grounds, sports complex, library, hospital, cafeteria, convenience shopping, parking lots, primary and secondary schools, clinics, dispensaries, health club, sub post office, police station, electrical sub stations, ATM's, banks, electronic cyber library, open market, garbage bins, play grounds, yoga center, gardens, water supply, electric supply, street lighting, sewerage, drainage, public works and other utilities, club house, services and conveniences, fire brigade, staff quarters of PMRDA and a public utility, Student Hostels and working women's hostel, (in case of Student Hostels, working women's hostel, the plot shall not be less than 2000 sq. mt. and a minimum of 50% of the plot area shall be used for open users such as open space, parks, recreational facilities, parking lots etc.) and such additional public utility users as decided by the Metropolitan Commissioner of PMRDA.
- 2.10** “Access” means a clear approach to a plot or a building;
- 2.11** “Architect” means a person registered with Council of Architecture(COA) as per Architects Act, 1972 as an Architect with a valid (COA) Registration Number;
- 2.12** “Architectural projection” means Chajja, Cornice, Ledge etc. which is a protrusion from the building facade or window line of the building used for non-habitable uses.;
- 2.13** “Atrium” means a sky lighted naturally/mechanically ventilated area in buildings, with no intermediate floors, used as circulation space or entrance *foyer*;

- 2.14 “Balcony”** means a horizontal cantilever projection, including parapet and handrail balustrade to serve as a passage or sitting out place with at least one side fully open, except being provided with railing or parapet wall for safety;



- 2.15 “Basement”** means the lower storey of a building below or partly below the ground level with one or more than one levels;
- 2.15.1 “Building”** means any structure for whatsoever purpose and of whatsoever materials constructed and every part thereof whether used as human habitation or not and includes foundation, plinth, walls, floors, roofs, chimneys, wells, door steps, fencing, plumbing and building services, fixed platforms, verandas, balcony; cornice or projection, part of a building or anything affixed thereto or any wall fence enclosing or intended to enclose any land or space and signs and outdoor display structures. However, tents, shamianas and the tarpaulin shelters erected for temporary and ceremonial occasions with the permission of the Metropolitan Commissioner shall not be considered as building;
- 2.16 “Built up Area”** means the area covered by a building on all floors including cantilevered portion, mezzanine floors if any but excepting the areas excluded specifically from FSI under these Regulations;
- 2.17 “Building Line”** means the line upto which the plinth of a building adjoining a street or an extension of a street or on a future street may lawfully extend. It includes the lines prescribed, if any, in any scheme and / or Regional/Development Plan, or under any other law in force;
- 2.18 “Building Height”** means the vertical distance measured in the case of flat roofs, from the average level of the ground around and contiguous to the building to the terrace of last floor of the building adjacent to the external walls; to the highest point of the building and in the case of pitched roofs, up to the point where the external surface of the outer wall intersects the finished surface of the sloping roof; and in the case of gable facing road, the mid-point between the eaves level and the ridge. Architectural features serving no other function except that of decoration shall be excluded for the purpose of measuring heights;
- 2.19 “Builder / Developer”** means a person who is legally empowered to construct or to execute work on a building unit, building or structure and/or land development or where no person is empowered, the owner of the building unit, building or structure.
- 2.20 “Bio-Technology Unit”** means an Unit or a Park which is certified as such by the Development Commissioner (Industries);

- 2.21 "Carpet area"** means the net usable floor area of an apartment, excluding the area covered by the external walls, areas under services shafts, exclusive balcony or veranda area and exclusive open terrace area, but includes the area covered by the internal partition walls of the apartment.
- Explanation.— For the purpose of this clause, the expression "exclusive balcony or veranda area" means the area of the balcony or veranda, as the case may be, which is appurtenant to the net usable floor area of an apartment, meant for the exclusive use of the allottee; and "exclusive open terrace area" means the area of open terrace which is appurtenant to the net usable floor area of an apartment, meant for the exclusive use of the allottee;
- 2.22 "Chajja"** means a sloping or horizontal structural overhang usually provided over openings on external walls to provide protection from sun and rain and for purpose of architectural appearance;
- 2.23 "Chimney"** means an upright shaft containing one or more flues provided for the conveyance to the outer air of any product of combustion resulting from the operation of heat producing appliance or equipment employing solid, liquid or gaseous fuel;
- 2.24 "Cluster"** means any defined area with proper access;
- 2.25 "Control Line"** means a line on either side of a highway or part of highway beyond the building line fixed in respect of such highway by the Highway Authority from time to time;
- 2.26 "Courtyard or Chowk"** means a space permanently open to sky enclosed on sides fully or partially by buildings and may be at ground level or any other level within or adjacent to a building;
- 2.27 "Canopy"** means a projection over any entrance;
- 2.28 "Congested Area"** means the area shown as congested on the Regional/Development Plan;
- 2.29 "Convenience Shopping"** means shops for domestic needs each with carpet area not exceeding 20 sq.m.;
- 2.30 "Corridor"** means a common passage or circulation space including a common entrance hall;
- 2.31 "Detached Building"** means a building whose walls and roofs are independent of any other building with marginal distances on all sides as specified;
- 2.32 "Development"** with its grammatical variations means the carrying out of buildings, engineering, mining or other operations in, or over, or under land or the making of any material change, in any building or land or in the use of any building or land or any material or structural change in any Heritage building or its precinct and includes demolition of any existing building, structure or erection of part of such building, structure of erection and reclamation, redevelopment and layout or sub-division of any land and to develop shall be construed accordingly;
- 2.33 "Regional/Development Plan"** means i) **Development Plan** :- "Development Plan" means a plan for the development of the area within the jurisdiction of a Planning Authority and includes revision of a development plan and proposals of a Special Planning Authority for development of land within its jurisdictions.
- ii) **Regional Plan** :- "Regional Plan" means a plan for the development or redevelopment of a region which is approved by the State Government and has come into operation under Maharashtra Regional & Town Planning Act, 1966.
- 2.34 "Dwelling Unit /Tenement"** means an independent housing unit with separate facilities for living, cooking and sanitary requirements;

- 2.35 “Enclosed Stair- case”** means a staircase separated by fire resistant walls and door (s) from the rest of the building;
- 2.36 “Existing Building or Use”** means a building, structure or its use existing authorisedly;
- 2.37 “Exit”** means a passage, channel or means of egress from any building, storey or floor area to a street or other open space of safety;
- 2.37.1 “Vertical Exit”** means exit used for ascension or descension between two or more levels including stairways, smoke proof towers, ramps, escalators and fire escapes;
- 2.37.2 “Horizontal Exit”** means a protected opening through or around a firewall or a bridge connecting two buildings;
- 2.37.3 “Outside Exit”** means an exit from the building to a public way, to an open area leading to a public way, to an enclosed fire resistive passage to a public way;
- 2.39 “External Wall”** means an outer wall of a building, not being a party wall even though adjoining to a wall of another building and also means a wall abutting on an interior open space of any building;
- 2.40 “Escalator”** means a power driven, inclined, continuous stairway used for raising or lowering passengers;
- 2.41 “Fire and/ or Emergency Alarm System”** means an arrangement of call points or detectors, sounders and other equipments for the transmission and indication of alarm signals, for testing of circuits and, whenever required, for the operation of auxiliary services. This device may be workable automatically or manually to alert the occupants in the event of fire or other emergency;
- 2.42 “Fire lift”** means a lift specially designed for use by fire service personnel in the event of fire;
- 2.43 “Fire Proof Door”** means a door or shutter fitted to a wall opening, and constructed and erected with the requirement to check the transmission of heat and fire for a specified period;
- 2.44 “Fire Resisting Material”** means a material which has certain degree of fire resistance;
- 2.45 “Fire Resistance”** means the time during which a material fulfils its function of contributing to the fire safety of a building when subjected to prescribed conditions of heat and load or restraint. The fire resistance test of structures shall be done in accordance with "IS -3809 - 1966 Fire Resistance Test of Structures";
- 2.46 “Fire Separation”** means the distance in meters measured from any other building on the site, or from other site, or from the opposite side of a street or other public space to the building;
- 2.47 “Fire Service Inlets”** means a connection provided at the base of a building for pumping up water through in-built fire-fighting arrangements by fire service pumps in accordance with the recommendations of the Fire Services Authority;
- 2.48 “Fire Tower”** means an enclosed staircase which can only be approached from the various floors through landings or lobbies separated from both, the floor areas and the staircase by fire resisting doors and open to the outer air;
- 2.49 “Floor”** means the lower surface in a storey on which one normally walks in a building. The general term floor unless otherwise specifically mentioned shall not refer to a mezzanine floor;

Note-The sequential numbering of floor shall be determined by its relation to the determining entrance level. For floor at or above ground level, with direct entrance from / to road or street shall be termed as ground floor. The other floors above ground floor shall be numbered in sequence as Floor 1, Floor 2, etc., with the number increasing upwards. The stilt shall be termed as stilt floor or Stilt floor 1, Stilt floor 2 etc. and floors above shall be numbered as Floor 1, Floor 2, etc.,

- 2.50 “Floor space index (F. S. I)”** means the quotient obtained by dividing the total built-up area on all floors, excluding exempted areas as given in Regulation no.17.7 by the area of the plot;

$$\text{F.S.I.} = \frac{\text{Total built-up area on all floors}}{\text{Plot area}}$$

- 2.51 “Premium FSI”** means the FSI that may be available on payment of premium as may be prescribed under these regulation;
- 2.52 “Fitness centre”** means and includes the built up premises, including toilet facilities, provided in the building including gymnasium for the benefit of its inmates and for the purpose of fitness, physical exercises, yoga and such other activities as may be permitted by the Commissioner from time to time.
- 2.53 “Footing”** means a foundation unit constructed in brick work, masonry or concrete under the base of a wall or column for the purpose of distributing the load over a large area;
- 2.54 “Foundation”** means that part of the structure which is in direct contact with and transmitting loads to the ground;
- 2.55 “Front Margin”** means the distance between the boundary line of plot abutting the means of access/ road/ street and the building. In case of plots facing two or more means of accesses / roads / streets, the plot shall be deemed to front on all such means of access / road / streets;
- 2.56 “Gallery”** means an intermediate floor or platform projecting from a wall of an auditorium of a hall providing extra floor area, additional seating accommodation etc. These shall also include the structures provided for seating in stadia.
- 2.57 “Garage Private”** means a building or portion thereof, designed and used for parking of privately owned motor driven or other vehicles;
- 2.58 “Garage-Public”** means a building or portion thereof designed as other than a private garage, operated for gain, designed or used for repairing, servicing, hiring, selling or storing or parking motor driven or other vehicles.;
- 2.59 “Group Housing Scheme”** means a building or a group of buildings constructed or to be constructed with one or more floors, consisting of more than one dwelling units and having common service facilities. Common service facilities means facilities like stair case, balcony, corridor, and veranda, lift, etc;
- 2.60 “Ground Level”** means the average level of ground in a plot (Site);
- 2.61 “Guest house”** means a premise for housing the staff of Government, semi –government, public undertaking and private limited company for short duration.
- 2.62 “Habitable Room”** means, a room constructed or intended for human habitation;
- 2.63 “Home Occupation”** means occupation, other than an eating or a drinking place, offering services to the general public, customarily carried out by a member of the family residing on the premises without employing hired labour, and for which there is no display to indicate from the exterior of the building that it is being utilized in whole or in part for any purpose other than a residential or dwelling use, and in connection with which no article or service is sold or exhibited for sale except that which is produced therein, which shall be non-hazardous and not affecting the safety of the inhabitants of the building and the neighbourhood and provided that no mechanical equipment is used except for what is customarily used for purely domestic or household purposes and / or employing licensable goods;

- 2.64 “Information Technology Establishment (ITE)”** means an establishment which is in the business of developing either software or hardware relating to computers or computer technology as approved by Director of Industries;
- 2.65 “Ledge or Tand”** means a shelf like projection, supported in any manner whatsoever, except by vertical supports within a room itself but not having projection wider than 0.60m.;
- 2.66 “Licensed Engineer / Structural Engineer / Supervisor”** means a qualified Engineer/ Structural Engineer / Supervisor licensed by the Metropolitan Commissioner;
- 2.67 “Lift”** means an appliance designed to transport persons or materials between two or more levels in a vertical or substantially, vertical direction, by means of a guided car platform;
- 2.67.1 “Lift Well”** means an unobstructed space within an enclosure provided for the vertical movement of the lift car(s) and any counter weights, including the lift pit and the space for top clearance;
- 2.68 “Loft”** means, an intermediate floor between two floors, with a maximum height of 1.5 m., which is constructed and used for storage purpose, fully defined in regulation no. 18.5;
- 2.69 “Mall”** means a large enclosed shopping area;
- 2.70 “Marginal distance / Set back”** means a minimum distance required to be left open to sky between the boundary of the building plot and the building excluding court yard/chowk, which is an integral part of the plot;
- 2.71 “Mezzanine floor”** means an intermediate floor between two floors of any story, forming an integral part of floor below, overhanging or overlooking a floor beneath, not being a loft between the floor and the ceiling of any storey;
- 2.72 “Means of Access”** shall include the road/street/vehicular access way, pathway upto the plot and to the building within a plot;
- 2.73 “Net plot area”** means the area as per Regulation no.15.7;
- 2.74 “Newly merged area”** means area included in the jurisdiction of PMRDA.
- 2.75 “Non-Combustible Material”** means a material which does not burn nor add heat to a fire when tested for combustibility in accordance with IS: 3808 – 1966 _Method of Test for Combustibility of Building Materials‘;
- 2.76 “Non-conforming User”** means any lawful use / building existed on the Site but which does not conform to the zoning shown on the Regional/Development Plan;
- 2.77 “Occupancy or Use Group”** means the principal occupancy or use for which a building or a part of a building is used, or intended to be used, for the purposes of classification of a building according to the occupancy. Occupancy shall be deemed to include subsidiary occupancies which are contingent upon it. Buildings with mixed occupancies are those buildings in which more than one occupancy are present in different portions of the building. The occupancy classification shall have the meaning given from **2.77.1 to 2.77.13**;
- 2.77.1 “Residential Buildings”** means any building in which sleeping accommodation is provided for normal residential purposes with or without cooking or dining or both facilities. It includes one or two or multi-family dwellings, lodging or rooming houses, residential hotels, hostels, dormitories, dharmshalas, apartment houses, flats, service apartment, studio apartment and private garages incidental thereto;

- 2.77.2 “Educational Buildings”** means a building exclusively used for a school or college recognized by the appropriate Board or University, or any other competent authority involving assembly for instruction, education or recreation incidental to educational use, and including a building for such other users incidental thereto such as library, a research institution. It shall also include quarters for essential staff required to reside in the premises and a building used as a hostel attached to an educational institution whether situated in its campus or not and, also includes buildings used for day-care purposes more than 8 hours per week;
- 2.77.3 “Institutional Buildings”** means a building constructed or used by Government, Semi-Government organization or registered trusts or persons and used for medical or other treatment, or an auditorium or complex for cultural and allied activities or for an Hospice care of persons suffering from physical or mental illness, handicap, disease or infirmity, care of orphans, abandoned women, children and infants, convalescents, destitute or aged persons and for penal or correctional detention with restricted liberty of the inmates ordinarily providing sleeping accommodation, and includes hospitals, sanatoria, custodial and penal institutions such as jails, prisons, mental hospitals, houses of correctional detention and reformatories;
- 2.77.4 “Assembly Buildings”** means any building or part of building where groups of people congregate or gather for amusement, recreation or social, religious, patriotic, civil, travel and similar purposes, e.g. theatres, motion picture house, drive-in-theatres, multiplexes, assembly halls, city halls, town halls, auditoria, exhibition halls, museums, mangalkaryalaya, cultural centre, skating rinks, places of worship, dance theatres, club & gymkhana, passenger stations and terminals of air, surface and other public transportation services, recreation piers and stadia having built up area more than 1000 sq.m.;
- 2.77.5 “Business Buildings”** means any building or part of building, which is used for transaction of business for the keeping of accounts and records for similar purposes; offices, banks, professional establishments, I.T. establishments, call centre, offices for private entrepreneurs, court houses, libraries shall be classified in this group in so far as principal function of these is transaction of public business and the keeping of books and records;
- 2.77.6 “Office Building / Premises”** means the premises whose sole or principal use is to be used as an office or for office purpose; —office purposes□ shall include the purpose of administration, clerical work, handling money, telephone/ telegraph/ computer operations and —clerical work□ shall include writing, book-keeping, sorting papers, typing, filing, duplicating, drawing of matter for publication and the editorial preparation of matter for publication;
- 2.77.7 “Mercantile (Commercial) Buildings”** means any building or part of a building, which is used as shops, stores, market, malls for display and sale of merchandise either wholesale or retail Office, storage and service facilities incidental to the sale of merchandise and located in the same building shall be included under this group;
- 2.77.8 “Public-Semi-public Building”** means a building constructed or used by Government, Semi Government Organization, Government Undertaking, Local Authorities, for conducting public semi-public use like municipal office, post office, telephone office, etc.;
- 2.77.9 “Wholesale Establishments”** means an establishments wholly or partly engaged in wholesale trade, manufactures, wholesale outlets including related storage facilities, A.P.M.C. establishments, warehouses and establishments engaged in truck transport including truck transport booking agencies;

- 2.77.10 “Industrial Buildings”** means any building or part of a building or structure, in which products or materials of all kinds and properties are fabricated, assembled or processed like assembling plants, laboratories, power plants, smoke houses, refineries, gas plants, mills, dairies, factories etc.;
- 2.77.11 “Storage Buildings”** means any building or part of a building used primarily for the storage or sheltering of goods, wares or merchandise, like ware houses, cold storage, freight depots, transit sheds, godowns, store houses, public garages, hangars, truck terminals, grain elevators, barns and stables;
- 2.77.12 “Hazardous Buildings”** means any building or: part of a building which is used for the storage, handling, manufacture or processing of highly combustible or explosive materials or products which are liable to burn with extreme rapidity and / or which may produce poisonous gases or explosions during storage, handling, manufacturing or processing, which involve highly corrosive, toxic or noxious alkalis, acids or other liquids or chemicals producing flames, fumes and explosive, mixtures of dust or which result in the division of matter into fine particles subject to spontaneous ignition;
- 2.77.13 “Special Buildings”** means
- (i) multi-storied buildings for any user having height more than 15 meter in height measured from ground; or,
 - (ii) buildings for the purposes of educational, assembly, mercantile, institutional, public and semi-public, industrial, storage and for hazardous material, buildings having built-up area more than 500 sq. m on each any floor, irrespective of the height of the building; or,
 - (iii) multi-storied buildings for any user having mixed occupancies, with any of the aforesaid occupancies mentioned in (ii) above, having built-up area more than 500 sq. m on each floor;
- 2.78 “Owner”** means a person who has legal title for land or building;
- 2.79 “Parapet”** means a low wall or railing built along the edge of a roof, terraces, balcony, veranda etc.;
- 2.80 “Parking Space”** means an enclosed or unenclosed, covered or open area sufficient in size to park vehicles. Parking space shall be served by a driveway connecting them with a street or alley and permitting ingress or egress of vehicles;
- 2.81 “Permit / Permission”** means a permission or authorisation in writing by the Authority to carry out the work regulated by these Regulations;
- 2.82 “Plinth”** means a portion of a structure between the surface of the surrounding ground and surface of the floor immediately above the ground;
- 2.83 “Plot / Site”** means a parcel or piece of land enclosed by definite boundaries;
- 2.84 “Porch”** means a covered surface supported on pillars or otherwise for the purpose of pedestrian or vehicular approach to a building;
- 2.85 “Podium”** means a continuous projecting base or pedestal around a building, generally used for parking and movement of vehicles, as specified in these regulations;
- 2.86 “Recreational Open Space / Layout open space”** means a statutory common open space kept in any layout or group housing scheme or campus planning, exclusive of margins and approaches, on ground only;

- 2.87 “Record Plan”** means a Plan to be prepared and submitted to the authority on basis of which a final occupancy certificate is issued.;
- 2.88 “Restaurant”** means a premises used for serving food items on commercial basis including cooking facilities and seating arrangements in residential building. And for commercial premises restaurant may be allowed of any built up area situated on any floor with a separate parking and garbage disposal facility.
- 2.89 “Road / Street”** means any highway, street, lane, pathway, alley, stairway, passageway, carriageway, footway, square place or bridge, whether a thoroughfare or not, over which the public have a right of passage or access or have passed and had access uninterruptedly for a specified period, whether existing or proposed in any scheme, and includes all bunds, channels, ditches, storm-water drains, culverts, sidewalks, traffic islands, roadside trees and hedges, retaining walls, fences, barriers and railings within the street lines;
- 2.90 “Road / Street Line”** means the line defining the side limit of a road / street;
- 2.91 “Road/Street Level or Grade”** means the officially established elevation or grade of the centre line of the street upon which a plot fronts and if there is no officially established grade, the existing grade of the street at its mid – points.
- 2.92 “Room Height”** means the vertical distance measured from the finished floor surface to the finished ceiling/ slab surface. In case of pitched roofs, the room height shall be the average height between bottom of the eaves and bottom of ridge;
- 2.93 “Row Housing”** means a row of houses with front and rear marginal distances;
- 2.94 “Semi Detached Building”** means a building detached on three sides with marginal distances as specified;
- 2.95 “Service Apartment”** means a premise in which rooms are let out on short/long term basis.;
- 2.96 “Service Floor”** means a non-habitable floor generally provided in multi-storied buildings and especially in starred hotels where from services like water supply, sewerage disposal system, electricity etc. are co-ordinated/maintained. Height of such floor shall not be more than 1.8m. from floor level to soffit of outer beam and shall not be counted in FSI.
- 2.97 “Site, corner”** means a site at the junction of and fronting on two or more intersecting streets;
- 2.98 “Site, Depth of”** means the mean horizontal distance between the front and rear side boundaries;
- 2.99 “Site, Double Frontage”** means a site, having a frontage on two streets other than a corner plot;
- 2.100 “Site, Interior or Tandem”** means a site, access to which is by a passage from a street whether such passage forms part of the site or not;
- 2.101 “Smoke Stop Door”** means a door for preventing or checking the spread of smoke from one area to another;
- 2.102 “Stair Cover”** means a structure with a covering roof over a stair case and its landing built to enclose only the stair for the purpose of providing protection from weather and not used for human habitation;

- 2.103 “Stilts or Stilt Floors”** means the portion of a building above ground level consisting of structural column supporting the super structure with at least two sides open and without any enclosures for the purpose of parking vehicles, scooters, cycles, etc.;
- 2.104 “Store Room”** means a room used as storage space;
- 2.105 “Storey”** means the portion of a building included between the surface of any floor and the surface of the floor next above it, or if there be no floor above it, then the space between any floor and the ceiling next above it;
- 2.106 “Supported Double Height Terrace”** means open terraces with railing having minimum height equal to two floors within building line.
- 2.107 “Telecommunication Cell Site/Base Station (TCS/BS)”** means tower of requisite height and dimensions, delta, single pole antennae, microwave antenna, cabin of requisite dimensions for housing equipment, telecom transceiver machinery, related civil work, requisite wires and cables, power supply equipment, Diesel Generator (DG) Set/ Alternate power supply mechanism, cabin /cupboard for housing any or all of the aforesaid items as necessary;
- 2.108 “Tenement”** means an independent dwelling unit with a kitchen or cooking alcove;
- 2.109 “Terrace”** means a flat, open to sky roof of a building or a part of a building having parapet;
- 2.110 “To Erect”** - To erect a building means
- (a) to erect a new building on any site whether previously built upon or not;
 - (b) to re-erect any building of which portions above the plinth level have been pulled down, burnt or destroyed; and
 - (c) conversion from one occupancy to another;
- 2.111 “Travel Distance”** means the distance from the remotest point on a floor of a building to a place of safety, be it a vertical exit, horizontal exit or an outside exit measured along the line of travel;
- 2.112 “Tower like structure”** means a structure in which the height of the tower like portion is at least twice the width of the broader base;
- 2.113 “Unsafe Building”** means those buildings which are structurally unsafe, unsanitary or not provided with adequate means of ingress or egress which constitute a fire hazard or are otherwise dangerous to human life or which in relation to existing use constitute a hazard to safety or health or public welfare, by reason of inadequate maintenance, dilapidation or abandonment;
- 2.114 “Veranda”** means a covered area with at least one side open to the outside with the exception of 1 m. high parapet on the ground floor to be provided on the open side;
- 2.115 “Water Closet (WC)”** means a privy with arrangement for flushing the pan with water. It does not include a bathroom;
- 2.116 “Water Course”** means a natural channel or an artificial one formed by draining or diversion of a natural channel meant for carrying storm water and waste water;
- “Major Water Course”** means a water course which carried strong water discharging from a contributing area of not less than 160 Ha.;
- “Minor Water Course”** means a water course which is not major;

- 2.117 "Width of Road"** means the whole extent of space within the boundaries of road when applied to a new road, as laid down in the city surveys map or Regional/Development Plan or prescribed road lines by any Act or Law and measured at right angles to the course or intended course of direction of such road whichever is more;
- 2.118 "Window"** means an opening to the outside other than the door which provides all or part of the required natural light, ventilation or both, to the interior space;

3.0 APPLICABILITY OF REGULATIONS

- 3.1** These regulations shall apply to all development, redevelopment, erection and/or re-erection of a building, change of user etc. as well as to the design, construction or reconstruction of, and additions and alteration to a building. These regulations shall also apply to any revision of the development permissions/building permissions granted earlier under any Development Control Regulations. Further, these Regulations shall apply to development work defined in Regulation No.3.2 to 3.5. However, features approved by earlier permission shall remain intact unless it contradicts the provisions of FSI under these regulations.
- 3.2 Construction/ Part Construction** - Where the whole or part of a building is demolished or altered or reconstructed, removed, except where otherwise specifically stipulated, or part is proposed to be newly constructed or revised, these Regulations apply only to the extent of the work involved.
- 3.3 Change of Occupancy / User:** -Where the occupancy or the user of a building is changed, except where otherwise specifically stipulated, these Regulations shall apply to all parts of the building affected by the change.
- 3.4 Reconstruction** - The reconstruction, in whole or part of a building which has ceased to exist due to an accidental fire, natural collapse or demolition, having been declared unsafe, or which is likely to be demolished by or under an order of the PMRDA and for which the necessary certificate has been given by the PMRDA, shall be allowed subject to the provisions in these Regulations.
- 3.5 Revised permission** – Any development permission granted earlier may be revised. While granting the revised permission, the approved plans and commencement certificate of the earlier permission with the owner and office, shall be stamped as **‘CANCELLED’** by the Authority.
- 3.6 Development of sites or land sub-division or amalgamation of land** –Where land is to be developed, sub-divided or two or more plot are to be amalgamated or a layout is to be prepared, these Regulations shall apply to the entire area under development, sub-division, amalgamation and layout.

Provided that, where a part of an existing layout is being altered, these regulations shall apply only to that part which is being altered, without adversely affecting the requirement of layout roads, recreational open space, etc of earlier sanctioned layout.

4.0 INTERPRETATION

Section of general clauses Act, 1897 shall be applicable in case of standard terms and phrases as defined and interpreted therein.

- 4.1** In these Regulations, the use of present tense includes the future tense, the masculine gender includes the feminine and the neutral, the singular number includes the plural and the plural includes the singular. The word "person" includes a corporation/company, "writing" includes "printing and typing" and "signature" includes thumb impression made by a person who cannot write if his name is written near such thumb impression or digital signature in case of 'e' submissions.

- 4.2** Whenever sizes and dimensions of rooms and spaces within buildings are specified, they shall mean clear dimensions unless otherwise specified in these Regulations. However, sizes and dimensions may not be disputed with reference to finished/unfinished surfaces unless it differs overall dimensions of the building.

5.0 DEVELOPMENT PERMISSION AND COMMENCEMENT CERTIFICATE

- 5.1** No person shall carry out any development, in contravention of the Development Plan proposals.
- 5.2** No person shall carry out any development work including development of land by laying out into suitable plots or amalgamation of plots or development of any land as group housing scheme or to erect, re-erect or make alterations or demolish any building or cause the same to be done without first obtaining a separate building permit / commencement certificate for each such development work / building from the Metropolitan Commissioner.
- 5.3** No temporary construction shall be carried out without obtaining prior approval of the Metropolitan Commissioner, which may be granted subject to such conditions as may be deemed necessary by him. However, temporary site office/watchman cabin/labour- material shed/toilet may be constructed without permission after the development permission is granted. These temporary constructions shall be removed after the completion of construction under development permission.

5.4 Development undertaken on behalf of Government -

As per the provisions of Section 58 of The Maharashtra Regional and Town Planning Act, 1966, the office in-charge of the Government Department shall inform in writing to the Metropolitan Commissioner of the intention to carry out its purpose along with details of such development or construction as specified below :-

- i) An official letter by the authorised officer of Government Department addressed to the Metropolitan Commissioner, giving full particulars of the development work or any operational construction.
- ii) Ownership documents and measurement plan issued by the Competent Authority of Land Records Department.
- iii) Development / building plans conforming to the provisions of Regional/Development Plan and these Regulations for the proposed development work to the scale specified in these Regulations.
- iv) The proposals of the Regional/Development Plan or Town Planning Scheme affecting the land.
- v) A Site Plan of the area proposed to be developed to the scale.
- vi) Detailed plan showing the plan, sections and elevations of the proposed development work to the scale, including existing building specified either to be retained or to be demolished.

- 5.4.1** The operational construction of the Government or Government undertaking, whether temporary or permanent which is necessary for the operation, maintenance, development or execution of any of the following services shall be exempted from the provisions of these Regulations:-

- i) Railways;
- ii) National Highways;
- iii) National Waterways;
- iv) Airways and Aerodromes;
- v) Posts and Telegraphs, telephones, wireless, broadcasting and other like forms of communication, excluding mobile towers;
- vi) Regional grid for electricity;
- vii) Defence Authorities;

viii) Any other essential public service as may be notified by the State Government.

All such constructions shall however, conform to the prescribed requirements for the provision of essential services, water supply connection, drains, etc.

5.4.2 However the following constructions of the Government Departments do not come under the purview of operational construction for the purpose of exemption under Regulation no.5.4.1.

- i) New residential building (other than gate lodges, quarters for limited essential operational staff and the like), roads and drains in railway colonies, hospitals, clubs, institutes and schools in case of Railways and commercial development;
- ii) New building, new construction or new installation or any extension thereof, in case of any other services.

5.4.3 However, no permission shall be necessary for the following types of works:-

- i) The carrying out of any works by the Central or State Government or any public sector undertaking or any local authority-
 - (a) required for the maintenance or improvement of highway, road or public street, being works carried out on land within the boundaries of such highway, road or public street; or
 - (b) required for the purpose of inspecting, repairing or renewing any drains, sewers mains, pipes including gas pipes, telephone and electric cables, or other apparatus including the breaking open of any street, or other land for the purpose.

Provided that the concerned authority shall inform the local authority, in writing at the earliest and pay the necessary restoration charges to the PMRDA within a month. The restoration charges shall not be more than the expenditure incurred by the PMRDA to restore the road etc and supervision charges, if any.
- ii) The carrying out of works in compliance with any order or direction made by any Authority under any law for time being in force
- iii) The carrying out of works by any Authority in exercise of its powers under any law for time being in force.
- iv) The excavation (including excavation of wells) made in the ordinary course of agricultural operation.
- v) The construction of a road intended to give access to land solely for agricultural purpose.
- vi) Normal use of land which has been used temporarily for other purposes like marriage pandals or for festive occasions; and
- vii) In case of land normally used for one purpose and occasionally used for any other purpose, such occasional use of land for that other purpose.

6.0 PROCEDURE FOR OBTAINING DEVELOPMENT PERMISSION /BUILDING PERMISSION (COMMENCEMENT CERTIFICATE)

6.1 Notice/ Application - Every person who intends to carry out development and erect, re-erect or make alterations in any place in a building or demolish any building, shall give notice/ application in writing through registered Architect or Licensed Engineer / Structural Engineer / Supervisor, to the Authority of his said intention in the prescribed form (See Appendix A1 or A2)It will be mandatory to submit complete information in the form accompanied with Appendix A-1 and A-2.Such notice shall be accompanied by the payment receipt of required scrutiny fee and any other fee/ charges prescribed by the Metropolitan Commissioner from time to time and the plans and statements in sufficient copies (See Regulation no. 6.1.1), and as per the requirement under Regulation no.6.2 and 6.3. One set of plans shall be retained in the office of the Metropolitan Commissioner for record after the issue of permission or refusal. The plans may be submitted in electronic form as may be specified by the Metropolitan Commissioner from time to time.

Provided that, the applicant owner/developer shall have an option of choosing the process of approvals of Building Permission on Fast Track based on Risk Based categorization as mentioned in Appendix-U.

6.1.1 Copies of Plans and Statements - Four copies of plans and statements shall be made available along with the notice. Where clearance is required from other agencies, number of copies of plans required shall be as decided by the Metropolitan Commissioner.

6.2 Information Accompanying Notice/Application - The Notice/Application shall be accompanied with the key (location plan), site plan, sub-division layout plan/ building plan, services plans, specifications and certificate of supervision and ownership title etc., as prescribed in Regulation no.6.2.1 to 6.2.13.

6.2.1 Size of drawing sheets and colouring of plans.

6.2.1.1 The size of drawing sheets shall be of A0 to A4. If necessary, submission of plans on sheets bigger than A0 size shall also be permissible. Prints of plans shall be on one side of paper only. All dimensions shall be indicated in metric units.

6.2.1.2 Colouring Notations for Plans: - The Plans shall be coloured as specified in following Table:

**Table No.1
COLOURING OF PLANS**

Sr. No.	Item	Site Plan		Building Plan	
		White Plan	Ammonia	White Plan	Ammonia Print
(1)	(2)	(3)	(4)	(5)	(6)
1.	Plot lines	Thick Black	Thick Black	Thick Black	Thick Black
2.	Existing Street	Black	Blue	..	..
3.	Future street if any	Black dotted	Blue dotted	..	..
4.	Permissible Building lines	Thick dotted black	Thick dotted blue	..	..
5.	Existing work	Black (outline)	Blue	Black	Blue
6.	Work proposed to be demolished	Yellow hatched	Yellow hatched	Yellow hatched	Yellow hatched
7.	Proposed work	Red filled in	Red	Red	Red
8.	Drainage & sewerage work	Red dotted	Red dotted	Red dotted	Red dotted
9.	Water supply work	Black dotted thin	Black dotted thin	Black dotted thin	Black dotted thin
10.	Deviations from the sanctioned plan	Red hatched	Red hatched	Red hatched	Red hatched
Note:-	For land development/sub-division/layout/building plan, suitable colouring notations shall be used which shall be indexed.				

6.2.2 Ownership title and area - Every application for development permission and commencement certificate shall be accompanied by the following documents for verifying the ownership and area etc. of the land:-

- Latest Property card(s) or 7/12 extract(s) of a date not more than one month prior to the date of submission, power of attorney, wherever applicable.

- b) Measurement Plan of the property issued by Land Record Department.
- c) Statement of area of the holding by triangulation method /CAD (computer added designs and drafting based software) from the qualified licensed technical personnel or architect with an affidavit from the owner with regard to the area in the form prescribed by the Metropolitan Commissioner.
- d) Any other document prescribed by the Metropolitan Commissioner.
- e) Wherever third party interest is created by way of agreement to sale or mortgage etc. the registered consent of such interested persons shall be submitted with the application.
- f) A certified copy of approved sub-division / amalgamation / layout of land from the concerned authority.
- g) In the case of land leased by the Government or local authorities, no objection certificate of Government or such authorities shall be obtained if there is deviation from lease conditions and shall be attached to the application for development permission in respect of such land.

6.2.3 Key Plan or Location Plan - A key plan drawn to a scale of not less than 1:10,000 shall be submitted as a part of building plan / development proposal along with the application for a building permit and commencement certificate; showing the boundary and location of the site with respect to neighbourhood landmarks or with respect to the area within the radius of 200 m. from the site, whichever is more.

6.2.4 Site Plan - The site plan shall be submitted with an application for building permission drawn to a scale of 1:500 or more as may be decided by the Metropolitan Commissioner. This plan shall be based on the measurement plan duly authenticated by the appropriate officer of the Department of Land Records. This plan shall have the following details:-

- a) The boundaries of the site and of any contiguous land belonging to the neighbouring owners;
- b) The position of the site in relation to neighbouring streets;
- c) The name of the street, if any, from which the building is proposed to derive access;
- d) All existing buildings contained in the site with their names (where the buildings are given names) and their property numbers;
- e) The position of the building and of other buildings, if any, which the applicant intends to erect, upon his contiguous land referred to in (a) above in relation to:
 - (i) The boundaries of the site and, in a case where the site has been partitioned, the boundaries of the portions owned by others;
 - (ii) All adjacent streets, buildings (with number of storeys and height) and premises within a distance of 12 m. of the work site and of the contiguous land (if any) referred to in (a)
- f) The means of access from the street to the building and to all other buildings (if any) which the applicant intends to erect upon.
- g) The space to be left around the building to secure free circulation of air, admission of light and access;
- h) The width of the street (if any) in front and the street (if any) at the side of or near the building, including the proposed roads;
- i) The direction of the north line relative to the plan of the building;
- j) Any existing physical features, such as wells, tanks, drains, pipe lines, high tension line, railway line, trees, etc.;

- k) The ground area of the whole property and the break-up of the built-up area on each floor;
- l) A plan indicating parking spaces as required and provided under these regulations;
- m) Overhead electric supply lines, if any, including space for electrical transformer / sub-station according to these regulations or as per the requirements of the electric distribution company.
- n) Any water course existing on Site or adjacent to site;
- o) Existing alignments of water supply and drainage line;
- p) Such other particulars as may be prescribed by the Metropolitan Commissioner.

6.2.5 (i) Sub-Division/ Layout Plan— In the case of development of land, the notice shall be accompanied by the sub-division/ layout plan which shall be drawn to a scale of not less than 1:500, however, for layout having areas of 4.0 ha. and above, the plan shall be drawn to a scale of not less than 1:1000, containing the following:

- (a) Scale used and north point;
- (b) The location of all proposed and existing roads with their existing /proposed widths within the land;
- (c) Dimension of plots;
- (d) The location of drains, sewers, public facilities and services, electrical lines, natural water courses, water bodies and streams etc.
- (e) Table indicating size, area and use of all plots in the sub-division/ layout plan;
- (f) The statement indicating the total area of the site, area utilized under roads, recreational open spaces, amenity spaces, playground, recreation spaces and Regional/Development Plan reservations/ roads, schools, shopping and other public places along with their percentage with reference to the total area of the site proposed to be sub-divided / laid out;
- (g) In case of plots which are sub-divided in built-up areas, in addition to the above, the means of access to the sub-division from existing streets;
- (h) Contour plan of site, wherever necessary.

(ii) Amalgamation Plan:-Where two or more plots / holdings are to be amalgamated, plan showing such amalgamation drawn to a scale not less than 1:500. Instead of submitting a separate plan, such amalgamation may be allowed to be shown on building / layout-plan itself. However, 7/12 extract or property card of amalgamated plot shall be submitted before occupation certificate.

6.2.6 Building Plan - The plans of the buildings with elevations and sections accompanying the notice shall be drawn to a scale of 1:100 or to a scale as may be directed by the Metropolitan Commissioner and shall

- a) include floor plans of all floors together with the built-up area, clearly indicating the sizes of rooms and the position and width of staircases, ramps and other exit ways, lift-wells, lift machine rooms and lift pit details. It shall also include ground floor plan as well as basement plans and shall indicate the details of parking spaces, loading and unloading spaces provided around and within building as also the access ways and the appurtenant open spaces with projections in dotted lines, distance from any building existing on the plot in figured dimensions along with accessory building;
- b) show the statement of built-up area and Carpet area of every flat or shop or any unit along with proportionate common built-up area attached to it and area of balcony and double height terraces, if any attached to the said unit;

- c) show the use or occupancy of all parts of the building;
- d) show exact location of essential services e.g. wc, sink, bath and the like;
- e) include sectional drawings of the building showing all sectional details including staircase;
- f) show all street elevations;
- g) give dimensions of the projected portions beyond the permissible building line;
- h) include terrace plan indicating the drainage and the slopes of the roof;
- i) give indications of the north point relative to the plans; and
- j) give dimensions and details of doors, windows and ventilators.
- k) give such other particulars as may be required to explain the proposal.

6.2.6.1 Building Plans for Special Buildings :-

The following additional information shall be furnished/indicated in the Building Plans of Special Building as mention in regulation no 2.77.13 in addition to the items (a) to (k) of Regulation no. 6.2.6.:-

- (a) access to fire appliances/vehicles with details of vehicular turning circle and clear motorable access way around the building of minimum 6 m. width;
- (b) size (width) of main and alternate staircases, wherever necessary, along with balcony approach, corridor, ventilated lobby approach;
- (c) location and details of lift enclosures;.
- (d) location and size of fire lift;
- (e) smoke stop lobby/door, where provided;
- (f) refuse chutes, refuse chamber, service duct, etc.;
- (g) vehicular parking spaces;
- (h) refuge area, if any;
- (i) details of Building Services :-Air-conditioning system with position of fire dampers, mechanical ventilation system, electrical services, boilers, gas pipes etc.,
- (j) details of exits including provision of ramps, etc. for hospitals and buildings requiring special fire protection measures,
- (k) location of generator, transformer and switch gear room;
- (l) smoke exhaustor system, if any;
- (m) details of fire alarm system network;
- (n) location of centralized control, connecting all fire alarm systems, built in fire protection arrangements and public address system etc.
- (o) location and dimensions of static water storage tank and pump room along with fire service inlets for mobile pump and water storage tank;
- (p) location and details of fixed fire protection installations such as sprinklers, wet risers, hose reels, drenchers, CO2 installation etc.;
- (q) location and details of first aid, fire fighting equipment's /installations.
- (r) certificate of structural engineer about structural and earth-quake safety;

Provided that, the provision of fire escape stair case shall be made as per Regulation No.18.28.4

6.2.7 Service Plan - Plans, elevations and sections of water supply, grey water supply, sewage disposal system and details of building services, where required by the Metropolitan Commissioner, shall be made available on a scale not less than 1:100 in general and 1:1000 for layouts.

6.2.8 Supervision - The notice shall be further accompanied by a certificate of supervision in the prescribed form given in Appendix B, by a licensed Architect/ Engineer/ Structural Engineer, as the case may be. In the event of the said licensed technical personnel ceasing to be employed

for the development work, further development work shall stand suspended till a new licensed technical person is appointed.

6.2.9 Building/ Layout Permission Fee- The notice shall be accompanied by receipt of Building/ Layout Permission Fee. The building permission fee or layout /subdivision of land fees shall be as decided by the Metropolitan Commissioner from time to time. Provided that, such fees shall not be applicable for the development proposals implemented by Government / Government departments or Public Authorities of State or Central Government.

6.2.10 Development Charges- Development charges as required under Section 124A of the Act shall be deposited with the Planning Authority before issue of development permission/ commencement certificate. In case of revised permission where no development is carried out in pursuance of the earlier permission, amount of difference of development charges, if any, shall be levied and recovered. In case of revised permission, where development is commenced in pursuance of earlier permission, development charges shall be levied on the land and built-up area, over and above the area covered in the earlier permission.

6.2.11 Premium charges - Premium charges as may be required to be recovered under these regulations shall be paid to the Planning Authority before issue of development permission/ commencement certificate. The amount of premium collected shall be kept in a separate development fund called as **PMRDA Infrastructure fund'** and shall be utilized for the purpose of developing new/ up-gradation of infrastructure as well as implementation of Regional/Development Plan proposals and creation of civic amenities.

6.2.12 Tax clearance – Deleted

6.2.13 The notice/application shall be further accompanied by a certificate of supervision in the prescribed form as given in Appendix B, by a licensed Architect or Licensed Engineer / Structural Engineer / as the case may be. In the event of the said licensed technical personnel ceasing to be employed for the development work, further development work shall stand suspended till a new licensed technical person is appointed

6.3 Signing the Plan -

All the plans shall be duly signed by the owner, co-owner, if any, and the Architect or Licensed Engineer / Structural Engineer / Supervisor and shall indicate his name, address and license number allotted by the Authority.

6.4 Qualification and Competence of the Architect / Licensed Engineer / Structural Engineer/ Supervisor -

Architect/ Engineer/Structural Engineer/ Supervisor referred to in regulation no 6.3 shall be registered / licensed by the Metropolitan Commissioner as competent to plan and carry out various works as given in Appendix "C". The qualification and procedure for registration and licensing of the Engineer / Structural Engineer / Supervisor / Developer shall be as given in **Appendix- "C"**. Architects registered with council of Architecture shall not be required to register with the Authority.

6.5 Discretionary Powers:-

6.5.1 Interpretation.

In conformity with the intent and spirit of these regulations, the Metropolitan Commissioner may by order in writing -;

- (i) decide on matters where it is alleged that there is an error in any order, requirement decision, and determination on interpretation made by him or officer authorised by him in the application of these regulations.

- (ii) decide the extent of the proposal of regional/development plan with respect to survey number, where boundaries of the survey number shown on development plan varies with the boundaries as per revenue record/ measurement plan/ city survey sheets.
- (iii) determine and establish the location of zonal boundaries in exceptional cases, or in cases of doubt or controversy;
- (iv) decide the alignment of regional/development plan road, where the street layout actually on the ground varies from the street layout as shown on the Regional/Development Plan;
- (v) decide the alignment of blue and red flood line on Regional/development plan where it varies with the said lines given by the irrigation department or any other Government institutions dealing with the subject, from time to time;
- (vi) authorise erection of a building or use of premises for a public service undertaking for public utility purposes only, where he finds such authorisation to be reasonably necessary for the public convenience and welfare, even if it is not permitted in any Land Use Classification,
- (vii) modify the limit of a zone where the boundary line of the zone divides the plot. In such cases, the zone over the larger portion of the plot having area more 50% shall be considered.

6.5.2 Relaxation:

In specific cases, where a clearly demonstrable hardship is caused, the Metropolitan Commissioner by order in writing and subject to payment of premium; if any, may permit any of the dimensions / provision prescribed by these regulations to be modified provided the relaxation sought does not violate the health safety, fire safety, structural safety and public safety of the inhabitants of the buildings and the neighbourhood. However, no relaxation for the setback required from the road boundary (front marginal distance), F.S.I. or minimum required parking shall be granted under any circumstances, unless otherwise specified in these regulations.

While granting such relaxation, conditions may be imposed on size, cost or duration of the structure, abrogation of claim of compensation, payment of deposit and its forfeiture for noncompliance.

6.5.3 Temporary Constructions- The Metropolitan Commissioner may grant permission for temporary construction for a period not exceeding six months at a time and in the aggregate not exceeding for a period of one year, such a permission may be given by him for the construction of the following, viz.: -

- (i) Structures for protection from the rain or covering of the terraces during the monsoon only.
- (ii) Pandals for fairs, ceremonies, religious function, etc.
- (iii) Structures for godowns/storage of construction materials within the site.
- (iv) Temporary site offices and watchman chowkies within the site only during the phase of construction of the main building.
- (v) Structures of exhibitions/ circuses etc.
- (vi) Structures for storage of machinery, before installation for factories in industrial lands within the site.
- (vii) Structures for ancillary works for quarrying operations in conforming zones.
- (viii) Government milk booths, telephone booths and ATM Centers.
- (ix) Transit accommodation for persons to be rehabilitated in a new construction.
- (x) Structures for educational and medical facilities within the site of the proposed building during the phase of planning and constructing the said permanent buildings.

(xi) Ready mix concrete plant.

Provided that, temporary constructions for structures etc. mentioned at (iii), (iv), (vi), (ix) (x) and (xi) may be permitted to be continued temporarily by the Metropolitan Commissioner, but in any case not beyond completion of construction of the main structure or building and that structure in (vii) and (viii) may be continued on annual renewal basis by the Metropolitan Commissioner beyond a period of one year.

6.5.4 Delegation of Powers- Except the discretionary powers, and where the Metropolitan Commissioner's special permission is expressly stipulated, the powers or functions vested in him/her by these Regulations may be delegated to any official under his/her control, subject to his/her revision if necessary and to such conditions and limitations, if any, as he/she may prescribe.

6.5.5 Drafting error –Draftsman errors which are required to be corrected as per actual situation on site or as per the city survey record or sanctioned layout etc. may be corrected by the Metropolitan Commissioner, after consultation with the Director of Town Planning, Maharashtra State, Pune. The 'draftsman's errors' shall include errors on Regional / Development Plan in respect of typographical errors in S.No./G.No./C.T.S. No./F.P.No., errors in boundaries of such land parcels, errors in showing alignment of existing Nalas, river, canal, lake and like water bodies, etc. by taking into account a Revenue/Land Record or as the case may be, the record of concerned Town Planning Scheme.

6.6 Grant or Refusal of permission

6.6.1 After receipt of the notice/ application as mentioned in Regulation No. 6.1 above, the Authority may either sanction or refuse the plans or may sanction them with such modifications or directions as it may deem necessary after having recovered the necessary charges and there upon shall communicate its decision to the person giving the notice in the prescribed form given in Appendix D1/D2/D3 and E1/E2 as the case may be. Such approval shall also be deemed to have been granted under relevant provisions of the PMRDA.

6.6.2 (i) In case of special buildings, the building scheme shall also be subject to the norms of Maharashtra Fire Prevention and Life Safety Act, 2006 and shall also be subject to the scrutiny of the Chief Fire Officer, of the PMRDA and the sanction / development permission shall be issued by the Metropolitan Commissioner after the clearance from the Chief Fire Officer of the PMRDA.

(ii) In case of land subdivision or plotted layout, tentative layout shall be recommended for demarcation at first instance. After having demarcated the layout by the Land Records Department, the owner shall submit the demarcated layout for final approval to the Authority and the Authority shall examine the provision laid down in Regulation no.6.8 and grant final approval if it is in accordance with the layout recommended for demarcation and confirming to the regulations. This shall also be mandatory to Group Housing Scheme where roads in the adjoining layouts/Regional Plan/ Development Plan roads are to be coordinated and/or amenity space is to be earmarked.

6.6.3 If within sixty (60) days of receipt of the notice, the Authority fails to intimate in writing to the person who has given the notice, of its refusal or sanction or sanction with such modifications or directions, the notice with its plans and statements shall be deemed to have been sanctioned.

Provided, nothing shall be construed to authorise any person to do anything on the site of the work in contravention or against the terms of lease or titles of the land.

Provided further that, the development proposal, for which the permission was applied for, is strictly in conformity with the requirements of provisions of these regulations, or regulations framed in this behalf under any law for the time being in force and the same in no way violates

either provisions of any draft or final plan or proposals published by means of notice, submitted for sanction under the Act.

Provided further that, any development carried out in pursuance of such deemed permission which is in contravention of the provisions mentioned above, shall be deemed to be an unauthorised development for purposes of Sections 52 to 57 of the Maharashtra Regional and Town Planning Act, 1966 and other relevant Acts.

Provided further that, upon receipt of intimation of any claim for deemed permission, the Authority shall within fifteen days from the date of receipt of such claim, communicate its remarks, if any, regarding deemed permission to the applicant, failing which, the proposal shall be approved and commencement certificate and one set of duly approved plans for proposed development shall be issued to the applicant within fifteen days thereafter.

Provided further that, necessary explanation shall be called from the concerned officer of the Authority for not processing and disposing of the proposal within 60 days.

- 6.6.4** After the plan has been scrutinised and objections have been pointed out, the owner giving notice shall modify the plan, comply with the objections raised and resubmit it. The prints of plans submitted for final approval, shall not contain superimposed corrections. The authority shall grant or refuse the commencement certificate / building permit within 60 days from the date of resubmission. No new objections shall be raised when they are resubmitted after compliance of earlier objections, except in circumstances to be quoted for additional compliances.

6.7 Commencement of work

The commencement certificate/development permission shall remain valid for 4 years in the aggregate but shall have to be renewed every year from the date of its issue. The application for renewal shall be made before expiry of one year if the work is not already commenced. Such renewal can be done for three consecutive terms of one year after which proposals shall have to be submitted to obtain development permission afresh. If application for renewal is made after expiry of the stipulated period during which commencement certificate is valid, then the Authority may condone the delay for submission of application for renewal by charging necessary fees; but in any case, commencement certificate shall not be renewed beyond 4 years from the date of commencement certificate/ development permission.

Provided that, no such renewal shall be necessary if the work is commenced within the period of valid permission and such permission shall remain valid till the work is completed.

For the purpose of this regulation, "**Commencement**" shall mean as under: -

(a)	For layout, sub-division and amalgamation	Final demarcation and provision of water bound macadam roads complete.
(b)	For a building work including additions and alterations.	Construction of basement upto ground level slab or construction of building at plinth level whichever is minimum.
(c)	For bridges and overhead tanks construction.	Foundation and work up to the base floor.
(d)	For underground works	Foundation and work upto floor of underground floor.

- 6.8** In case of land subdivision / group housing schemes, it shall be the responsibility of the owner / developer to construct all infrastructure including roads with asphaltting, storm water drains, sewer lines, water supply lines, development of recreational open spaces etc. In case of land subdivision, these works shall generally be completed within two years and phase wise building permission shall be granted depending upon the percentage of infrastructure work completed. The layout plots should be released for construction in stages according to

infrastructure work completed. The condition to that effect shall be incorporated in the commencement certificate. In case of group housing scheme, these works shall be completed before completion of the project and occupancy certificate shall be granted phase wise as per completion of infrastructure work.

After handing over roads and infrastructure to the PMRDA on completion of scheme, the responsibility of maintenance of such road and infrastructure shall lie with the PMRDA.

7.0 PROCEDURE DURING CONSTRUCTION

7.1 Owner / Architect / Developer / Engineer / Structural Engineer / Supervisor or any licensed Technical persons' liability: - Neither the grant of permission nor approval of the drawing nor inspection by the Authority during erection of the building, shall in any way relieve the Owner / Architect / Developer / Engineer / Structural Engineer / Supervisor or any licensed Technical persons of such building / development, from full responsibility for carrying out the work in accordance with these Regulations and safety norms as prescribed by the Bureau of Indian Standards.

7.2 Documents at site –

- (i) **Development Permission:** The person to whom a development permission is issued shall during construction, keep -
 - (a) posted at a conspicuous place on the site for which permission has been issued, a copy of a development permission; and
 - (b) a copy of the approved drawings on the site for which the permission was granted.
- (ii) **Display board:** Display board mentioning name of the owner, name of architect, name of structural engineer, except for small individual plot holders.

7.3.1 Plinth Checking- the owner shall give notice in prescribed form given in Appendix-F to the Authority after the completion of work upto plinth level with a view to enable the Authority to ensure that the work is carried out in accordance with the sanctioned plans. The Authority shall carry out inspection jointly with Architect / liasoning technical person within 7 days from the receipt of such notice and decide the application. If it is sanctioned then, the Authority shall grant such certificate as prescribed in Appendix-G.

Provided that, if the Authority has not taken decision on such application within a period as stipulated above, the permission shall be deemed to have been granted. In such circumstances, the applicant shall get the plinth checked from the registered Technical Personnel along with correctness certificate and submit it to the Authority for record. Thereafter no separate permission shall be required from the Authority for continuing of work. Such certificate shall clearly indicate the correctness of execution of plinth on site in consonance with the sanctioned plan.

7.3.2 Deviation during constructions-If during construction of a building any departure of a substantial nature from the sanctioned plans is intended by way of internal or external additions, sanction of the Authority shall be necessary. A revised plan showing the deviation shall be submitted and the procedure laid down for the original plans shall apply to all such amended plans. Any work done in contravention of the sanctioned plans, except any changes made within the internal layout of a residential or commercial unit which do not violate FSI or other regulations, without prior approval of the Metropolitan Commissioner shall be deemed as unauthorised. However, any changes made within the internal layout of a residential or commercial unit, which do not violate FSI or other regulations, shall not be treated as unauthorised. Such changes shall be incorporated in plan along with completion certificate.

7.4 Completion Certificate - The owner through his licensed surveyor / engineer / structural engineer / supervisor or his architect, as the case may be, who has supervised the construction, shall furnish a building completion certificate to the Authority in the form in Appendix 'H'. This

certificate shall be accompanied by three sets of plans of the completed development, the certificate about the operation of the lift from consultant and certificate of structural stability / compliance issued by R.C.C. consultant, wherever necessary.

In case of special buildings, the completion certificate shall also be accompanied with the NOC along with completion plans from Chief Fire Officer of PMRDA.

- 7.5 Occupancy certificate** - The Metropolitan Commissioner after inspection of the work and after satisfying himself that there is no deviation from the sanctioned plans, issue an occupancy certificate in the form in Appendix- I or refuse to sanction the occupancy certificate in Appendix -J within 8 days from the date of receipt of the said completion certificate, failing which the work shall be deemed to have been approved for occupation, provided the construction conforms to the sanctioned plans. One set of plans, certified by the Metropolitan Commissioner, shall be returned to the owner along with the occupancy certificate. Where the occupancy certificate is refused or rejected, the reasons for refusal or rejection shall be given in intimation of the rejection or the refusal.

The applicant may request for deemed occupancy certificate if eligible as above. Metropolitan Commissioner shall issue the deemed occupancy certificate within 8 days of the application.

- 7.6 Part occupancy certificate:-** When requested by the holder of the development permission, the Authority may issue a part occupancy certificate for a building or part thereof, before completion of the entire work, as per development permission, provided sufficient precautionary measures are taken by the holder to ensure public safety and health. The occupancy certificate shall be subject to the owners indemnifying the Authority in the form in Appendix 'K'.

8.0 INSPECTION

The Authority shall have the power to carry out inspection of the work under the provisions of the Act, at various stages to ascertain whether the work is proceeding as per the provisions of regulations and sanctioned plan.

9.0 UNSAFE BUILDINGS

All unsafe buildings shall be considered to constitute danger to public safety and hygiene and sanitation and shall be restored by repairs or demolished or dealt with as otherwise directed by the Metropolitan Commissioner. The redevelopment of such buildings shall be as per the provisions stipulated in these regulations.

10.0 OFFENCES AND PENALTIES

- 10.1 Offences and penalties:-**Any person who contravenes any of the provisions of these regulations / any requirements or obligations imposed on him by virtue of these regulations including the maintenance of fire protection services and appliances and lifts in working order or who interferes with or obstructs any person in the discharge of his duties shall:

- be guilty of an offence and upon conviction shall be punished with a fine as fixed by the Metropolitan Commissioner and as stipulated in Section 52 of The Maharashtra Regional and Town Planning Act, 1966;
- be subject to further suitable actions including demolition of unauthorised works, as stipulated under Section 53 of The Maharashtra Regional and Town Planning Act, 1966;
- in case of Licensed Engineer / Structural Engineer / Supervisor, subject to suitable action against him which may include cancellation of license and debarring him from further practice/ business for a period as decided by the Authority;

- (d) in case of registered architects, subject to action of the Council of Architecture as per the provisions of Architects Act, 1972 on the report of the Metropolitan Commissioner.

10.2. Revocation of Permission:-

- 1) Without prejudice to the powers of revocation conferred by Section 51 of the Act the Authority may, after giving the opportunity of being heard, revoke any development permission issued under these regulations where it is noticed by it that there had been any false statement or any misrepresentation of material fact in the application on the basis of which the development permission was issued and thereupon the whole work carried out in pursuance of such permission shall be treated as unauthorised.
- 2) In the case of revocation of the permission under sub- regulation (1), no compensation shall be paid.
- 3) Further the concerned person/applicant is subject to proceedings under the Indian Penal Code for making false statement before the public Authority. However, the decision to file a case shall be done under the express permission of the Metropolitan Commissioner.

11.0 AMENDMENT TO APPENDICES

The Metropolitan Commissioner shall be authorised to amend the **Appendices A to K** (except Appendix C) in these regulations, as and when necessary.

12.0 Provision with respect to NBC

Any aspect not covered in these regulations or in particular the planning, design and construction of building and its appurtenant services shall be done to the satisfaction of Metropolitan Commissioner for which, the NBC shall be reference document for conformity regarding the various aspect. The latest version to the NBC shall be referred at the time of enforcement of these regulations.

PART II GENERAL LAND DEVELOPMENT REQUIREMENTS

13.0 REQUIREMENTS OF SITE

13.1 SITES NOT ELIGIBLE FOR CONSTRUCTION OF BUILDING:

No piece of land shall be used as a site for the construction of building

- (a) If the Authority considers that the site is insanitary, incapable of being well drained or it is dangerous to construct a building on it;
- (b) If the entire site is within a distance of 9 m. from the edge of water mark of a minor water course (first order stream) and 15 m. from the edge of water mark of a major water course shown on Regional Plan or village/city survey map or otherwise;
Provided that where a minor water course passes through a low lying land without any well- defined banks, the owner of the property may be permitted by the Authority to restrict and or to realign the same within the same land according to cross section available with the PMRDA, modified from time to time without changing the position of the inlet and outlet of the water course. In such case marginal open spaces shall be as required under these regulations subject to minimum 4.50 m. from the edge of the trained nala;
- (c) Notwithstanding anything contained hereinabove, the Authority shall be entitled to take cognizance of the existence of all water courses whether shown on the Regional Plan or not, while sanctioning layouts and no person shall take any action without the permission of the Authority which results in reducing the water way or closing or filling up of any existing water course. If any watercourse, whether shown in the Regional Plan/Revenue Record or not, but existing on the site/land, owned by private person, the area under such water course shall not be deducted for computation of FSI.
- (d) If the owner of the plot has not shown to the satisfaction of the Authority all the measures required to safeguard the construction from constantly getting damped;
- (e) If the building is proposed on any area filled up with carcasses, excreta, filth and offensive matter till the production of certificate from the Competent Authority to the effect that it is safe from the health and sanitary point of view, to be built upon;
- (f) If the use of the site is for the purpose, which will be a source of annoyance to the health and comfort of the inhabitants of the neighbourhood;
- (g) If the plot has not been approved as a building site by the Metropolitan Commissioner;
- (h) If the proposed use of land or occupancy of the building on the site does not conform to the land use proposals in the Regional/Development Plans or Zoning Regulations;
- (i) If the level of the site is less than prescribed datum level depending on topography and drainage aspects;
- (j) If it doesn't derive access from an authorised street/means of access described in these Regulations;
- (k) If the land is within a prohibited distance from the Defence Establishments as decided by The Ministry of Defence, Government of India;
- (l) If it is within the river / lake boundary and blue flood line of the river (prohibitive zone);
- (m) If the site is hilly and having gradient more than 1:5 whether shown on the Regional Plan or not;
- (n) If the site is not developable / buildable by virtue of restrictions imposed under any law or guidelines of any Government department.

- 13.2 Distance of site from Electric Lines:** No structure including verandah or balcony shall be allowed to be erected or re-erected or any additions or alterations made to a building on a site within the distance quoted in Table No. 2 below in accordance with the prevailing Indian Electricity Rules and its amendments from time to time between the building and any overhead electric supply line. Amenity space shall not be shown under the overhead electric supply lines.

Table No. 2

Electric Lines	Vertic ally	Horizontally
	(m.)	(m.)
- 1 -	-2-	-3-
(a) Low and medium voltage Lines and Service Lines.	2.5	1.2
(b) High voltage lines up to including 33,000 V.	3.7	2
(c) Extra High voltage beyond 33,000 V.	3.7	2
	(Plus 0.3 m. for every additional 33,000 V. or part thereof)	(Plus 0.3 m. for every additional 33,000 V. or part thereof)
Note: The minimum clearance specified above shall be measured from maximum sag for vertical clearance and from maximum deflection due to wind pressure for horizontal clearance.		

13.3 CONSTRUCTION WITHIN FLOOD LINE:

- Area between the river bank and blue flood line (Flood line towards the river bank) shall be prohibited zone for any construction except parking, open vegetable market, garden, lawns, open space, cremation and burial ground, or like uses without any form of construction or any form of earthwork with external dumping, provided the land is feasible for such utilization.
- Area between blue flood line and red flood line shall be restrictive zone for the purposes of construction. The construction in the area may be permitted at a height of 0.45 m. above the red flood line.
- If the area between the river bank and blue flood line or red flood line forms the part of the entire plot in developable zone i.e. residential, commercial, public-semi-public, industrial, then, FSI of this part of land may be allowed to be utilised on remaining land.
- The blue and red flood line shall be as marked by the Irrigation Department or any other Government institutions dealing with the subject.

13.4 DEVELOPMENT WITHIN 30 M. FROM RAILWAY BOUNDARY:

Any construction within 30 m. from railway boundary shall be subject to restrictions as may be specified by the Railway Authority from time to time.

13.5 ENVIRONMENTAL COMPLIANCE:

Environment compliance/implementation of Green norms shall be carried out as per the provisions of Government Notifications issued from time to time.

13.6 RESTRICTIONS IN THE VICINITY OF AIRPORT:

Height restriction in the vicinity as well as the funnel of the Airport, as may be specified by the concerned authority from time to time, shall be observed.

13.7 RESTRICTIONS IN THE VICINITY OF ANCIENT MONUMENTS:

- 1) The Restrictions for Development in the vicinity of the declared monuments as prescribed under the Ancient Monuments and Archaeological Sites and Remains Act, 1958 and amendments made to it from time to time shall be observed.
- 2) The Restrictions for Development in the vicinity of the ancient monuments as prescribed under Ancient Monuments and Archaeological Sites and Remains Act, 1960 and amendments made to it from time to time shall be observed.

13.8 DEVELOPMENT ALONG HIGHWAYS / CLASSIFIED ROADS:

The development along the highways shall be subject to the provisions of National Highways Act, 1956 and State Highways Act, 1955 and orders issued by Ministry of Surface Transport, GoI and Public Works Department of the State Government, in these regards, from time to time.

A service road of 12 m. wide shall be provided along National and State Highways on both sides. These service roads may not be provided in piecemeal where authorized development / construction have already been taken place without the provisions of service road.

13.9 DISTANCE FROM LAND FILL SITES:

For any residential/commercial development, segregating distance from the land fill site (as determined by the Competent Authority) shall be observed as specified under Solid Waste Management Rules in force from time to time or as specified by Competent Authority.

13.10 AUTHORITIES TO SUPPLY COMPLETE INFORMATION TO THE PMRDA:

The PMRDA shall obtain information on restrictions to be imposed on developments from the concerned Government agencies as per their respective legislations/regulations/rules as mentioned above. This information shall be published by the PMRDA on its portal/website as and when it is updated by the concerned department. However, it is the duty of the applicant to ensure that restrictions informed by the authorities are followed scrupulously. The Metropolitan Commissioner shall ensure compliance of the restriction informed by the concerned authorities while sanctioning the development permission.

14.0 MEANS OF ACCESS

- 14.1 Every plot / building whether existing or proposed, shall have means of access as required in these Regulations.
- 14.2 Every person who erects a building shall not at any time erect or cause or permit to erect or re-erect any building which in any way encroaches upon or diminishes the area set apart as means of access.

14.3 Width of Means of Access:-

A) For Residential Development -The plots shall abut on a public means of access like street / road. Minimum width of access / layout road / internal road in any development proposal / subdivision / group housing shall be as given in Table No.3.

Table No-3

S.No.	Length of Means of access in mt	Width of Means of access in mt
i	upto150	9.00
ii	above 150 and to upto300	12.00
iii	more than 300	15.00

B) For Other than Residential Development –The minimum width of access / layout road / internal road in any development proposal other than residential (for commercial/industrial use) shall be as given in Table No.3(a).

Table 3(a)		
Sr. no.	Length of Mean of Access in m.	Width of Means of Access in m.
i	Upto 75	12
ii	75 to 150	15
iii	Above 150	18 or more

NOTE -1 The means of access shall be clear of required marginal open spaces from the existing building line. In no case, development on plots shall be permitted unless it is accessible by the authorized public street existing prior to coming in to force of these Regulations or road from the layout sanctioned prior to these Regulations.

- 14.3.1 Pathways:** -A pedestrian approach to the buildings from road / street / internal means of access wherever necessary, shall be through paved pathway of width not less than 2.0 m., 3.0 & 4.5 m. provided its length measured from exit way of the building is not more than 20 m. 40 m and 60m. respectively from the main / internal means of access. If the length is more than 60 m., then regular street as provided in Table No.3 shall be necessary. This provision shall also apply to group housing scheme or layout of building for other uses except development under regulation no.21.4.
- 14.3.2** The length of means of access shall be determined by the distance from the farthest plot (building) to the public street. The length of the subsidiary access way shall be measured from the point of its origin to the next wider road on which it meets.
- 14.3.3** In the interest of general development of an area, the Metropolitan Commissioner may require the means of access to be of larger width than that required under regulation No. 14.3.
- 14.3.4** In case where a private passage is unrestrictedly used by public for more than 10 years as a means of access of width not less than 9 m. to a number of plots, the Metropolitan Commissioner may take steps including improvement under, the provision of relevant Act to declare it as a public street
- 14.3.5** In congested areas in the case of plots facing street / means of access less than 4.5 m. in width the plot boundary shall be shifted to be away by 2.25 m. from the central line of the street/ means of access way to give rise to a new street / means of access way of width of 4.5 m. clear from the structural projections.
- 14.4.** Means of access shall be levelled, metalled, flagged, paved, sewerred, drained, channelled, lighted, laid with water supply line and provided with trees for shade (wherever necessary) to the satisfaction of the Authority, free of encroachment and shall be maintained in a condition to the satisfaction of the Metropolitan Commissioner.
- 14.4.1.** If any private street or any other means of access to a building is not constructed & maintained as specified above, the authority may by written notice require the owner or owners of the several premises fronting or adjoining the said street or other means of access or abutting thereon or to which access is obtained through such street or other means of access or which shall benefit by works executed to carry out any or more of the aforesaid requirements in such manner and within such time as the authority shall direct. If the owner or owners fail to comply with this direction,

the authority may arrange for its execution and recover the expenses incurred from the owner/ owners.

- 14.5. Access from the Highways/classified roads: Generally the plot / building along Highway and classified roads shall derive access from service road. However, highway amenities like petrol pump; hotel etc. may have an access direct from Highways and such other roads having a width of 30 m. or more. The above will be subject to the provisions of State Highways Act, 1965 and National Highway Act 1956. Provided that in suitable cases, the planning authority may suspend the operation of this rule till service roads are provided.
- 14.6. For building identified in Regulation No. 6.2.6.1, the following additional provisions of means of access shall be ensured;
- (a) The width of the main street on which the building abuts shall not be less than 12 m. and one end of this street shall join another street of width not less than 12 m. in width subject to Regulation No.14.3.
 - (b) The approach to the building and open spaces on its all sides (see Regulation No. 17.1, 17.2 and 17.3) shall be minimum 6 m. and the layout for the same shall be approved in consultation with the Fire Officer, Fire Brigade Authority and the same shall be of hard surface capable of taking the weight of fire engine, weighing up to 45 tones. The said open space shall be kept free of obstructions and shall be motorable.
 - (c) Main entrances to the plot shall be of adequate width to allow easy access to the fire engine and in no case it shall measure less than 4.5 m. The entrance gate shall fold back against the compound wall of the premises, thus leaving the exterior access way within the plot free for movement of fire engine / fire service vehicles. If main entrance at boundary wall is built over, the minimum clearance shall be 4.5 m.

15.0 REGULATIONS FOR LAND SUB-DIVISION AND LAYOUT

15.1 Layout or Sub-division proposal shall be submitted for the following:

- (i) When more than one building excepting for accessory buildings in the case of residential building is proposed on any land, the owner of the land shall submit proposal for proper layout of building or sub-division of his entire contiguous holding.
- (ii) When development and redevelopment of any tract of land which includes division and sub- division or amalgamation of plots for various land uses within a colony.
- (iii) When group housing scheme or campus /cluster planning of any use is proposed.

15.2 Roads / streets in Land Sub-division or Layout.

- 15.2.1 The width of roads/ streets/ public and internal access way including pathway shall conform to provisions of Regulation No. 14.3 to 14.6.
- 15.2.2 In addition to the provisions of Regulation No. 14.3 Cul-de-sacs giving access to plots and extending upto 150 m. normally and 275 m. maximum with an additional turning space at 150 m. shall be allowed only in residential area, provided that Cul-de-sacs would be permissible only on straight roads and further provided that cul-de-sacs ends shall be higher in level than the level of starting point. The turning space, in any case shall be not less than 81 sq. m. in area with no dimension being less than 9 m.
- 15.2.3 **Intersection of Roads:-** At junctions of roads meeting at right angles, the rounding off at the intersection shall be done, unless otherwise directed by the Metropolitan Commissioner, with the tangent length from the point of intersection to the curve being 1/2 the road width across the direction of tangent as given below: The building shall also set back at required marginal distance from this rounding off.




Fig. 1- Rounding off intersections at junctions




Fig.2. - Rounding off intersection at junctions.

15.2.3.1 For junctions of road meetings at less than 60 degrees, the rounding off or cut or similar treatment shall have tangent length of U and V from the intersections point as shown in diagram 2. The tangent length at obtuse angle junction shall be equal to half the width of the road from which the vehicle enters as shown in diagram 2. Provided however, that the radius for the junction rounding shall not be less than 6 m.

15.2.3.2 While granting the development permission for land sub-division or group housing/campus planning, it shall be necessary to coordinate the roads in the adjoining lands. Also, proper hierarchy of roads shall be maintained while deciding width of road in addition to the regulations no. 14.0 and 15.2. The design of roads in PMRDA area shall be as per Annexure I.

15.2.3.3 Whenever called upon by the Metropolitan Commissioner to do so, areas under roads shall be handed over to the Metropolitan Commissioner by way of deed after development of the same for which nominal amount of Re 1/- shall be paid by the Authority.

15.3 Recreational open spaces:

15.3.1.1 In any layout or subdivision or any development of land for any use/zone admeasuring 0.20 Ha. or more, after deducting D.P / R.P. road and reservation area, if any, 10% of the net plot area shall be reserved as recreational open space, which shall as far as possible be provided in one place. In case of land admeasuring more than 0.8 ha. recreational open space may be allowed to be reserved at different locations in the same layout provided that the size and other dimensions conform to the provisions herein below.

- i) The above-mentioned area of 0.2 Ha. shall be measured with reference to original holding as on 11th January 1967 and not with reference to sub-divided holding in revenue / city survey record thereafter without the permission under the Maharashtra Regional & Town Planning Act, 1966. However, this provision shall not be applicable to plots compulsorily got subdivided below 0.4 hec due to the DP reservations / RP/DP Roads/ Road widening/deemed reservations or any other proposal of the PMRDA.

For the land which are sub-divided after 11th January 1967 without taking prior permission from the Planning Authority and having plot area below 0.20 hectare, prior to the coming in to force of these regulations, the applicant may adopt any option of-

- a) providing 10% open space subject to minimum 200 sq. m., or
 - b) availing the reduced FSI on such land to 75% of the basic FSI as otherwise permissible. In such cases premium FSI or loading of TDR shall be permissible on such plot proportionately.
- ii) For the plots having area upto 0.20 Ha., regularised under the Maharashtra Gunthewari Development (Regularisation, Upgradation and Control) Act, 2001, no such open space shall be required for the development permission on such plot having area upto 0.20 Ha.
 - iii) Notwithstanding anything contained in the definition of —Open Space in this regulation, such recreational open space may be permitted on podium in congested / non congested area subject to Regulation no.18.12

Provided that, in case of lands declared surplus or retainable under Urban Land (C & R) Act, 1976, if the entire retainable holding or entire surplus holding independently admeasures 0.2Ha., or more, then 10% recreational open space shall be necessary in respective holding.

Provided further that such recreational open space shall also be necessary for group housing scheme or campus/ cluster planning for any use / zone.

Provided further that, no such open space shall be necessary in case of layout or subdivision of plots from already sanctioned layout by the Authority where the requisite recreational open space has already been left in the sanctioned layout.

Provided further that no such open space shall be necessary for development of the reservations in the Regional/Development Plans designated for the purpose other than residential.

In case of development of land for educational purpose, in lieu of 10% recreational open space, atleast 40% of the gross area, excluding the area under Regional/Development Plan road and reservations in Regional/Development Plan, (or as decided by the Government from time to time) shall be earmarked for playground. Notwithstanding anything contained in this regulation, the shape and location of such open space shall be such that it can be properly used as playground. Provided that, the area of such playground shall not be deducted for computation of FSI.

15.3.2 The owner shall give an undertaking that the recreational open space shall be for the common use of all the residents or occupants of the layout / building unit.

- a) On sanction of the development permission, the recreational open space shall deemed to have vested in the society / association of the residents / occupants except otherwise specified. In case such society or association is yet to be formed, the owner shall give undertaking to the Metropolitan Commissioner that he will transfer the recreational opens pace to the society/ association whenever it is formed. The recreational open space shall not be sold / leased out / allotted/ transferred for any purpose, to any other person and it shall not be put to any other user except for the common use of residents/ occupants as mentioned in Regulation no.15.3.7.
- b) If the Metropolitan Commissioner is convinced that, such open space is being used in violation of the provisions as prescribed in these regulations, then, he shall take over possession of such land of recreational open space for maintaining it for the uses permissible in these regulation, subject to condition that it shall not be further handed over or allotted to any person/institute/authority to that effect.

Provided that, it shall not bar to return the possession of such open space to the original society/ association of plot owners, after taking due undertaking to that effect.

15.3.3 No permission shall be granted to delete / reduce open spaces of the existing sanctioned layout/ subdivision. However, while revising the layout, such recreational open space may be rearranged without decrease in area subject to minimum prescribed area under these Regulations with the consent of plot / tenement holders / co-owners.

15.3.4 The open spaces shall be exclusive of means of accesses / internal roads / designations or reservations in Regional/Development Plan roads and areas for road widening.

15.3.5 Such recreational open space may be allowed to be earmarked, partly or fully, in green belt area shown on the Regional/Development Plan after leaving distance of 15 m. from river and 9.0m. from nala, provided, such recreational space is sizable as required under this regulation. Provided that, the only user and concerned structures as may be permissible under the regulation no.19.8 in respect of Green belt, may be permitted in such open space.

15.3.6 Minimum dimensions -The minimum dimensions of such recreational open space shall be not less than 10m. and if the average width of such recreational open space is less than 20m. the length thereof shall not exceed 2 ½ times the average width.

15.3.7 Structures permitted in Open Space- If required, structure and uses which can be permitted without counting in FSI in the recreational open spaces shall be as under:

- 1) There may be maximum two storeyed structure with maximum 15% built up area of recreational open space, out of which maximum 10% built up area shall be allowed on ground floor and remaining can be permitted on 1st floor.

- 2) The structures used for the purpose of pavilion, gymnasium, fitness centre, club house, vipashyana and yoga centre, crèche, kindergarten, library, water tank, (underground or elevated), electric substation, generator set, pump houses, garbage treatment, public health out post/ centre or other structures for the purpose of sports and recreational activity (indoor or outdoor stadiums, etc. as per availability of area) may be permitted.
- 3) The remaining area of the recreational open space shall be kept open to sky and properly accessible to all members as a place of recreation, garden, or a playground without any obstructions. At least 20% of the open spaces as required by these regulations shall be made of pervious material. Use of grass pavers, paver blocks with at least 50% opening, landscape would be considered as pervious surface.
- 4) No detached toilet block shall be permitted.
- 5) A swimming pool may also be permitted in such a recreational open space. The ownership of such structures and other appurtenant users shall vest in all the owners on account of whose cumulative holdings, the recreational open space is required to be kept in the land.
- 6) The proposal for the construction of such structure should come as a proposal from the owner/s, owners' society / societies or federation of owners' societies and shall be meant for the beneficial use of the owners / members of such society / societies / federation of societies.
- 7) The remaining area of the recreational open space shall be kept open to sky and properly accessible to all members as a place of recreation, garden or a playground.
- 8) The owners' society / societies, the federation of the owners' societies shall submit to the Authority, a registered undertaking agreeing to the conditions in (5) & (6) above while obtaining permission for the above said construction.

15.3.8 Every plot meant for a recreational open space shall have an independent means of access. In case of group housing scheme, if such recreational open space is surrounded by buildings and is meant for use by the occupants of those buildings, then independent means of access may not be insisted.

15.4 PROVISION FOR AMENITY SPACE

In any layout or sub division of plots or development proposal for residential/commercial users, having area 0.4 ha. or more, amenity space of 15% on gross area excluding area under Regional Plan road and reservation in Regional Plan/Development Plan, if any, shall be provided while granting permission to the layout / development proposal. These Amenity Space shall be deemed to be for public purpose for the use of PMRDA and Floor Space Index (FSI) in lieu thereof may be made available in-situ (on remaining land). The calculation of this in-situ FSI shall be shown on the layout / building plan. If the owner desires to have TDR against it, instead of in-situ FSI, then he may be awarded TDR. The generation of TDR or in-situ FSI shall be equivalent to the quantum mentioned in Regulation no. 46.0 in respect of TDR.

Provided that, the Metropolitan Commissioner shall ensure that amenity space shall be earmarked in the layout so that after amalgamating the amenity spaces in the adjacent layouts, it becomes larger in area. It shall be approachable by minimum 12 m. wide road except the cases where 12 m. approach road to the site is not available.

Provided that, in case of sub-division of land measuring 8000 sq. m. or more in area in an industrial zone, 5 percent of the total area in addition to 10 percent stipulated in Regulation No 15.3.1, shall be reserved as amenity open space which, shall also serve as general parking space. When the additional amenity open space exceeds 1500 sq. m., the excess area may be used for construction of buildings for banks, canteens, welfare centre, health centre, offices, convenient shopping, crèches and other common purposes considered necessary for industrial

users as approved by the Metropolitan Commissioner. However, this regulation shall not be applicable to Regulation no.19.6(v), (i.e. Regulation for allowing Residential /Commercial user in Industrial Zone), wherein separate provision for land for public amenities / utilities is made.

Provided that, it shall not be necessary to provide such Amenity space, if the land is proposed to be developed for IT or ITES users only and having area upto 2.00 Hectare.

Provided further that, this regulation shall not be applicable where entire development permission is for amenities specified in definition of amenity space.

Provided further that, this regulation shall not be applicable for revision of earlier sanctioned development permissions granted under the regulations in force prior to these regulations, where no such amenity space is provided, or such amenity space is allowed to be developed by the owner in earlier sanctioned development permission.

Provided further that, the option of development of amenity space by the owner or handing over of amenity space to PMRDA shall be open to the owner in case of earlier approved layouts/development permissions, subject to the written permission for the specific public use as defined in regulation no. 2.9.

Provided further that, the entire amenity space required to be shown as above shall be shown at a single location.

However, if some amenity space is provided in the earlier permission, then quantum of such amenity space in the revised permission –

- i) shall be limited to the area provided in earlier permission.
- ii) shall not be reduced even though area of such amenity space is more than what is specified in this regulation.

15.4.1 DEVELOPMENT OF AMENITY SPACE

Development of amenity space may be carried out by the PMRDA either on its own or through the private participation for monetization of land. The priority for development of particular amenity in particular Residential area shall be decided by the Metropolitan Commissioner. Amenity Space may be allowed to be utilized for uses mentioned in these regulations as per 2.9

15.5 PROVISION FOR ELECTRIC SUB-STATION

In case of development/re-development of any land, building or premises mentioned below, provision for electric sub-stations may be made as under.

Sr. No.	Plot Area	Maximum requirements
1	Plot above 2000 sq.m.	One single transformer sub-station of the size of 5m.x5m. and height of not more than 5m.
2	Layout or sub-division of a plot measuring 2 .0 ha. or more.	A suitable site for an electric sub-station.

Provided that the sub-station, if required, may be constructed in such a manner that it is away from main building at a distance of at least 3 m. and does not affect the required side marginal distances or prescribed width of internal access or larger open space.

15.6 PLOT AREA, PLOT WIDTH FOR VARIOUS USES:

Minimum plot areas and widths for various uses shall be as given below in the **Table No.4**

Table No. 4				
MINIMUM PLOT AREA, MINIMUM WIDTH, FOR VARIOUS USES				
Sr. No.	Uses	Plot area (in sq.m.)	Min. Plot Width	Type of Development
(1)	(2)	(3)	(4)	(5)
1	Residential and Commercial (except those in 2,3 & 4 below)	i) 30 and above but upto 125	As per Table No. 16	Row
		ii) Above 100 but less than 250		Semi-detached/ Detached
		iii) 250 & above		Detached
2	Plots in EWS Housing / High Density Housing / Sites and Services / Slum Up-gradation / Reconstruction Scheme by public authority.	25 and above but upto 125	As per Table No.16	Row
3	Auto Fuel Filling station -			
	(a) Without service bay	510	16.75 m	Detached
	(b) With service bay	1100	30.5 m	Detached.
4.	Industrial	300	10 m	Detached.
Note : In case of sr.no.1, pattern of development permissible within a plot shall be shown in dotted line while approving the layout. However change in pattern may be permitted in future, if it fits in to above pattern of development and does not disturb the overall pattern of development already approved.				

15.7 NET PLOT AREA AND COMPUTATION OF FSI

For the purpose of computing FSI/Built-up area, **the net area of the plot** shall be as under:

- In case of a plotted layout/sub-division /group housing scheme / any development, net area shall be the balance plot area, after deducting the area covered by amenity space under Regulation no 15.4 which is deemed reservations and Regional/Development Plan proposals, if any, from the total area of plot.
- For the purpose of computation of FSI/built-up area, the net area of the plot shall only be considered.
- In case of plotted layout, the basic FSI of such net area shall be distributed on all plots on pro- rata basis or on certain plots to which land owner desires, subject to maximum receiving potential prescribed in these regulations.
- In case of plots from already approved layouts, the plot area shall be treated as net plot area.
- The above regulations in respect of net plot area and computation of FSI shall apply to proposals in all land use zones.

15.8 Relocation of DP / RP Sites / DP / RP Proposals while approving the layout of land:

If the land proposed to be laid out for any development is affected by any reservations for public purposes, the Metropolitan commissioner may allow adjustment in the location of such reservation to suit development without altering the area of such reservation. Provided that no such shifting of the reservations shall be permitted:

- (a) if the reservation proposed to be relocated is in parts;
- (b) beyond 200 mts. of the location in the Development Plan / Regional Plan;
- (c) beyond the holding of the owner in which such reservation is located;
- (d) unless the alternative location and size is at least similar to the location and size of the development plan / regional plan as regards access, levels, etc.;
- (e) unless the relocation is within area covered by the layout or development permission under sanction; and
- (f) if the reservation is already shifted under these regulations.
- (g) if the land is reserved in view of its geographical location like eco sensitive, Nala, training reservation etc.


The Development Plan / Regional Plan shall be deemed to be modified to that extent.

- 15.9 Adjustment of the boundaries of the reservation:** The Metropolitan Commissioner with the consent of the owner may adjust the boundaries of the reservation in the same land and location provided that the area of such reservation is not reduced.


15.10 AMALGAMATION OF PLOTS

Amalgamation of plots shall be permissible if they are contiguous permissible subject to following:

- a) Amalgamation of plot having incompatible zoning in Regional/Development Plan shall not be allowed.
- b) Amalgamation of plot which is not desirable from planning point of view (eg. as shown in below) shall not be permitted.



These plots shall not be amalgamated.



This plots shall not be amalgamated.

16.0 LAND USE CLASSIFICATION AND PERMISSIBLE USES

- (1) In case of Development / re-development of any land, building or premises, the intended use shall conform to the land use, purpose of designation, allocation or reservation, assigned to it in the Regional Plan as the case may be, unless specified otherwise.
- (2) **Lawful existing non-conforming uses** - Any lawful non-conforming use of premises existing prior to the date of enforcement of these regulations, shall continue and may be allowed to be expanded within the holding in the original sanction, unless in the opinion of the Metropolitan Commissioner the activity poses danger to public safety and/ or life and that when a building, containing non-conforming use is pulled down or has fallen down, the use of the new building shall be in conformity with these Regulations or with lawful existing use.

Provided further, that non-conforming cattle stables and industries causing nuisance shall be shifted to a conforming area within such period as may be decided by the Metropolitan Commissioner.

- (3) **Existing features shown on Regional Plan** – The existing features shown on Regional Plan are indicative and stand modified on Regional Plan as per actual position. Mention of particular use on Regional Plan, shall not bar the owner from permission allowed in the zone shown for such land. Also, boundaries of s. no./gat. no, alignment of existing road / nalla, water bodies and other physical features of land shall be as per measurement plan of Land Records Department.
- (4) **Development of Parking** – The Metropolitan Commissioner may develop any land in any developable zone, owned by or in possession of the PMRDA, for public parking single or multi-

(5) **Discontinuance of Zoning in pursuance of existing use**— If any land is shown in Public semi –public zone, Public Utility, because of the activity existed there-on, such lands shall be deemed to have been shown in the adjacent predominant Zone after such activity ceases to exist and thereupon, the development shall be permissible as per the adjoining predominant zone, with the special permission of Metropolitan Commissioner.

(6) **Development permission granted as per the I to R provisions** - In industrial zone on which Residential/ Commercial permission is granted is deemed to be converted into Residential/ Commercial zone to the extent of that area, after issuance of full and final occupation certificate to the project.

17.0 OPEN SPACE, SETBACK AREA AND HEIGHT LIMITATIONS

17.1 Exterior Open Spaces:

Provisions for open spaces at the front side/sides and rear of the building shall be as given in Part IV of these Regulations.

17.2 Buildings Abutting Two or More Streets:

When a Building abuts two or more streets, the setbacks from the streets shall be such as if the building is fronting on each such street.

17.3 Marginal distances for Buildings of Higher Heights

(a) **Front Margin** - Front margin shall be as given below with reference to height of building

i)	Height above 15 m. & upto 24 m.	4.5 m for residential and 6.00 m. for residential with mix use
ii)	Height above 24 m. & upto 36 m.	6.0 m.
iii)	Height above 36 m. & upto 50 m.	9.00 m.

Provided that, in case of group housing scheme where building abuts on internal road, the minimum 3.0 m. set back from internal road or distance between two buildings whichever is more shall be provided. For Regional /development plan road or classified road or through road, passing through Group Housing Scheme or any deemed public road, the setback as prescribed in the regulations shall be provided.

(b) **Side or rear marginal distance** - Side or rear marginal distance **in relation to the height** of the building for light and ventilation shall be as below

The marginal distance on all sides shall be as per **Table No. 16** for building height 15.0 m. and below. For height more than 15.0 m., the marginal distance on all sides except the front side of a building shall be minimum $H/4$ (Where H = Height of the building above ground level) subject to a minimum of 3.0 m. for residential building, 4.5 m. for commercial building and 6.0 m. for special building mentioned in definition no. 2.77.13. Provided that such marginal distance shall be subject to maximum of 16.0 m. If the land owner wishes to keep higher margins he may be allowed to do so.

Provided further that the building height for the purposes of this regulation and for calculating the marginal distances shall be exclusive of height of parking floors upto 6.0 m.

Provided also that, for building having shops / commercial user on any floor, 50% of front marginal distances shall be made available exclusively for pedestrians.

17.3.1 In case of layout of two or more buildings of any users:-

i) **Distance between two buildings-** The distance between two buildings shall be the side/rear marginal distance required for the taller building between the two adjoining buildings.

ii) Provided that, the path way / internal road may be allowed to be proposed in such marginal distance by keeping 3.0 m. distance on both side from such internal road.

Provided also that, where rooms do not derive light and ventilation from the exterior open space, the distance between the two buildings may be reduced by 1 m. subject to a minimum of 3 m. (if necessary 6.0 m. in case of special building) and maximum of 8.0 m. No projections shall be permitted in this exterior space.

17.3.2 In case of group housing scheme where building abuts on internal road, the minimum 3.0 m. set back from internal road or distance between two buildings whichever is more shall be provided. For Regional/Development Plan road or classified road or through road, passing through Group Housing Scheme, the setback as prescribed in the regulations shall be provided.

17.4 Interior & Exterior chowk:

17.4.1 (a) Interior chowk: Wherever habitable rooms or kitchen derives ventilation from inner chowk or interior open space, the size of such interior open space shall not be less than 3m. x 3m. upto height of 18m. and for height more than 18m., the interior open space shall not be less than $H/6$ m. x $H/6$ m. where H = height of highest wall of the chowk.

(b) Exterior chowk: The minimum width of the exterior chowk for the purpose of light and ventilation, shall not be less than 2.4 m. and depth shall not exceed 2 times the width, for buildings upto 17m. height and for height more than 17m., the exterior open space shall not be less than $H/7$ m. x $H/7$ m. where H = height of highest wall of the chowk. If the width of the exterior chowk is less than 2.4 m. it shall be treated as a notch and shall not be considered for deriving ventilation.

However, for (a) and (b) above maximum distance shall be subject to the maximum limit prescribed for distance between two buildings.

17.4.2 Where only water closet, bathroom, combined bathroom and water closet are abutting on the interior open space, the size of the interior open space shall be in line with the provision for ventilation shaft as given in Regulation no. 18.15.ii)

17.5 Area and Height limitations - The area and height limitations, height of buildings, floor space index, abutting different road widths shall be as given in Part IV and Regulation No. 15.6.

17.6 Permissible Structures / Projections in marginal open spaces/ distances

The following projections shall be permissible in marginal distances:

(a) Projections into distances: - Every open space provided either interior or exterior shall be kept free from any erection thereon and shall be open to the sky and no cornice, chajja, roof or weather shade more than 0.75 m. wide shall overhang or project over the said marginal distances so as to reduce the width to less than the minimum required. However, sloping/horizontal chajja provided over balcony/ gallery etc. may be permitted upto balcony projections at horizontal level.

(b) Balconies - as specified in regulation no 18.13

(c) A canopy not exceeding 5m. in length and 2.5 m. in width in the form of cantilever and unenclosed over the main entrance providing a minimum clear height of 2.40 m. below the beam bottom of canopy. The canopy shall not have access from upper floors (above floors), for using as sitting out place. There shall be a minimum clearance of 1.5 m. between the plot boundaries and canopy. Provided that, more than one canopy may be allowed in case of special buildings, as per requirement.

(d) A projection of maximum 30 cm. on roof top terrace level may be allowed throughout the periphery of the building. In case of pitched roof projection of maximum 45 cm. at rooftop terrace level throughout periphery of the building shall be allowed.

(e) Accessory buildings:- The following accessory buildings may be permitted in the marginal open spaces :-

- i) In an existing building where toilet is not provided, a single storeyed toilet subject to a maximum area of 4.0 sq. m. in the rear or side open space and at a distance of 7.5 m. from the road line or the front boundary and 1.5 m. from other boundaries may be permissible. The Commissioner may reduce 1.5 m. margin in exceptional cases to avoid hardship.
- ii) Parking lock up garage not exceeding 2.4 m. in height shall be permissible in the rear corner of the plot with independent bungalow. Parking lock up garage when attached to main building shall be 7.5 m. away from the road line and shall be of such constructions giving fire resistance of 2 hours. The area of sanitary blocks and parking lock up garage shall be taken into account for the calculation of FSI.
- iii) Suction tanks, soak pits, pump room (maximum 10 sq.m.), electric cabin of sub-station of gen-set area, electric meter room as per requirements, garbage shaft for wet and dry garbage separately with collection chamber, space required for fire hydrants, electrical and water-fittings, water tanks, dustbins etc.
- iv) One watchman's cabin / booth not more than 5 sq. m. in built up area having min. 1.80 m. width or diameter. Cabin / booth shall be as per as possible at the entrance to the campus.

Note :- When a building abuts falling on three or more roads then above mentioned user, except (iv), shall be permissible in front setback facing the smaller road of less important from traffic point of view.

f) "Ramp" for basement in side and rear marginal distances subject to provisions under these regulations.

g) Fire escape staircase of single flight not less than 1.2 m.

h) Staircase mid-landing of 1.2 m. width with clear minimum headway of 2.1 m. below the mid-landing. However, clear distance from edge of landing to the plot boundary shall not be less than 1.8 mt.

i) Architectural projections - Architectural projections upto 1m. which will not reduce the side marginal spaces by 3 m., sky signs and Hoardings as per the policy approved by the Metropolitan Commissioner.

j) Construction of ottas, railings, barricades or supporting columns for canopy or porch shall not be permitted within the minimum required front marginal distances. However, steps may be permitted within 1.2 m. from the building line.

k) Supported double height terraces (within the building line) as mentioned in regulation no.18.26

l) Open parking spaces excluding the area under the fire driveways.

17.7 Exclusion of structures / projections for FSI calculation

- i) Structures/ Projections /features / ornamental projection of glass façade permitted in marginal open spaces as mentioned in Regulation No.17.6 (a),(b),(c),(d) , (e)(iii), (f), (g), (h),(i), (j), (k).
- ii) Stilt / Multi-storied floors /podium/ basement used as parking including passage therein.
- iii) Areas covered by Porches, Entrance lobby / foyer, canopies, Air conditioning / air handling plant rooms, lift well, machine room and service floor of height not exceeding 1.8 m. for hospitals, shopping malls, plazas and Star category hotels (rating with three stars and above) on payment of premium as may be decided by the Commissioner.
- iv) Area of structure for an effluent treatment plant as required as per the requirements of the Maharashtra Pollution Control Board or other relevant authorities.

- v) Rockery, Well and well structures, plant, Nursery, Water pool platform around a tree, Fountain bench, Chabutara with open top and unenclosed sides, Ramps, Compound wall, Gate slide / swing, Steps outside the buildings, Domestic working place (open to sky), Overhead water tank on top of the building, Refuge area for high rise buildings as specified in Regulation No. 18.28.6
- vi) Telecommunication tower, antenna and allied activities.
- vii) Atrium in shopping malls, public buildings on payment of premium as may be decided by the Metropolitan Commissioner.
- viii) Open to sky swimming pool of the top terrace and top most podium.
- ix) Structures permissible in recreational open space as per regulation No.15.3.7

17.8 Height of Building

17.8.1 (a) Height of building is allowed to the extent that is required to consume the maximum building potential on plot as given in the table under regulation no. 17.1 & 17.3, subject to other restrictions as per these regulations, and prior approval of Chief Fire Officer, PMRDA, if required under this regulation.

Notwithstanding anything contained in these regulations, for the building having height more than 36.0 mt., the minimum road width shall be 12.0 mtr.

17.9 Height Exemptions -

The appurtenant structures such as roof tanks and their supports, ventilating, air-conditioning, lift rooms and similar service equipment, stair cover, chimneys and parapet walls and architectural features not exceeding 1.20 m. in height and **Parking floors not exceeding 6.0 m in height**, shall not be included in computation of height of building **for the purposes of marginal distances only**.

17.10 Deleted

17.11 PARKING, LOADING AND UNLOADING SPACES: -

17.11.1 Parking spaces –

Wherever a property is to be developed or redeveloped, parking spaces at the scale laid down in these Regulations shall be provided. When additions are made to an existing building, the new parking requirements will be reckoned with reference to the additional space only and not to the whole of building but this concession shall not apply where the use is changed. The provisions for parking of vehicles shall be as given in Table No.7 & 8. Area required for parking spaces shall be increased by 50 % for PMRDA area.

17.11.2 General space requirements:-

- (i) **Types:** The parking spaces mentioned below include parking spaces in basements or on a floor supported by stilts, or on upper floors, covered or uncovered spaces in the plot and / or lock up garages. The height of the stilt shall generally be allowed upto 3 m.
- (iii) **Size of parking space:** The minimum sizes of parking spaces to be provided shall be as shown below in **Table No.6:-**

Table No- 6		
S.No.	Type of Vehicle	Minimum Size/ area of parking space
(1)	(2)	(3)
(a)	Motor vehicle	2.5 m X 5 m
(b)	Scooter, Motor Cycle.	1.0 m. x 2.0 m.
(c)	Bicycle	0.50 m x 1.4 m.
(d)	Transport vehicle	3.75 m. X 7.5 m.
Note:	In the case of parking spaces for motor vehicle, upto 50 percent of the prescribed space may be of the size of 2.3 m. X 4.5 m.	

- (iii) **Marking of parking spaces:** Parking space shall be paved and clearly marked for different types of vehicles.
- (iv) **Maneuvering and other ancillary spaces:** Off street parking space must have adequate vehicular access to a street and the area shall be exclusive of drives, aisles and such other provisions required for adequate maneuvering of vehicles.
- (v) **Ramps for Basement parking :-** Ramps for parking in basement should conform to the requirement of Regulation No.18.11

Table No 7
Off Street Parking Spaces

Sr. No.	Occupancy	One parking Space for every	Congested Area			Non Congested Area		
			Car	Scooter	Cycle	Car	Scooter	Cycle
1	2	3	4	5	6	7	8	9
1	Residential i) Multi family residential	(a) 2 Tenements having built-up area more than 100sq.m.	1	1	1	1	2	2
		(b) 3 tenements having built-up area between 50 to 100sq.m.	0	2	4	1	3	3
		(c) 4 tenements having built-up area upto 50 sq.m.	0	4	4	0	5	5
		(a) For every five guest rooms	1	2	2	1	3	3
	ii) Lodging establishments tourist homes, hotels with lodging accommodation.							
	iii) Restaurants	(a) For hotel, eating houses 25sq.m. of area of restaurant including kitchen, pantry hall, dining rooms etc.	0	1	2	1	1	1
2	Institutional (Hospital, Medical Institutions)	For 100 sq.m. carpet area or fraction thereof.	1	2	2	1	4	4
3.	Assembly (theatres, cinema houses, concert halls, auditoria, assembly halls including those of college and hostels)	For every 40 Seats.	1	2	5	1	5	5
4.	Mangal Karyalaya / Marriage Halls, Cultural Halls	For every 100 sq.m. built up area or fraction thereof.	1	2	3	2	4	6

5	Educational – i) Primary School	100 sq. m. built up area or fraction thereof the administration area.	0	2	2	1	2	2
	ii) Secondary School	100 sq. m. built up area or fraction thereof of the entire built up area.	0	1	4	0	2	8
	iii) College	100 sq. m. built up area or fraction thereof the administration area and public service area.	0	2	5	1	2	8
6.	Government or semipublic or private business buildings.	100 sq. m. built up area or fraction thereof	1	1	2	1	3	3
7.	Mercantile (markets, departmental stores, shops and other Commercial users) including wholesale markets	100 sq. m. built up area or fraction thereof	1	1	2	1	3	3
8.	Industrial	300 sq. m. built up area or fraction thereof	0	2	2	1	3	3
9.	Storage (any type)	300 sq. m. built up area or fraction thereof	0	1	1	1	1	1
9.	Plots less than 200 sq. m. (any use)		0	1	1	0	1	1
Note-1) Plots upto 100 sq. m. as in the case of shops, row houses parking space need not be insisted.								
2) Fraction of parking unit need not be provided. However, in case where proportional number of vehicles is less than 1 (i.e. fraction) it will be rounded to the next full number.								
3) In case of independent single family residential bungalows having plot area upto 300 sq. m., parking space need not be insisted separately.								
4) Further a garage shall be allowed in rear or side marginal distance at one corner having minimum dimension of 2.5 m. x 5.0 m. & maximum dimension 3 m. x 6 m. i.e. minimum 12.5 sq. m. and maximum 18.0 sq. m. built up area.								
5) Mechanical Parking shall be permissible in case of parking provided over and above the requisite parking requirements stipulated under these regulations.								

Table No 8
Off Street Parking Spaces
For Township Projects Under Part IX

Sr. No.	Occupancy	One parking Space for every	Congested Area			Non Congested Area		
			Car	Scooter	Cycle	Car	Scooter	Cycle
1	2	3	4	5	6	7	8	9
1	Residential i) Multi family residential	(a) 2 Tenements having built-up area more than 100sq.m.	1	2	2	2	2	2
		(b) 3 tenements having built-up area between 50 to 100sq.m.	0	3	4	1	4	4
		(c) 4 tenements having built-up area upto 50 sq.m.	0	4	4	0	5	5
		(a) For every five guest rooms	1	3	3	2	3	3
	ii) Lodging establishments tourist homes, hotels with lodging accommodation.							
	iii) Restaurants	(a) For hotel, eating houses 25sq.m. of area of restaurant including kitchen, pantry hall, dining rooms etc.	0	2	2	1	2	2
	2	For 100 sq.m. carpet area or fraction thereof.	2	2	3	2	5	5
3.	Assembly (theatres, cinema houses, concert halls, auditoria, assembly halls including those of college and hostels)	For every 40 Seats.	1	2	5	2	7	7
4.	Mangal Karyalaya / Marriage Halls, Cultural Halls	For every 100 sq.m. built up Area or fraction thereof	1	4	4	2	8	8
5.	Educational – i) Primary School	100 sq.m. built up area or fraction thereof the administration area.	0	3	3	1	4	4
	ii) Secondary School	100 sq.m. built up area or fraction thereof of the entire built up area.	0	1	5	0	2	10

	iii) College	100 sq.m.built up area or fraction thereof the administration area and public service area.	0	2	6	1	4	10
6.	Government or semipublic or private business buildings.	100 sq. m. built up area or fraction thereof	1	2	4	2	4	4
7.	Mercantile (markets, department al stores, shops and other Commercials users) including wholesale markets	100 sq. m. built up area or fraction thereof	1	3	3	1	4	4
8.	Industrial	300 sq. m.built up area or fraction thereof	1	2	2	1	4	4
9.	Storage (any type)	300 sq. m.built up area or fraction thereof	0	2	2	1	2	2
9.	Plots less than 200 sq.m. (any use)		0	1	1	0	1	1

Note 1. -For plots upto 100 sq. m. as in the case of shops, row houses parking space need not be insisted.

Note 2. - Fraction of parking unit need not be provided. However, in case where proportional number of vehicles is less than 1 (i.e. fraction) it will be rounded to the next full number.

Note 3 :- In case of independent single family residential bungalows having plot area upto 300 sq. m., parking space need not be insisted separately.

Note 4 :- Further a garage shall be allowed in rear or side marginal distance at one corner having minimum dimension of 2.5 m. x 5.0 m. & maximum dimension 3 m. x 6 m. i.e. minimum 12.5 sq.m. and maximum 18.0 sq.m. built up area.

Note 5 - Mechanical Parking shall be permissible in case of parking provided over and above the requisite parking requirements stipulated under these regulation.

17.11.3 Off street parking space shall be provided with adequate vehicular access to a street, and the area of drives, aisles and such other provisions required for adequate maneuvering of vehicle shall be exclusive of the parking space stipulated in these regulations.

17.11.4 To meet the parking requirements as per these regulations, common parking area for group of buildings, open or multi-storeyed, may be allowed in the same premises.

17.11.5 In addition to the parking spaces provided for building of Mercantile (Commercial) like office, market, departmental store, shopping mall and building of industrial and storage, loading and unloading spaces shall be provided at the rate of one space for each 1000 sq. m. of floor area or fraction thereof exceeding the first 200 sq. m. of floor area, shall be provided. The space shall not be less than 3.75 m. x 7.5 m.

17.11.6 Parking lock up garages shall be included in the calculation for floor space for F.S.I. calculations.

- 17.11.7 The space to be left out for parking as given in this Regulation shall be in addition to the marginal distances left out for lighting and ventilation purposes. However, those spaces may be used for parking provided minimum distance of 3 m. (6.0 m. in case of special building) around the buildings is kept free of any parking or loading and unloading spaces. Such parking area may be allowed to cover on top by sheet roofing so as not to infringe the marginal distances to be kept open.
- 17.11.8 In case of parking spaces provided in basements, at least two separate ramps of adequate width and slope for entry and exit (as per Regulation No. 18.11) shall be provided preferably at opposite ends.
- 17.11.9 In case of Special Townships Areas, in addition to the regular parking area as per Regulation No.17.11, a space of 3.0 m. wide strip along the road on front shall be provided as visitors parking for the buildings with commercial or any use mixed with commercial. In such case, minimum front margin shall be 6.0 m. inclusive of 3.0 m. wide strip as above irrespective of the lesser front margin requirement in the applicable regulations.

18.0 REQUIREMENTS OF PARTS OF BUILDINGS:

This part sets out the standard space requirements of various parts of building, light and ventilation, the building services, fire safety, etc. The following parts of a building, wherever present, shall conform to the requirements given herein:

18.1 Plinth

- 18.1.1 The plinth of building shall be so located with respect to the surrounding ground level that adequate drainage of the site is assured. The height of the plinth shall not be less than 45 cm above the surrounding ground level. In areas subjected to flooding, the height of the plinth shall be at least 45cm. above the high flood level or greater than 45 cm. as may be decided by the Planning Authority in deserving cases.
- 18.1.2 **Interior Courtyards:** Every interior Courtyard shall be raised at least 0.15 m. above the surrounding ground level and shall be satisfactorily drained.
- 18.1.3 In the case of special housing schemes undertaken by public agencies for low income group and economically weaker section of society, the minimum height of plinth shall be not less than 30 cm.

18.2 Habitable Rooms

18.2.1 Size and dimension of Habitable Rooms

Internal dimensions and size of rooms for various uses and occupancies shall be as in table no.9 below.

Table No.9			
No	Occupancy	Minimum Area in sq. m.	Minimum width in m.
(1)	(2)	(3)	(4)
1	a) Any habitable room in residential building / room from any other occupancy like hostels, residential hotel, lodging & boarding/housing etc except kitchen.	9.5	2.4
	b) Any Habitable room from any other occupancy like hostels, residential hotel, lodging & boarding-houses etc.	9.5	2.4

2	Room in a single – room tenement in Housing scheme for EWS & LIG.	12.5	3.0
3	a) Room in two-room tenements-		
	i) one of the rooms	9.5	2.4
	ii) other room	7.5	2.4
	b) Room in a two-room tenement in Housing scheme for EWS & LIG		
	i) one of the room	9.0	2.5
	ii) other room	6.5	2.1
4	Single bedded room in a hostel of a recognized educational institutions	7.5	2.4
5	a) Shop in R 1 zone	6.0	1.8
	b) Shop in other than R 1 zones	10	2.0
6	Class room in an educational building	38	5.5
7	Institutional building (Hospital)		
	a) Special room	9.5	3
	b) General Ward	40	5.5
8	Cinema Hall, auditorium assembly hall etc.	In conformity with the Maharashtra Cinema Rules	

Note : Where enclosed balcony area is to be counted in minimum dimensions required for a room, then such enclosed width shall not be more than 1/3 of the dimension of that room.

18.2.2 Height of Habitable Rooms

The minimum and maximum height of a habitable room shall be given in Table No. 10 hereunder:

Table No. 10			
Height of Habitable Rooms			
No.	Occupancy	Minimum Height (m)	Maximum Height (m)
(1)	(2)	(3)	(4)
1	Flat Roof -		
	a) Any habitable room	2.75	4.2
	b) Habitable room in LIG Housing	2.6	4.2
	c) Air-conditioned habitable room	2.4	4.2

	d) Assembly Halls, Residential Hotels of 3 star category and above, Institutional, Educational, Industrial, Hazardous or storage occupancies, Departmental Stores, Malls, IT Buildings, Office Buildings, Entrance Halls and Lobbies to department stores and assembly halls.	3.6	4.2 Subject to written permission of the Metropolitan Commissioner greater height may be permitted.
	e) shops	3.0	4.2
2	Pitched roof-		
	a) Any habitable room	2.75	4.2
	b) Habitable room in EWS / LIG Housing.	2.6(average with 2.0 m. at the lowest point)	4.2(average with 3.2 m. at the lowest point)

Provided that -

- the minimum head-way under any beam shall be 2.4m.
- in all occupancies, except those included in serial no. 1 (d) in the Table above, any height in excess of 4.2 m. shall be deemed to have consumed additional FSI of 50 % of the relevant floor area.

18.3 Kitchen

18.3.1 Kitchen size -

- The area of the kitchen where separate dining area is provided shall be not less than 5.5sq.m. with a minimum width of 1.8m, where a kitchen, which is intended for use as a dining area also, shall have a floor area of not less than 7.5 sq.m. with a minimum width of 2.1m.
- In case of special housing scheme for low income group and economically weaker section of the society, PMAY, the size of a cooking alcove serving as cooking space shall not be less than 2.4sq.m. with a minimum width of 1.2m.. The size of individual kitchen provided in a two-roomed house shall be not less than 3sq.m. with a minimum width of 1.5 m.

18.3.2 Height: The room height of a kitchen measured from the surface of the floor to the lowest point in the ceiling (bottom of slab) shall not be less than 2.75 m.

18.3.3 Other Requirement: Every room to be used as kitchen shall have-

- unless separately provided, means for the washing of kitchen utensils which shall lead directly or through a sink to grated and trapped connection to the waste pipe;
- an impermeable floor;
- a flue, if found necessary,
- window of not less than 1 sq.m. in area, opening directly on to an interior or exterior open space (in case of naturally ventilated space).

18.3.4 Requirements regarding pantry:-

A pantry shall have –

- A floor area of not less than 3 sq.m. with the smaller side not less than 1.4 m.
- A sink for the cleaning of kitchen's utensils which shall drain through a grated and trapped connection to the waste water pipe where water borne sewerage system is not available and the grated connection shall be made to the pucca surface drain leading to soak pit. or other approved system of disposal; and
- An impermeable floor and an impermeable dado 0.9 m. high.

18.4 Bath Rooms, Water Closets, Combined bath room and water closet

18.4.1 Size of bathroom and water closet -

- i) The size of a bathroom shall be not less than 1.5 sq.m. with a minimum width 1.0 m. The size of a water closet shall be not less than 1.0 sq.m with a minimum width of 0.9m. The minimum area of a combined bathroom and water-closet shall be 2.4 sq.m. with a minimum width of 1.0 m.
- ii) In the case of EWS/LIG/PMAY housing scheme the sizes of bathroom and water-closets shall be as follows:-
 - a) The size of independent water-closet shall be at least 0.90sq.m. with minimum width of 0.9m.
 - b) The size of independent bathroom shall be at least 1.20sq.m. with a minimum width of 1.00m
 - c) The size of combined bathroom & water-closet shall be atleast 1.80sq.m. with minimum width of 1.0m.

18.4.2 Height:- The Height of a bathroom or water closet measured from the surface of the floor to the lowest point in the ceiling (bottom of slab) shall be not less than 2.1 m.

18.4.3 Other Requirements - Every bathroom or water closet shall -

- i. be so situated that at least one of its walls shall open to external air unless mechanically ventilated;
- ii. not be directly over or under any room other than another water-closet, washing place, bath or terrace, unless it has a water-tight floor;
- iii. have platform or seat made of water-tight non-absorbent material;
- iv. be enclosed by walls or partitions and the surface of every such wall or partition shall be finished with a smooth impervious material to a height of not less than 1 m. above the floor of such a room;
- v. every water closet and/or a set of urinals shall have a flushing cistern of adequate capacity attached to it. In EWS/LIG/PMAY housing, however, no such flushing cistern need be provided;
- vi. be provided with an impervious floor covering sloping towards the drain with a suitable grade and not towards veranda or any other room;
- vii. in High Density housing, pour flush water seal latrines (NEERI type) may be permitted when the sewerage system is not available and the water table in the area is not high;
- viii. all the sewerage outlets shall be connected to the sewerage system. Where no such systems exist a septic tank shall be provided within the plot conforming to the appropriate standardized issued by NBC / CPHEEO.
- ix. have a window or ventilator, opening to a shaft or open space, of area not less than 0.3 sq.m. with side not less than 0.3m, unless mechanically ventilated.

18.4.4 Restriction on use of room containing water closet.

No room containing water closets shall be used for any purpose except as a lavatory and no such room shall open directly into any kitchen or cooking space by a door, window or other opening. Every room containing water closet shall have a door completely closing the entrance to it.

18.5 Ledge or Tand / Loft :-

Location and extent - Lofts may be provided over kitchen, habitable rooms, bathrooms, water closets, and corridor within a tenement in residential buildings, over shops and in industrial building, as mentioned in below Table No.11 subject to the following restrictions-

- i) The clear head room under the loft shall not be less than 2.2 m.
- ii) Loft in commercial areas and industrial building shall be located 2 m. away from the entrance.
- iii) Loft shall not interfere with the ventilation of the room under any circumstances.
- iv) The minimum headroom of Ledge or Tand / Loft shall be 2.2m.
- v) The maximum height between loft and ceiling shall be 1.5m.

Table No. 11		
Provision of Loft		
Sr. No.	Rooms over which Permitted	Maximum Coverage (Percentage to area or room below)
(1)	(2)	(3)
1	Kitchen/Habitable room	25
2	Bathroom, water closet, corridor	100
3	Shops with width up to 3m.	33
4	Shops with width exceeding 3m.	50
5	Industrial	33

18.6 Mezzanine floor

18.6.1 Size of mezzanine floor : The minimum size of a mezzanine floor, if it is used as a habitable room shall not be less than 9.50 sq.m. The aggregate area of the mezzanine floor shall not exceed 50 % of the built up area of that floor.

Note :- Mezzanine floor area shall be counted towards FSI

18.6.2 Height -The minimum height of a mezzanine floor shall be 2.2 mt. The headroom under mezzanine room shall not be less than 2.20 mt.

18.6.3 Other Requirements of mezzanine floor :

A mezzanine floor may be permitted over a room or a compartment provided:

- it conforms to the standards of living rooms as regards lighting and ventilation in case the size of mezzanine floor is 9.50 sq.m. or more.
- it is so constructed as not to interfere, under any circumstances, with the ventilation of the space over & under it.
- such mezzanine floor or any part thereof will not be used as a kitchen. iv) it is at least 1.8 mt. away from front wall of such rooms.
- access to the mezzanine floor is from within the respective room only.
- in no case shall a mezzanine floor be closed so as to make it liable to be converted into unventilated compartments.

18.7 Store Room :-

18.7.1 Size :- The floor area of a store room in a residential building where light ventilation and height are provided at standards lower than as required for living room shall not be more than 3 sq. m. One or more store rooms may be allowed considering size of flat. Prayer/Pooja room may be allowed in same manner.

18.7.2 Height- The height of a store room shall not be less than 2.20m.

18.8 Garage

18.8.1 Size of private Garage :- The size of a garage in individual residential building shall be not less than 2.5 m. X 5 m. and not more than 3 mt. X 6 mt. The garage, if located in the side open space, shall not be constructed within 3.0m. from the main building, but at least 7.5mt away from any access road.

18.8.2 Size of Public Garage. The size of a public garage shall be calculated based on the number of vehicles to be parked.

18.8.3 Height of private Garage :-The minimum and maximum height of garage shall be 2.4 mt. and 2.75 mt. respectively.

18.8.4 Plinth of private Garage :-The plinth of garage located at ground level shall not be less than 15 cm. above the surrounding ground level.

18.8.5 Set back of Private Garage :-

The garage shall setback behind the building line for the street / road on to which the plot abut, and shall not be located affecting the access ways to the building. If the garage is not set-back as aforesaid, the Planning Authority may require the owner or occupier of the garage to discontinue use, of premises or to take such other measures as the Planning Authority may consider necessary in order to prevent danger or obstruction to traffic along the street.

18.8.6 Location of Garage in case of Corner Site:

When the site fronts on two streets, the location of a garage (in a corner plot) (if provided within the marginal distances) shall be on diagonally opposite the point of intersections.

18.9 Roofs

The roof of a building shall be so constructed or framed as to permit effective drainage of the rain water there from by means of sufficient rain water pipes of adequate size, wherever required, so arranged, jointed and fixed as to ensure that the rain water is carried away from the building without causing dampness in any part of the walls or foundations of the building or those of an adjacent building.

The Metropolitan Commissioner may require rain water pipes to be connected to a storm water drain through a covered channel formed beneath the public footpath or in any other approved manner, if not used for rain water harvesting

Rainwater pipes shall be affixed to the outside of the walls of the building or in recesses or cut formed in such walls.

Top Terrace of a building shall not be sub-divided and it shall have only common access. However, intermediate terraces may be allowed to be attached with flat.

18.10 Basement

One or more basements may be permissible for following uses and shall be constructed after leaving the prescribed set-back / required front open space / required front margin, and prescribed building lines:

- a) storage of household or other goods or ordinarily non-combustible material;
- b) strong rooms, bank lockers, safe deposit vaults, radio/laser therapy unit, mortuary and medical allied uses, etc.;
- c) air-conditioning equipments and other machines used for services and utilities of the building;
- d) parking spaces;
- e) D.G. set room, meter room and Electric substation (which will conform to required safety requirements);
- f) Effluent Treatment Plant, suction tank, pump room;
- g) users strictly ancillary to the Principal user.

Provided that the users mentioned at (a) & (b) above shall be permitted only by counting in F.S.I. subject to the following conditions:

- i) All requirements regarding access, safety (including fire safety), ventilations, etc. shall be complied with.
- ii) All the planning standards (particularly as regarding parking) should be strictly adhered to. The basement shall not be used for residential purpose. iii) Users other than (a) and (b) shall not be counted in FSI.

Provided that,

- i) If the basement is proposed flushing to average surrounding ground level, then such basement can be extended in side and rear margins upto 3 mt. from the plot boundary. If the basement is proposed to be constructed below podium then marginal distances shall be as that of podium.
- ii) Multilevel basements may be permitted if the basement is used for parking. The ramps of minimum 3.0 m. width for entry and exit of vehicles separately shall be provided. In case of bonafide hardship, the Metropolitan Commissioner may allow only one ramp with not less than 6.0 m. in width.

The basement shall have the following requirements -

- (i) Every basement shall be in every part at least 2.4 mt. in height from the floor to the underside of the roof slab or ceiling soffit of beam.
- (ii) Adequate ventilation shall be provided for the basement with a ventilation area not less than 2.5% of the area of the basement. The standard of ventilation shall be the same as required by the particular occupancy according to these regulations. Any deficiency may be met by providing additional adequate mechanical ventilation in the form of blowers, exhaust fans, air conditioning systems etc.
- (iii) The minimum height of the ceiling of any basement shall ordinarily be 0.9 mt. and maximum shall be 1.2 mt. above the average surrounding ground level. However it does not apply to the mechanically ventilated basements. In such cases, basement may also be allowed flushing to the average ground level.
- (iv) Adequate arrangement shall be made such that surface drainage does not enter the basement.
- (v) The walls and floor of the basement shall be water-tight and be so designed that the effect of the surrounding soil and moisture, if any, is taken into account in design and adequate damp proofing treatment is given; and
- (vi) The access to the basement shall be separate from the main and alternate staircase providing access and exit from higher floors. Where the staircase is continuous the same shall be of enclosed type serving as a fire separation from the basement floor and higher floors. Open ramps shall be permitted if they are constructed within the building line subject to the provision of (iv) above.

18.11 Ramp**A) Non Vehicular Ramp-**

All the requirements of stairways in Regulation No 18.27 shall apply mutatis mutandis to non-vehicular ramp. In addition, the following requirement shall be complied with:

- a) Ramps with a slope of not steeper than 1 in 10 may be substituted for and shall comply with all the applicable requirements of required stairways as to enclosure, capacity and limited dimensions. In certain cases steeper slopes may be permitted but in no case greater than 1 in 8. Ramps shall be surfaced with approved non-slip slipping material. Provided that in the case of public offices, hospitals, assembly halls, etc. the slope of the ramp shall not be more than 1: 12.
- b) The minimum width of the ramps in hospitals shall be 2.25 m.
- c) Handrails shall be provided on both sides of the ramp.
- d) Ramps shall lead directly to outside open space at ground level or courtyards or safe place.
- e) For building above 24 m. in height access to ramps from any floor of the building shall be through smoke stop door.
- f) When there is a difference in level between connected areas for horizontal exits, ramps not more than 1 in 10 slope shall be provided; steps shall not be used.
- g) For High Rise building, if marginal open space is greater than minimum 6 m. then ramps may be permitted.

B) Ramp to basements and upper Storeys for vehicles-

For parking spaces in a basement and upper floors, at least two ramps of minimum 3.00mt. width or one ramp of 6.00 meter width and slope not more than 1:10 shall be provided preferably at the opposite ends.

C) In case of special building mentioned in Regulation No 2.77.13, ramp may be permitted in the side and rear marginal distances after leaving 6.0 mt distance from the plot boundary for movement of fire-fighting vehicles. Provided that when a building abutting 3 or more roads, then ramps may be allowed in front marginal distances facing the smaller road or less important road from traffic point of view.

18.12 Podium

Podium for parking of the vehicle may be permitted with following requirements / conditions

- i) Height of podium shall be at least 2.4 m. in height from the floor to the soffit of beam;
- ii) Podium shall not be provided in front setback space. Podium shall be allowed at a distance of **6.00 m.** from the plot boundary;
- iii) Podium shall only be used for parking and it shall be designed to take load of fire engine;
- iv) Podium shall be permissible for plots measuring 2000 sq.m. and above;
- v) Podium shall be permissible for joining two or more separate buildings in a plot buildings or wings of buildings subject to availability of manoeuvring space for Fire Engine. In such case the distance between two buildings/wings of the building shall be provided as otherwise required under these regulations;
- vi) The consent from the Chief Fire Officer, PMRDA shall be necessary before permitting the aforesaid podium;
- vii) For the plots having area 2000Sq.m. or more, recreational open space may be permitted on Podium subject to condition that out of required open/recreational space , at least 50% shall be provided on ground.

18.13 Balcony

Balcony or balconies of a minimum width 1.00m. and maximum of 2.00m. may be permitted at any floor except ground floor, not more than 15% of the built up area of the same floor and such balcony projection shall be subject to the following conditions:

- (i) No balcony shall reduce the marginal open space to less than 3 m. upto 24 m. building height. For height 24 m. and more no balcony shall reduce the marginal open space to less than 6mt;
- (ii) No balcony shall be allowed on ground floor which shall reduce minimum required front setback or marginal distance;
- (iii) The width of the balcony shall be measured perpendicular to the building up to the outermost edge of balcony;
- (iv) The balcony shall not be enclosed and declaration regarding this shall be submitted by the owner/developer/Architect at the time of approval to the building permission and the same shall be mention in the agreement or sale deed;
- (v) Nothing shall be allowed beyond the outer edge of balcony.

18.14 Stilt-

Stilt may be permitted on any floor subject to height of floor upto the soffit of the beam shall not be less than 2.4 m. In case of stilt on ground floor, plinth shall not be more than 15 cm from surrounding ground level.

18.15 Lighting and Ventilation of Rooms

i) Adequacy and manner of provision-

The minimum aggregate area of opening of habitable rooms and kitchens excluding doors shall be not less than 1/10th of floor area.

No portion of a room shall be assumed to be lighted if it is more than 7.5 m. from the opening assumed for lighting / ventilation of the portion, provided additional depth of any room beyond 7.5 m. may be permitted subject to provision of proportionate increase in the opening.

Where the lighting and ventilation requirements are not met through day lighting and natural ventilation, the same shall be ensured through artificial lighting and mechanical ventilation as per latest version of Part VIII - Building Services Section, Lighting and Ventilation of National

Building Code of India published by the Bureau of Indian Standards. In the case of special types of buildings requiring artificial lighting and air-conditioning for special types of manufacturing or other process the requirements about natural day lighting and ventilation may be relaxed.

ii) Ventilation Shaft:-

For naturally ventilating the space for water closets and bath room of staircase, if not opening on the exterior side of a building, open on the ventilation shaft, the size of which shall not be less than the values given below in **Table No. 12**

Table No. 12		
Height of building in m.	Size of ventilation in sq. m	Minimum width of shaft in m.
Up to 10	1.2	0.90
Up to 12	2.4	1.20
Up to 18	4.0	1.50
Up to 24	5.4	1.80
Up to 30	8.0	2.40
Above 30	9.0	3.0

iii) Artificial Lightning and Mechanical ventilation - where lighting and ventilation requirements are not met through day-lighting and natural ventilation, they shall be ensured through artificial lighting and mechanical ventilation in accordance with the provisions of Part 8, Building Services- Section 1, Lighting and Ventilation, **National Building Code of India, 2005.**

iv) In residential lodging hotels and other establishments where attached toilets are provided with mechanical ventilation system the size of ventilation shaft prescribed in this regulation stand relaxed.

18.16 Overhead Tanks:

Every overhead water storage tank shall be maintained in a perfectly mosquito-proof condition by providing a properly fitting hinged cover and every tank more than 1.5 m. in height shall be provided with a permanently fixed iron ladder.

18.17 Parapet

Parapet walls and handrails provided on the edges of roof terraces, balcony etc. shall not be less than 1.05 mt. and not more than 1.20 mt. in height from the finished floor level.

18.18 Cabin:

Where cabins are provided, a clear passage not less than 0.9 m. wide will be maintained. The size of a cabin shall not be less than 3 sq.m. and the distance from the farthest space of cabin to the nearest exit shall not be more than 18.5 mt if the cabin does not derive direct light and ventilation from any open spaces / mechanical means, its maximum height shall be 2.2 m.

18.19 Society Office:

In the case of multi-storied multi-family dwelling apartments constructed for co-operative housing societies or apartment owner's co-operative societies, a Society Office upto 12 sq.m. shall be provided on the ground floor or uppermost floor. If the number of flats are more than 20 the maximum size of the Society Office shall be of dimension of 20 sq.m.

18.20 Wells

Wells intended for supply of water for human consumption or domestic purposes may be permitted at suitable place.

18.20.1 Requirements: The well shall:

- (a) have minimum internal diameter of not less than 1 m.;
- (b) be constructed to a height not less than 1 m. above the surrounding ground level to form a parapet or curb and to prevent surface water from following into a well, and shall be surrounded with a paving constructed of impervious material which shall extend for a distance of not less than 1.8 m. in every direction from the parapet or the curb forming the well head and the upper surface for such paving shall be sloped away from a well;
- (c) be a sound and permanent construction (PUCCA) throughout. Temporary exposed (KUTCHA) wells shall only be permitted in fields or gardens for purposes of irrigation; and;
- (d) the interior surface of the lining or walls of the well shall be rendered impervious for depth of not less than 1.8 m. measured from the level of the ground immediately adjoining the well-head.

18.21 Septic Tanks

Every building, group of buildings together shall be either connected to the public Drainage system or provided with sub-soil dispersion system in the form of septic tank which shall be governed by the following or any other alternative design and specifications

1. Design of septic tank:-

Where a septic tank is used for sewage disposal, the location, design and construction of the septic tank shall conform to requirements of the following Regulation

2. Location of Septic Tanks and Subsurface Absorption System:- A subsoil dispersion system shall not be closer than 18.00 m. of any source of drinking water such as well, to mitigate the possibility of bacterial pollution of water supply. It shall also be as far removed from the nearest habitable building as economically feasible but not closer than 6 m. to avoid damage to the structures.

3. Requirements:

- (a) **Dimensions of Septic Tanks:** Septic tanks shall have minimum width of 75 cm., minimum depth of 1 m. below the water level and a minimum liquid capacity of 1 cu.m. Length of tanks shall be 2 to 4 times the width;
- (b) Septic tanks may be constructed of brick work, stone masonry, concrete or other suitable materials;
- (c) Under no circumstances should effluent from a septic tank be allowed into an open channel drain or body of water without adequate treatment;
- (d) Minimum nominal diameter of pipe shall be 100 mm. further, at junctions of pipes in manholes; direction of flow from a branch connection should not make an angle exceeding 45 degree with the direction of flow in the main pipe;
- (e) The gradients of land drains under drainage as well as the bottom of dispersion trenches and soak way should be between 1:300 and 1:400;
- (f) Every septic tank shall be provided with ventilating pipe of at least 50 mm diameter. The top of the pipe shall be provided with a suitable cage of mosquito proof wire mesh. The ventilating pipe shall extend to a height, which would cause no smell nuisance to any building in the area. Generally, the ventilating pipe may extend to a height of about 2 m. when the septic tank is at least 15 m. away from the nearest building and to a height of 2 m. above the top of the building when it is located closer than 15 m;
- (g) When the disposal of septic tank effluent is to seepage pit, the seepage pit may be of any suitable shape with the least cross sectional dimension of 90 cm. and not less than 100 cm. in depth below the invert level of the inlet pipe. The pit may be lined with stone, brick or concrete blocks with dry open joints which should be backed with at least 7.5 cm. of clean coarse aggregate. The lining above the inlet level should be finished with mortar. In the case

of pits of large dimensions, the top portion may be narrowed to reduce the size of the RCC cover slabs. Where no lining is used, especially near trees, the entire pit should be filled with loose stones. A masonry ring may be constructed at the top of pit to prevent damage by flooding of the pit by surface run off. The inlet pipe may be taken down to a depth of 90 cm. from the top as an anti-mosquito measure;

- (h) When the disposal of septic tank effluent is to a dispersion trench, the dispersion trench shall be 50 to 100 cm. deep and 30 to 100 cm. wide excavated to a slight gradient and shall be provided with 15 to 25 cm. of washed gravel or crushed stones. Open jointed pipes placed inside the trench shall be made of unglazed earthenware clay or concrete and shall have minimum internal diameter of 75 to 100 mm. No dispersion trench should not be longer than 30 m. and trenches should not be placed closer than 1.8 mt.

18.22 Boundary Wall

The requirements of the boundary wall are given below:

- (a) Except with the special permission of the Metropolitan Commissioner the maximum height of the compound wall shall be 1.5 m. above the centre line of the front street. Compound wall upto 2.4 m. height may be permitted if the top 0.9 m. is of open type construction (railings). However Metropolitan Commissioner may allow the plinth and the boundary wall up to 0.90 m. above ground level and balance height may be of open railing or as decided by him;
- (b) In case of corner plot the height of boundary wall shall be restricted to 0.75 m. for a length equal to fanning of the road on the front and side of the intersections and balance height of 0.75 m. if required in accordance with (a) may be made of open construction (railings);
- (c) However, the provisions of (a) and (b) are not applicable to boundary wall of jails. In industrial buildings, electric sub stations, transformer stations institutional buildings like sanatoria, hospitals, industrial buildings like workshops, factories and educational buildings like schools, colleges, including the hostels, and other uses of public utility undertakings. Height upto 2.4 m. to boundary walls of these types of building may be permitted by the Metropolitan Commissioner.

18.23 Letter Box Room

A letter box of appropriate dimensions shall be provided on the ground floor of residential and commercial buildings with five and more storeys.

18.24 Meter Rooms

For all buildings above 15 m in height and in special occupancies, like educational, assembly, institutional, industrial, storage, hazardous and mixed occupancies with any of the aforesaid occupancies having area more than 500sq.m. on each floor, provision shall be made for an independent and ventilated meter (service) room, as per requirements of electric (service) supply undertakings on the ground floor with direct access from outside for the purpose of termination of electric supply from the licensee's service and alternative supply cables. The door/doors provided for the service room shall have fire resistance of not less than two hours.

18.25 Chimneys

Chimneys, where provided, shall conform to the requirements of IS: 1646-1960 Indian Standard Code of Practice for Fire Safety of Building. Provided that the Chimneys shall be built at least 0.9 m. above flat roof. In the case of sloping roofs, the chimney top shall not be less than, 0.6 m. above the ridge of the roof in which the chimney penetrates.

18.26 Supported Double Height Terrace (within the building line)

Supported double height terraces (open terraces with railing having minimum height equal to two floors) within the building line, not exceeding 20% of the built up area of the same floor may be permitted without counting in FSI subject to payment of premium as decided by Metropolitan Commissioner.

18.27 EXIT REQUIREMENTS

18.27.1 General-The following general requirements shall apply to exits.

- (a) An exit may be a doorway; corridor, passageway(s) to an internal staircase, or external staircase, or to a VERANDA or terrace(s), which have access to the street, or to the roof of a building or a refuge area. An exit may also include a horizontal exit leading to an adjoining building at the same level;
- (b) Lifts and escalators shall not be considered as exits;
- (c) Every exit, exit access or exit discharge shall be continuously maintained free of all obstructions or impediments to full use in the case of fire or other emergency;
- (d) Every building meant for human occupancy shall be provided with exits sufficient to permit safe escape of occupants in case of fire or other emergency;
- (e) In every building, exits shall comply with the minimum requirements of this part, except those not accessible for general public use;
- (f) No building shall be altered to reduce the number, width or protection of exits to less than that required;
- (g) Exits shall be clearly visible and the routes to reach the exits shall be clearly marked and sign posted to guide the occupants to the floor concerned;
- (h) The floors of area covered for the means of exit shall be properly illuminated;
- (i) All exits shall provide continuous means of egress to the exterior of a building or to an exterior open space leading to a street and;
- (j) Exits shall be so arranged that they shall be reached without passing through another occupied unit.

18.27.2 Types of exits -

Exits shall be either of horizontal or vertical type. An exit may be doorway, corridor, and passageways to an internal staircase or external staircase, ramps or to a veranda and/or terraces which have access to the street or to roof of a building. An exit may also include a horizontal exit leading to an adjoining building at the same level. Lifts and escalators shall not be considered as exits.

18.27.3 Number and Size of Exits

The requisite number and size of various exits shall be provided, based on number of occupants in each room and floor based on the occupant load, capacity of exits; travel distance and height of building as per provisions of Regulation no. 18.27.5 to 18.27.8

18.27.4 Arrangement of Exits

Exits shall be so located so that the travel distance on the floor shall not exceed 22.5 m. for residential, education, institutional and hazardous occupancies and 30 m. for assembly business, mercantile, industrial, storage & hazardous occupancies. Wherever more than one exit is required for a floor of a building, they shall be placed as remote from each other as possible. All the exits shall be accessible from the entire floor area at all floor levels.

18.27.5 Occupant Load -

For determining the exits required the number of persons within any floor area or the occupant load shall be based on the actual number of occupants but in no case, less than that specified in **Table No. 13** below:

Table No. 13 Occupant Load		
Sr. No.	Group of Occupancy	Occupant Load floor Area in sq.mt. per person
(1)	(2)	(3)
1	Residential	12.5
2	Educational	4.00
3	Institutional	15 (See Note-1)
4	Assembly	
	(a) with fixed or loose seats and dance floors	0.6 (See Note-2)
	(b) without seating facilities including dining rooms	1.5 (See Note-2)
5	Mercantile	
	(a) Street floor and sales basement	3
	(b) Upper sale floors	6
6	Business and industrial	10
7	Storage	30
8	Hazardous	10

Note 1 - Occupant load in dormitory portions of homes for the aged, orphanages, asylums, etc. where sleeping accommodation is provided shall be calculated at not less than 7.5 sq.m. floor area per person.

Note 2 - The gross area shall include, in addition to the main assembly room or space, any occupied connecting room or space in the same storey or in the storeys above or below where entrance is common to such rooms and spaces and they are available for use by the occupants of the assembly space. No deductions shall be made in the gross area for corridors, closets or other sub-divisions. The area shall include all space serving the particular assembly occupancy.

18.27.6 Capacity of Exits -

- 1) Occupants per unit exit width shall be in accordance with **Table No.14**

Table No. 14 Occupants per Unit Exit Width				
Sr.No.	Group or Occupancy	Number of Occupants		
		Stairways	Ramps	Doors
1	Residential	25	50	75
2	Educational	25	50	75
3	Institutional	25	50	75
4	Assembly	40	50	60
5	Business	50	60	75
6	Mercantile	50	60	75
7	Industrial	50	60	75
8	Storage	50	60	75
9	Hazardous	25	30	40

- 2) For the dormitory portions of homes for the aged, orphanages, mental hospitals, etc. these multipliers will be doubled.
- 3) The gross floor area shall include, in addition to the main assembly rooms or space, any occupied connecting room or space in the same storey or in the storey above or below where entrance is common to such rooms and space and they are available for use by the occupants of the assembly place.
- 4) No deductions shall be made in the gross area of the corridors, closets or other sub-divisions; the area shall include all space serving the particular assembly occupancy shall be reckoned.

18.27.7 Provision for Staircase-

All buildings having height more than ground floor shall have provision of staircase. The special buildings shall have two staircases out of which one shall be fire escape staircase. They shall be of enclosed type. At least one of them shall be on external walls of buildings and shall open directly to the exterior, interior open space or to an open place of safety. Further, the provision or otherwise of alternative staircases shall be subject to the requirements of travel distance being complied with.

Provided that for purely residential building/residential building along with ground floor mix use having height upto 24 meters and built up area on any floor does not exceed 500 sq.mts. an additional staircase shall not be insisted. Provided also that in such cases width of stair case shall be minimum 1.50 mt.

18.27.8 Width of Stairways-

Notwithstanding anything contained in regulations, the following minimum width provision shall be made for staircases flight/corridor.

Table No. 15		
Type of Building	Built-up area on floor served by single staircase	
	upto 5 sq.m.	More than 500 sq.m.
Multi-Storeyed Residential Buildings	1.20 m.	1.50 m
Residential Hotel Buildings	1.50 m.	1.80 m
Assembly buildings like auditoria, theatres, Cinemas etc., Mangalkaryalaya, marriage halls.	1.80 m.	2.00 m.
Institutional Buildings like hospitals & Educational	2.00 m.	2.30 m.
All other public buildings including commercial buildings.	1.50 m.	1.80 m.

Note:-

- for individual house and row housing with 2 storey's, the minimum shall be 0.75 m.
- The width of the mid-landing/quarter landing should not be more than 1.5 times and the floor landing should not be more than two times of the width of the stair flight.

18.28 Other Requirements of Individual Exits- The detailed requirements of individual exits are given in Regulation no. **18.28.1 to 18.28.8.**

18.28.1 Doorways:

- Every exit doorway shall open into an enclosed stairway, a horizontal exit or a corridor or passage way providing continuous and protected means of egress;
- No exit doorway shall be less than 90 cm in width in case of residential and 100 cm. in width in case of other buildings. Doorways shall be not less than 200 cm. in height. Doorways for bathrooms, water closet, stores etc. shall be not less than 75 cm. wide;
- Exit doorways shall open outwards, that is away from the room but shall not obstruct the travel along any exit. No door, when open, shall reduce the required width of stairway or landing to less than 90 cm. Overhead or sliding doors shall not be installed;
- Exit door shall not open immediately upon a flight of stairs, a landing equal to at least the width of the door shall be provided in the stairway at each doorway. Level of landing shall be the same as that of the floor which it serves;
- Exit doorway shall be openable from the side which they serve without the use of a key;
- Mirrors shall not be placed in exit ways or exit doors to avoid confusion regarding the direction of exit.

18.28.2 Revolving Doors :

Revolving doors shall not be used as required exits except in residential, business and mercantile occupancies, but shall not constitute more than half the total required door width.

18.28.3 Stairways:

- i) Interior stair shall be constructed of non-combustible materials throughout;
- ii) Interior staircase shall be constructed as a self-contained unit with at least one side adjacent to an external wall and shall be completely enclosed;
- iii) A staircase shall not be arranged around a lift shaft;
- iv) Hollow combustible construction shall not be permitted;
- v) The minimum width of treads without nosing shall be 25 cm. for an internal staircase for residential buildings. In the case of other buildings, the minimum treads shall be 30 cm. The treads shall be constructed and maintained in a manner to prevent slipping;
- vi) The maximum height of riser shall be 19 cm. in the case of residential buildings and 15 cm. in the case of other buildings. They shall be limited to 15 per flight;
- vii) Handrails shall be provided with a minimum height of 100 cm. from the centre of tread, to the top of the handrails. Balusters / railing shall be provided such that the width of staircase does not reduce;
- viii) Floor indicator - The number of each floor shall be conspicuously painted in figures at least 15 cm. large on the wall facing the flights of a stairway or at such suitable place as is distinctly visible from the flights;
- ix) The minimum headroom in a passage under the landing of a staircase shall be 2.2 m;
- x) For building more than 15m. in height or more access to main staircase shall be gained through at least half an hour fire resisting automatic closing doors placed in the enclosing wall of the staircase. It shall be a swing type door opening in the direction of the escape;
- xi) No living space, store or other fire risk spaces shall open directly into the external staircase;
- xii) External exit door of staircase enclosure at ground level shall open directly to the open spaces or should be reached without passing through any door other than a door provided to form a large lobby;
- xiii) In the case of assembly, institutional, residential hotels, industrial and hazardous occupancies, the exit sign with arrow indicating the way to the escape route shall be provided at a height of 0.5m. from the floor level on the wall and shall be illuminated by electric light connected to corridor circuits. All exit way marking signs should be flush with the wall and so designed that no mechanical damage shall occur to them due to moving of furniture or other heavy equipments. Further all landings of floor shall have floor indication boards indicating the floor number. The floor indication board shall be placed on the wall immediately facing the flight of stairs and nearest to the landing. It shall be of size not less than 0.5m. x 0.5m;
- xiv) In case of single staircase it shall terminate at the ground floor level and the access to the basement shall be by a separate staircase. Wherever the building is served by more than one staircase, one of the staircases may lead to basement levels, provided the same is separated at ground level by either a ventilated lobby or cut-off screen wall without opening, having a fire resistance of not less than 2 hours with discharge point at two different ends or through enclosures. It shall also be cut off from the basement areas at various basement levels by a protected and ventilated lobby / lobbies.

18.28.4 Fire escape or external stairs –

Fire escape staircase, when provided, shall comply the following:

- i) External stairs shall always be kept in sound operable conditions;
- ii) All external stairs shall be directly connected to the ground;
- iii) Entrance to the external stairs shall be separate and remote from the internal staircase;
- iv) Care shall be taken to ensure that no wall opening or window opens on to or close to an external stair;
- v) The route to the external stairs shall be free of obstructions at all times;
- vi) The external stairs shall be constructed of non-combustible materials, and any doorway leading it shall have the required fire resistance;
- vii) No external staircase, used as a fire escape, shall be inclined at an angle greater than 45 degree from the horizontal;

- viii) External stairs shall have straight flight not less than 1250 mm wide with 250 mm treads and risers not more than 190 mm. The number of risers shall be limited to 15 per flight;
- ix) Handrails shall be of a height not less than 1000 mm and not exceeding 1200 mm. There shall be provisions of balusters with maximum gap of 150 mm.
- x) The use of spiral staircase shall be limited to low occupant load and to a building not exceeding 9 m in height. A spiral stair case shall be not less than 1500 mm in diameter and shall be designed to give adequate headroom;
- xi) Unprotected steel frame staircase will not be accepted as means of escape. However, steel staircase in an enclosed fire rated compartment of 2 h will be accepted as means of escape.

18.28.5 Corridors and passageways:

- i) The minimum width of a corridor shall not be less than 75cm. in the case of 2 storeys row housing residential buildings and 100cm. In the case of other buildings and actual width shall be calculated based on the provision of Regulations No 18.27.3 to 18.27.5 (both inclusive);
- ii) Where there is more than one staircase serving a building, there shall be at least one smoke-stop door in the space between the staircases;
- iii) Exit corridors & passageways shall be of width not less than the aggregate required width of exit doorways leading from them in the direction of travel of the exterior/stairways;
- iv) Where stairways discharge through corridors & passageways the height of the corridors & passageways shall not be less than 2.4 m;
- v) All means of exit including staircases, lifts, lobbies & corridors shall be adequately ventilated.

18.28.6 Refuge Area

For buildings more than 24 m in height, refuge area of 15 sq.m. or an area equivalent to 0.3 sq.m. per person to accommodate the occupants of two consecutive floors whichever is higher shall be provided as under:

The refuge area shall be provided on the periphery of the floor or preferably on a cantilever projection and open to air at least on one side protected with suitable railings.

- a) For floors above 24 m and upto 39 m—One refuge area on the floor immediately above 24m.
- b) For floors above 39 m—One refuge area on the floor immediately above 39 m and so on after every 15 m. Refuge area provided in excess of the requirements shall be counted towards FSI. However, area remained in excess because of planning constraints shall not more than 10% of required refuge area shall not be counted in FSI.

18.28.7 Lifts and Escalators:-

a) Lifts :-

Provision of lift shall be made for all buildings more than 15mt in height. In case the height of the building is more than 24.0 mt , at least two lifts shall be provided. However, in the case of a proposal to add one additional floor to an existing building having a lift, it will not be necessary to raise the existing lift to the additional floor.

- (a) All the floors shall be accessible for 24 hours by the lifts. The lifts provided in the buildings shall not be considered as a means of escape in case of emergency;
- (b) Grounding switch at ground floor level to enable the fire service to ground the lift cars in any emergency shall also be provided;
- (c) The lift machine room shall be separate and no other machinery shall be installed therein;
- (d) The planning and design of lifts including their number, type and capacity depending on the occupancy of the building, the population of each floor based on the occupant load and the building height shall be in accordance with **Section 5 - Installation of Lifts and Escalators** of Part 8- Building Services, of the **National Building Code of India, 2005**.

b) Escalators :

Escalators may be permitted in addition to required lifts. Such escalators may be permitted in atrium area in shopping malls / public buildings.

18.28.8 Fire Lift

Where applicable, fire lifts shall be provided with a minimum capacity for 8 passengers and fully automated with emergency switch on ground level. In general, buildings 15 m in height or above shall be provided with fire lifts. In case of fire, only fireman shall operate the fire lift. In normal course, it may be used by other persons. Each fire lift shall be equipped with suitable inter- communication equipment for communicating with the control room on the ground floor of the building. The number and location of fire lifts in a building shall be decided after taking into consideration various factors like building population, floor area, compartmentation, etc.

18.28.9 FIRE PROTECTION REQUIREMENTS

All buildings shall be planned, designed and constructed to ensure fire safety and this shall be done in accordance with Part IV of Fire Protection of National Building Code of India and Maharashtra Fire Prevention and Life Safety Measures Act, 2006, as prescribed in Part VI of these Regulations. The provisions of Part VI shall deem to be modified time to time as per the Fire Protection of National Building Code of India and Maharashtra Fire Prevention and Life Safety Measures Act, 2006. In case of special buildings, the building schemes shall also be cleared by the Chief Fire Officer of the PMRDA.

18.29 Additional requirements in case of Housing Schemes:

Following amenities shall be provided in a housing scheme and shall not be counted in FSI:

- i. Fitness Centre, Crèche, society office cum letter box room, laundry room, and measuring area of about 20 sq.m. in schemes having minimum 100 flats and thereafter additional 20 sq.m. area for every 300 flats.
- ii. Sanitary block for servants having maximum area of 3.00 sq.m. in schemes having minimum 100 flats and thereafter additional 3.00 sq.m. area for every 200 flats.
- iii. Drivers room of size 12 sq.m. with attached toilet in schemes having minimum 100 flats and thereafter additional 10 sq.m. area for every 300 flats.

PART – III
LAND USE CLASSIFICATION AND PERMISSIBLE USES.

19.1 RESIDENTIAL ZONE - R 1

Residential Zone R1 includes Residential plots abutting on roads below 9 m. in congested area and below 12 m. width in outside congested area.

19.1.1 The following uses and accessory uses to the principal use shall be permitted in buildings or premises in Zone R1, subject to other regulations:

- (i) Any residences.
- (ii) Hostels for students / working men/women, with or without boarding facilities.
- (iii) Old age home in independent building on road having width 9.00 meter and above,
- (iv) Customary Home occupation i.e. occupations customarily carried out by the members of the household without employing hired labour and shall include stitching, embroidery, button making etc. with or without motive power. If motive power is used, the total electricity load should not exceed 1 HP.
- (v) Medical and Dental Practitioner's Dispensaries including pathological laboratory, diagnostic clinics, polyclinics, counselling centre, clinics, to be permitted on any floor. Maternity homes, clinics, nursing home with indoor patients on ground or stilt floor or on first floor with separate means of access of staircase from within the building or outside, may be permitted but not within the prescribed marginal open spaces in any case and with the special permission of Commissioner. Maternity Homes and Hospitals are permitted for maximum 20 beds.
- (vi) Professional Offices in residential tenement for own purpose not exceeding carpet area of 50 sq. m. each.
- (vii) Community halls, welfare centre, gymnasias (each not exceeding 150 sq.m.)
- (viii) Primary and nursery schools including students' hostels in independent buildings, on widths of roads 9.00 m. or above and nursery schools on road having width 6.00 meter or above.
- (ix) Crèche, Day-care centre in an independent building or parts of building upto 50 sq.m.
- (x) Private coaching classes, mess in an independent building or parts of building upto 50 sq.m. with strictly subjected to separate parking facility in the same premises.
- (xi) Religious buildings.
- (xii) Public/ City Libraries and Museums in independent building or on any floor of the building with special permission of Metropolitan Commissioner if the user will not create nuisance to the occupant of the building.
- (xiii) Club Houses or gymkhanas, not conducted as a business, on independent plots which may have an extension counter or only branch of a bank, in such club-houses or gymkhana.
- (xiv) Public Parks or Private Parks, gardens, Yoga Centres and play field in independent plots not being used for business purpose, but not amusement parks.
- (xv) Bus shelters, Taxi-Rickshaw stands trolley bus shelters, Railway Station, Metro station, BRT stand, cycle stand.
- (xvi) Convenience shops not more than 20 sq. m., each only on ground floor, for the purposes of food grain shops (Ration shops). Pan shops Tobacconist, Shops for collection and distribution of cloths and other materials for cleaning and dyeing establishments, Darners, Tailors, Groceries, Confectionery and other general provisions. Hair dressing saloon and Beauty Parlour, bicycle hire and repair, Hat repair, shoe repair and shining shops, vegetable and fruit stalls/ shops, fish or/and meat shops, Milk shops, Floweriest, Bangles and Newspaper stalls, wood, coal and fuel merchants, Book and stationery etc. Medicine and Chemist shops, watch& mobile repairs and motorcycle repair shops. The Commissioner may from time to time add or alter or amend the above list.
- (xvii) Police Station, police chowky, Government and Metropolitan sub-offices, posts and Telegraph Offices, Branch offices of Banks, with safe Deposit Vaults, Electrical substations, Fire Aid posts along with home-guards and Civil Defence Centres, essential Public utility

and Pumping stations and water installations and ancillary structures thereof required to cater to the local area.

- (xviii) Electronic Industry of the Assembly type (not manufacturing type) with the following restrictions –
 - (a) Motive Power shall not exceed 1 H.P.
 - (b) Area occupied shall not exceed 100 sq.m.
- (xix) Information technology establishment (ITE) (pertaining to software only) on the plots/ premises fronting on roads having width 9.00 m. and above.
- (xx) Flour mill and wet / dry masala grinding / book binding subject to following conditions:
 - (a) It is located on ground floor.
 - (b) Adequate care has been taken in structural design.
 - (c) It does not cause any nuisance to the neighbour and residents of upper floor.
 - (d) Power requirement does not exceed 10 hp. Additional H.P. if required, may be granted with special written permission of Commissioner.
- (xxi) Places for disposal, for human bodies, like Burial grounds, cremation grounds on a road having width of 9 m. and above subject to the approval from PMRDA.
- (xxii) Agricultural, horticultural and allied uses (except agro-based industries).
- (xxiii) Raisin Production
- (xxiv) Roads, bridges, culverts and construction of any modes of transportation.
- (xxv) Any other use allowed in consultation with the Metropolitan Commissioner, PMRDA in accordance with the intend and spirit of these Regulations.

19.2 RESIDENTIAL ZONE R-2

Residential Zone R2 includes Residential plots abutting on road having existing or proposed width 9 m. and above in congested area and 12 m. and above in outside congested area

19.2.1 In this zone the following uses, along with their ancillary uses, mix uses may be permitted:

- i) All uses permissible in R-1 shall be permitted in R-2 zone, without restrictions on built-up area.
- ii) Shopping malls, Stores or shops for the conduct of retail business including departmental stores. Storage and sale of combustible materials shall not normally be permitted except with the special permission of the concerned authority.
- iii) Any activity of Government or semi- Government and of their authorities, including offices, training centres and like uses.
- iv) Personal service establishments: professional offices.
- v) Radio broadcasting stations and studio, telephone exchanges, mobile towers.
- vi) Frozen food lockers, fast food and vending stalls.
- vii) Tailor shops, embroidery shops and button – hole making shops, not employing more than 9 persons with individual motors not exceeding 1 H. P. and total H. P. not exceeding 3.
- viii) Cleaning and pressing establishments for clothes not employing solvents with flash point lower than 1380F machines with dry load capacity exceeding 30 kg and more than 9 persons and provided that total power requirement does not exceed 4 KW;
- ix) Shops for goldsmiths, locksmiths, watch and clock repairs, optical glass grinding and repairs, musical instrument repairs, picture framing, radio and household appliances repairs, upholstery and diamond cutting and polishing not employing more than 9 persons with individual motors not exceeding 1 H. P. and total H. P. not exceeding 3 H. P.
- x) Coffee grinding with electric motive power not exceeding 1 H.P.
- xi) Bakeries with no floor above not occupying for production and area in excess of 75 sq.m. and not employing more than 9 persons ,provided that the power requirements does not exceed 4KW.
- xii) Printing press as per table of service industries, posters, flex board printing shops.
- xiii) Electronic industry of assembly type (and not manufacturing type)
- xiv) Diamond cutting and polishing; not employing more than 6persons with motive power and exceeding 1/2 H.P.
- xv) Auto part stores and show rooms for motor vehicles and machinery.

- xvi) Sale of used or second hand goods or merchandise (not junk, cotton waste, rage or other materials of offensive nature).
- xvii) Club houses or other recreational activities, conducted as business.
- xviii) Storage of furniture and household goods.
- xix) Repairs to all household articles (excluding auto vehicle).
- xx) Veterinary dispensaries and hospitals.
- xxi) Animal pounds.
- xxii) Repair, cleaning shops and analytical, experimental or testing laboratories not employing more than 15 persons in the industrial activity but not including cleaning and dyeing establishment using a cleaning or dyeing fluid having a flash point lower than 60 degree C. and machines with dry load capacity of 30 kg. for any establishment carrying on activities that are noxious or offensive because of emission of odour, dust, smoke, gas, noise or vibration or other-wise dangerous to public health and safety, provided that the motive power requirement of such establishment does not exceed 10 H. P.
- xxiii) Accessory uses customarily incidental to any permitted principal use including storage space, upto 50% of the total floor area used for the principal use.
- xxiv) Paper box manufacturing including paper cutting, not employing more than 9 persons, with motive power not exceeding 5 H. P. and area not more than 50 sq. m.
- xxv) Mattress making and cotton cleaning, not employing more than 9 persons with motive power not exceeding 3 H.P. and area not more than 50 sq. m.
- xxvi) Establishment requiring power for sealing tin, packages, etc. not employing more than 9 persons, with motive power not exceeding 3 H.P.
- xxvii) Commercial halls, exhibition halls, community halls, welfare centre, gymnasias, etc.
- xxviii) Air-conditioned Cinema theatres & Multiplex.
- xxix) Art galleries, aquariums;
- xxx) Museums in independent structures or restricted to ground floors or on first floor in a stilted building;
- xxxi) Research, experimental and testing laboratories not involving any danger of fire or explosion nor of any noxious nature and located on a site not less than 4 Ha. in area and when the laboratory is kept at least 30 m. from any of the boundaries of the site and the necessary residential buildings 30 m from the laboratory.
- xxxii) Restaurants, eating houses, cafeteria, ice - cream and milk bars.
- xxxiii) Establishment for preparation and sale of eatables not occupying for production an area in excess of 75 sq. m. per establishment and not employing more than 9 persons. Sugarcane and fruit juice crushers not employing more than 6 persons with 1.5 H.P. with area not more than 25 sq.m. shall also come under that sub regulation
- xxxiv) Repairing garages not employing more than 9 persons and 2 H.P. motive power in the industrial activity with no floor above.
- xxxv) Battery charging and repairing, not employing more than 6 persons with an area not more than 25 sq.m. and not more than 2 chargers with power not exceeding 5 KW.
- xxxvi) Photographic studios and laboratories with not more than 50 sq. m. area, not employing more than 9 persons and not using power more than 3 H. P.
- xxxvii) Showroom for Distribution and sale of LPG;
- xxxviii) Coal and Firewood Shops.
- xxxix) Group medical centres, Polyclinics, on separate floors, preferably ground floor, pathology laboratories.
- xl) Residential Hotels, Boarding and Lodging shall be permitted in independent building or parts of building, but on separate floors.
- xli) Book Depot, Medicine and chemist shops.
- xl ii) Business/ corporate office on any floor.
- xl iii) IT buildings & office buildings
- xl iv) Office and showroom of LPG cylinders, not exceeding 100 kg.in aggregate, without storage of cylinders.
- xl v) Photographic studios and laboratories not using power more than 5 H.P. and employing not more than 9 persons;
- xl vi) Highway amenities as permitted in Agriculture zone with FSI at par with residential zone.

- xlvi) Trade or other similar schools not involving any danger of fire or explosion nor of offensive noise, vibration, smoke, dust, odour, glare, heat or other objectionable influences
- xlvi) Repairing garages
- xli) Yoga centres
- xlx) All other commercial users as may be deemed fit by the Metropolitan Commissioner.

Note: The Metropolitan Commissioner may from time to time add to amend the above list in consultation with Director of Town Planning, Maharashtra State, Pune.

19.2.2 The following uses shall be permitted only if it is conducted in independent premises / building:

The following uses shall be permitted in independent premises / building:

- i) Drive - in - theatres, theatres, cinema houses multiplex, club houses, assembly or concert halls, Mangal karyalaya, dance and music studios and such other places of entertainment.
- ii) Petrol filling and CNG service stations with ancillary facilities including convenience shopping.
- iii) Colleges, Secondary Schools, Trade or other similar schools.
- iv) Storage and sale of kerosene not exceeding 1000 liters in groceries and approved ration shops on retail basis.
- v) Bulk storage and sale of kerosene not exceeding 13000 liters in separate godowns confirming to the existing regulations of Chief Controller of Explosives, Government of India, provided further that the applicant shall make adequate fire fighting arrangements at his cost in his plot to the entire satisfaction of the Metropolitan Commissioner.
- vi) Storage and sale of LPG in cylinders not exceeding 6300 kg. in a separate godown confirming to the existing regulations of Chief Controller of Explosives, Government of India provided further that the applicant shall make adequate fire fighting arrangements at his cost in his plot to the entire satisfaction of the Metropolitan Commissioner.
- vii) Parking of automobiles and other light vehicles on open plots even as a business.
- viii) General Agriculture and Horticulture, domestic poultry upto the use of 20 birds per plot and with a space requirement of 0.25 sq. m. per bird.
- ix) Correctional and mental institutions, institutions for the children, the aged or widows, sanatoria and hospitals in independent building facing on roads of width not less than 15 m. (except veterinary hospitals) provided that those principally for contagious diseases, the insane or for correctional purposes shall be located not less than 45 m. from any residential premises.
- x) Residential hotels of 2 to 5 star categories.
- xi) Vegetable, fruit, flour, fish or meat market place
- xii) Service Industries- The Service Industries may be permitted in independent building (independent designated plot) in R2 and Commercial zones along with the limitation of area, maximum number of persons to be employed, maximum permissible power requirement and the special conditions if any as given in Appendix – L, for service industries. The Service Industries shall also be permissible in the buffer zone falling within 5 km distance from the PMC and PCMC Boundaries.

Note: - Drive-in theatres, theatres, cinemas, club-houses, assembly or concert halls and such other places of entertainment shall be allowed on roads having width exceeding 15m and more. These users may be permitted in combination with permissible non-residential uses except that of petrol pump, with the special permission of the Metropolitan Commissioner. However, in the case of a cinema/theatre the front open space shall be minimum 12m. and the side and rear open spaces shall not be less than 6m. Provided that, in the case of development and/or re-development of a cinema/theatre the user as mentioned above may be permitted in combination with the permissible users in a residential R-2 zone.

However, residential user in combination with that of a cinema/theatre may not be allowed in the same building.

Provided further that, on plot/lands where there is an existing cinema Theatres, redevelopment of the plots shall be allowed subject to the condition that at least 1/3rd of the existing seats shall be retained, which shall not be below 150 seats and may be developed in combination with user permissible in R2 zone. Provided also that, if redevelopment of existing cinema theatre is not possible considering the other requirement in these regulations, in such case user permissible in adjoining land shall be permissible with the special permission of Metropolitan Commissioner.

19.3 SLUM IMPROVEMENT ZONE - Deleted

19.4 COMMERCIAL ZONE

19.4.1 In commercial zones, buildings or premises shall be used only for the uses and purposes given in Regulation No. 19.4.2 subject to the following conditions:

- (a) all goods offered for sale shall be displayed within the building excluding passages;
- (b) when the commercial zone boundary falls short of a street, the frontage along such street shall not be permitted to be developed for uses which would not be permissible along such streets and;
- (c) when user other than those permissible in a residential zone without a shop line (R1) have an access from the side or rear open spaces, the width of the such open spaces shall not be less than 7m.

19.4.2 Uses Permissible in Commercial Zone :

- i) Any use permitted in residential zone without area and floor restrictions.
- ii) Club, business houses, veterinary- dispensaries, testing labs, paper and plastic packing bags and boxes manufacturing, mattress making.
- iii) Business Offices and exchanges.
- iv) Whole -sale establishments with storage area not exceeding 200 sq. m. subject to fire protection requirements.
- v) Public utility buildings.
- vi) Headquarters organizations.

19.5 CENTRAL BUSINESS DISTRICT ZONE – Deleted

19.6 INDUSTRIAL ZONE

Industries shall include any building or part of a building or structure, in which products or materials of all kinds and properties are fabricated, assembled or processed, for example assembly plants, laboratories, dry cleaning plants, power plants, pumping station; smoke houses, laundries, gas plants, refineries, dairies and saw - mills.

The following users shall be permissible in Industrial Zone.

- i) The service industries as listed in Appendix –L without restrictions on power requirement, employment, floor area and other restrictions.
- ii) Any industry / industries may be permitted only if the location is appropriate and is not likely to cause nuisance or hazard to adjoining owners. Minimum buffer open space / set back (which may include marginal distance and road width if any) from the boundary of industrial zone to residential or habitable zone/ use, shall not be less than 23 m. such buffer open space shall be kept in the land falling in the industrial zone.

Provided that, the area under such buffer setback shall not be deducted for computation of FSI.

Provided further that, if the land under industrial zone is utilized entirely for IT / ITES purposes, such buffer open space shall not be necessary.

- iii) Building or premises in industrial zone may be used for any industrial as well as accessory uses like banks, canteens, welfare centre and such other common purposes considered necessary for the industrial workers, quarters of watchmen, caretakers or other essential staff required to be maintained on the premises. Such residential/commercial/other uses may be permitted up to 25% of the total proposed built-up area of such industrial use.

Provided that, the Industries shall also be permissible in the buffer zone falling within 5 km distance from the PMC and PCMC Boundaries.

- iv) Following uses may also be permitted (Subject to provisions of separate entry & exit) to such users:

- (a) Parking lots,
- (b) Building of public utility concerns,
- (c) The buildings of Banks,
- (d) Residential Hotels, Restaurants,
- (e) Storage Buildings,
- (f) Drive-in -Theatres, cinema or theatres, subject to provision of provision of the Maharashtra Cinemas (Regulation) Act,
- (g) Highway amenities as permitted in Agriculture zone with FSI at par with Industrial zone,
- (h) Industrial training centre/ institute,
- (i) Information Technology Establishments. (IT/ITES),
- (j) Bio technology units,
- (k) Petrol pumps and service Station.

v) Allowing Residential / Commercial User In Industrial Zone (I to R Provision):-

- a) With previous approval of the Metropolitan Commissioner in consultation with the Divisional Head of concerned division of the Town Planning Directorate and on such conditions as deemed appropriate by him, the existing or newly built-up area of Industrial unit, in the Industrial zone may be permitted to be utilised for residential or commercial purposes.
- b) With the previous approval of the Metropolitan Commissioner, in consultation with the Divisional Head of Town Planning Directorate, the lands in the Industrial Zone including lands in industrial zone in Town Planning Scheme area, may be utilised for any of the permissible users in the Residential and Commercial Zone subject to the following conditions:
 - i) Such user shall be allowed only on payments of Premium at the rate 20 % of the land value arrived as per Annual Statement of rates (without considering the guidelines therein) of the respective year.
 - ii) The Residential/ Commercial user in respect of industries which are not in operation shall not be permitted unless NOC from Labour Commissioner, Maharashtra State, Mumbai stating that all legal dues have been paid to the workers or satisfactory arrangement between management and workers have been made, is obtained. However, in respect of any open land in the Industrial Zone where industry never existed, NOC from Labour Commissioner shall not be required.

- iii) In the layout or sub-division of such land admeasuring upto 2 Ha., 10% land for public utilities and amenities, like electric sub-station, bus-station, sub-post office, police out- post and such other amenities/utilities as may be considered necessary shall be provided.
- iv) In such layouts of sub-division having area more than 2 Ha. and upto 5 hect., 20% land shall be provided for public utilities and amenities like electric sub-station, bus-station, sub- post office, police out- post, garden, playground, school, dispensary and such other amenities/utilities as may be considered necessary.
- v) In such layout or sub division each more than 5Ha. in area, 25% land for public utilities and amenities like electric, sub-station, bus- station, sub-post office, police out post, garden, playground, school dispensary and such other amenities shall be provided.
- vi) With the special written permission of the Metropolitan Commissioner, the land having area up to 0.20 hectare in size which are allocated for industrial use may be permitted to be used for Residential purpose or any other permissible users in Residential Zone. Provided that, in such case the owner / developer shall be required to provide either by providing 10% amenity space in the form of open land or 5% built up space in the proposed construction at appropriate location preferably on ground floor.
- vii) The land under public utility / amenity shall be handed over to the Authority in lieu of FSI / TDR with proper access and basic land development. These areas will be in addition to the recreational space as required to be provided under these regulations.

Provided that, at least 50% of total land provided for public amenity/ utility space shall be reserved for unbuildable purposes such as garden, recreational ground, etc.

Provided also that irrespective of land use zone, where the provisions of Development Control and Promotion Regulations provide for amenity Space in Residential area which is more than what is stipulated in these regulations, then Amenity Space which is more shall only be provided.

- c) The required segregating distance between Industrial Zone and the area over which Residential use is permitted under this regulation, shall be provided within such land intended to be used for residential or commercial purpose.
- d) Such residential or local commercial development shall be allowed within the permissible FSI of the nearby Residential or Commercial Zone.
- e) Provision for Amenity Spaces shall be considered to be reservations in the Regional Plan and Transferable Development Rights against such amenity as per Regulation No.15.4 may be given or FSI of the same equivalent to the TDR quantum shall be available for utilisation on the remaining land. Moreover, the owner shall be entitled to develop remaining land with permissible TDR potential including the land under amenity space subject to maximum permissible limit of FSI (Maximum Building Potential) as mentioned in Regulation No.20.3.
provided that,
 - i) Residential/Commercial user may be allowed on the part area of the land holding subject to the condition that total area of

- the entire land holding shall be considered for deciding the percentage of the land to be reserved for public amenity/ utility spaces, as per these regulations.
- ii) If Regional Plan/Development Plan Reservations (excluding RP/DP Road/Road widening) are in the land under I to R conversions, then such reservation may be adjusted in amenity space as mentioned in the following manner:
 - a) If the area under Regional Plan/Development Plan reservation is less than the required area of public amenity space as per the said regulation, then only the difference between the area shall be provided for public amenity spaces.
 - b) If the area under Regional Plan/Development Plan reservation is more than the required area of public amenity spaces as per the said regulation, then the area for public amenity spaces shall be provided equal to Regional Plan/Development Plan reservation area.
 - iii) Out of the total area proposed to be utilised for residential development, 20% of the same shall be built for residential tenements having built up area 30 sq.m. and upto 50 sq.m. or in the plotted development, 20 % area shall be of plots upto 150 sq.m.
 - iv) While allowing such conversion minimum 20 % built up area shall be used for offices and commercial purpose.

19.7 AGRICULTURAL ZONE / NO DEVELOPMENT ZONE

The following uses shall be permissible:-

- (i) All agricultural uses including stabling of Cattles up to the limit of 10 animals per hectare.
- (ii) Poultry Farms.
- (iii) Public/semi-public sector utility establishments such as electric sub-stations, receiving stations, switch yards, over-head line corridors, radio and television stations, receiving stations, main stations for public gas distribution, sewage treatment and disposal works, water works along with residential quarters for essential staff required for such works, with the special permission of Metropolitan Commissioner.
- (iv) Garden, forestry, nursery, public parks, private parks; play fields, summer camps for recreation of all types.
- (v) Golf Course and Links, Race tracks, and shooting ranges with necessary safety measures.
- (vi) L.P.G. Godown, subject to following conditions:
 - a) Area of plot shall not be less than 1000 Sq.m.
 - b) The maximum permissible FSI shall be 20% on this plot.
 - c) Only ground floor structure shall be permissible.
 - d) It is necessary to obtain —No Objection Certificate— from Controller of Explosives and competent fire authority.
- (vii) Petrol/ Diesel /LPG /CNG, Pump subject to FSI upto 20% on gross area and subject to other provisions prescribed in regulations for special occupancies.
- (viii) Pottery manufacture.
- (ix) Storage and drying of fertilizer.
- (x) **Farm houses** subject to following conditions:-
 - (a) Minimum plot area under above use shall be 0.4 Ha.
 - (b) The land in which it is to be constructed is actually put under agricultural use.
 - (c) Farm house shall be permitted by the Metropolitan Commissioner only after the requisite permission for farm house is obtained by the owner from the Metropolitan Commissioner under the provisions of Maharashtra Land Revenue Code, 1966 and attested certified copy of such permission is attached with the application under Section 44 of the The Maharashtra Regional and Town Planning Act, 1966.
 - (d) The FSI shall not exceed 0.0375 subject to a maximum built up area of 400

sq.m. in any case. Only ground floor structure with or without stilt shall be permissible.

- (xi) Swimming pools / sports and games, health clubs, cafeteria, canteen, tennis courts, etc.
- (xii) Amusement park.

a) Amusement park with minimum plot area of 1.00 hect. With recreational and amusement devices like a giant wheel, roller coaster, merry-go-round or similar rides both indoor and outdoor, oceanic -park, swimming pool, magic mountain and lake, ethnic village, shops for souvenirs/citations, toys, goods, as principal uses and ancillary activities such as administrative offices, exhibition hall or auditorium, open air theatre, essential staff quarters, store buildings, fast food shops, museum, souvenir and small shops, ancillary structures to swimming pool ancillary constructions. Maximum permissible FSI shall be 0.20 i.e. FSI of 0.15 for principal activity and 0.05 for ancillary activities.

b) The required infrastructure, like proper and adequate access to the park, water supply, sanitation, conservancy services, sewage disposal and adequate off-street parking will have to be provided and maintained by the promoters of the project at their cost and to the satisfaction of the Metropolitan Commissioner.

c) The promoters of the project shall provide adequate facilities for collection and disposal of garbage at their cost, and to the satisfaction of the Metropolitan Commissioner and will keep, at all times, the entire environment clean, neat and hygienic.

d) Structures permitted in the amusement park (except those intended for park apparatus, entertainment such as magic mountain etc. and other equipment) should be ground floor structures, with the construction blending with the surrounding environment and landscape.

e) Except for minor dressing, hills and natural features, if any, shall be maintained in their natural condition and beautified with planting of trees etc.

f) All trees already growing on the land shall be preserved to the extent possible, except that if it becomes necessary to cut any tree, the required permission of the Metropolitan

Commissioner should be obtained under the relevant Act. At least 5 trees (of indigenous species) per 100 sq. m. shall be planted and grown within the area of the park.

g) Sufficient parking facilities and ancillary facilities for cars, buses, transport vehicles etc. shall be provided on site as prescribed by and to the satisfaction of the Metropolitan Commissioner.

h) The promoters of the project will prepare a suitable layout with appropriate landscaping of the recreational and other facilities and obtain approval of the Metropolitan Commissioner.

i) The development shall be regulated according to other requirements of these and all applicable rules and Regulations and subject to all other clearances as may be required.

j) Proper arrangements for safety, Regulations of traffic approaches to the park etc. shall be made to the satisfaction of the Metropolitan Commissioner and Police, from the law and order and traffic aspects.

- (xiii) Mobile Phone Towers with ancillary equipment as specified in Regulation no.45.0

- (xiv) The following users shall be permitted as per the policies decided by the Government from time to time:

a) IT/ITES parks/units in no development zone.

b) Research and Development institutions / Centers on following conditions:

1. The area of land shall be minimum 10 hectare.
2. FSI permissible shall be maximum 0.20 on gross plot area after deducting area under R.P. Road/D.P. Road/ Reservation/deemed reservation, if any.
3. Construction of staff quarters related to such institutions/center shall be permissible to the extent of 50% of the total proposed built-up area for such institution/center.
4. Trees of indigenous species shall be planted at the rate of 500 trees per hectare.
5. Research and Development of hazardous chemical and explosives may be permitted with the special permission of Metropolitan

Commissioner which may be granted after compliance of all safety measures and certification from concerned Government Authorities.

c) Bio-technology unit / B.T. Park.

d) Integrated highways amenities such as motels, way-side restaurants, fuel pumps, service stations, restroom and canteen for employees working on site and truck drivers, service godowns, factory outlets, highway malls, hyper market along with public conveniences like toilets, trauma centre, medicine shop, bank ATMs and like activities with FSI of 0.5 on gross area.

The Integrated highways amenities shall be allowed subject to following conditions:

- a) Minimum area of plot shall be 10000 Sq.mt.
- b) 10 % amenity space shall be provided which shall be handed over to planning authority.

- (xv) Ancillary service industries for agriculture produce marketing and management, ancillary service uses for agro related products like flowers, fruits, vegetables, poultry products, marine products, related collection centres, auction hall, godowns, grading services and packing units, knowledge parks, cold storages, utility services (like banking, insurance, post office services) as service industries for agriculture produce marketing on the land owned by individuals / organizations with FSI of 0.20
- (xvi) Solid waste management, land fill sites, bio-gas plants, power generation from waste.
- (xvii) Power generation from non-conventional sources of energy. Area covered under solar panels shall not be counted in FSI.
- (xviii) Brick, tile manufacture.
- (xix) Fish Farming.
- (xx) Religious buildings subject to conditions as may be prescribed by Planning Authority.
- (xxi) Slaughter house or Facilities for processing and disposal of dead animals with the special permission of PMRDA.
- (xxii) Cemeteries and crematoria and structure incidental thereto.
- (xxiii) Mangal karyalaya / lawns.
 - a) Minimum area for mangal karyalaya shall be 0.40 hect. with FSI of 0.20. It may be permitted along with essential guest rooms not exceeding 30% of the area of mangal karyalaya. Area for parking shall be 40% of gross area which shall be properly earmarked and bounded by bifurcating wall.
 - b) Lawns for ceremony shall be 0.80 hect. with FSI of 0.10. Area for parking shall be 40% of gross area.
 - c) The plot for mangal karyalaya or lawn shall abut on road having width of minimum 15m.
 - d) Such user (Mangal karyalaya and Lawns) shall be allowed only on payments of premium at the rate 10 % of the land value arrived as per Annual Statement of rates (without considering the guidelines therein) of the respective year.
- (xxiv) Bus Terminus.
- (xxv) public or private road.
- (xxvi) In the villages where no specific residential zone is shown, residential development may be permitted -
 - a. within a belt of 500 meters from the gaathan limits of settlements having a population of less than or equal to 5000 as per the latest Census and,
 - b. within a belt of 1500 meters from the gaathan limits in the case of non-municipal settlements having a population of more than 5000 as per the latest Census.
 - c. in case of settlements of both the categories, mentioned above, falling in the planning areas of Zone Plans, such distance from the gaathan limits shall be 500 meters only.
 - d. in the case of village settlements in the western ghat hilly area of the district, such residential development may be restricted to a belt of 200 meters from the gaathan limits.

For the purpose of this regulation, Western Ghat area shall be the area as declared and notified by the Ministry of Environment and Forests Department, New Delhi vide their Notification No.F.No.1-4/ 2012-RE(Pt.) Dt.13/11/2013 and amended from time to time.

Provided that such Residential development in the aforesaid belt in all the categories mentioned above (i) to (iv) shall not be permissible on lands which deserve preservation or protection from environmental considerations, viz, hills and hill-tops, and belts of 200 meters from the H.F.L.s of major lakes etc.

Provided further that for the Residential Zone available considering latest population as mentioned in (i) to (iii) above, the Metropolitan Commissioner shall prepare proper road network plan for the villages falling under their jurisdiction considering the existing roads and sanctioned Regional Plan proposals within a stipulated time of six months from the date of sanction of this modification and take preliminary approval from Director of Town Planning, Maharashtra State, Pune and submit the same to the State Government for modification to the Regional Plan under Section 20 of MR & TP Act, 1966. The Developer / Land Owners shall incorporate such proposed road network in their development proposals. However the sanctioning process of plans shall not be stopped during the course of preparation of such road network plan. Such road network subsequently be incorporated while preparing Development Plan for the PMRDA area.

Notwithstanding anything contained in the above regulation, such residential development in Agriculture/No development Zone shall be permitted only on payment of premium of the total area of land. Such premium shall be calculated considering 30 % rate of the said land as prescribed in the Annual Statement of Rates of the year granting such residential developments.

Provided further that where more than 50 percent of area of the Survey Number/Gat Number is covered within the above peripheral distance then the remaining whole of such Survey Number / Gat Number within one ownership shall be considered for development on payment of premium as above.

Provided further that, the "distance from gaathan" criteria shall also be applicable to the plots from the nearest gaathan of any village.

- (xxvii) Development of buildings of educational and medical institutions, run by Government / Public Authorities or run by Public Charitable Trusts may be permitted in Agriculture / No Development Zone with built up area upto 1/5th (i.e. 20%) of the net plot area, having at the most ground plus one storey, subject to plantation of trees at the rate of 5 trees per Are on the plot.

Provided that additional FSI over and above the basic FST permissible above may be granted by the Metropolitan Commissioner as per the following Table and subject to the conditions mentioned below: -

Sr. No.	Land Fronting on Road	Basic Permissible FSI on Net Plot Area	Additional FSI*	Maximum Permissible FSI	Note
1	2	3	4	5	6
1	Road having width of 12 mt. and above but less than 18 mt.	0.2	0.5	0.7	The building height above 15 mt. subject to maximum upto 30 mt. or as mentioned in Maharashtra Fire Prevention and Life Safety Measure Act, 2006 shall be allowed after clearance / No Objection Certificate from the Fire Advisor/Chief Fire Officer
2	Road having width of 18 mt. above	0.2	0.8	1.0	

Conditions:-

- (a) The additional FSI as mentioned in Column No. 4 of the Table above is to be granted only on payment of premium calculated considering 30% rate of the said land as

prescribed in the Annual Statement of Rates (ASR) of the year of granting such additional FSI. The Land Area considered for premium shall be equal to additional FSI / Built-Up area granted.

- (b) In case the educational use involves the nursery and elementary Schools, such nursery and elementary Schools shall be housed in single building with maximum Ground+ 2 floor.
- (c) Regulation No. 21 of the Standardised Development Control and Promotion Regulations shall apply to the above buildings constructed under this Regulation.

xxviii) Additional FSI in Agriculture / No-Development Zone for three stars and above category Hotels along National and State Highways shall be permissible subject to following conditions: -

- (a) Development of buildings for three stars and above category Hotels in No Development Zone along National and State Highways shall be permissible on independent plot upto FSI limit of 0.10 on gross plot area.
- (b) Additional FSI upto 0.90 on gross plot area, over and above the basic FSI permissible under clause (a) above, may be granted by the Metropolitan Commissioner on payment of premium calculated considering 35% rate of the said land as prescribed in the Annual Statement of Rates (ASR) for the year in which such additional FSI is granted. The land area considered for premium shall be equal to additional FSI/Built-Up area granted.
- (c) All other regulations, as applicable to Residential Zone, shall apply to the layout and buildings constructed under this Regulation.

19.8 GREEN BELT

19.8.1 Following uses shall be permissible

- (i) Agriculture,
- (ii) Tree Plantation, Gardens, Landscaping, public park Landscaping, Forestry and Nursery etc.
- (iii) River front development by Metropolitan PMRDA, or any institution authorised on behalf of Metropolitan Commissioner, PMRDA.
- (iv) Development of pedestrian pathways, Jogging track, Cycle track, Boat club etc.
- (v) Swimming pool, club house, recreational facilities after leaving marginal distance of 15 m. belt along river bank and 9.0m. from river and nalas, respectively subject to FSI of 10% with ground floor structure only, provided that no such construction shall be allowed within the blue line.
- (vi) Public toilets as per requirement, provided that no such construction shall be allowed within the blue line.
- (vii) Recreational open space of any layout/ sub-division/ development proposals, if submitted along with the developable land adjoining to such green belt, after leaving marginal distances of minimum 15m. and 9.0m. from river and nalas, respectively, (clarification – it is clarified that the FSI of the land under green belt zone shall be permissible to be utilized on the land adjoining but outside such green belt zone.)

19.8.2 The users and its extent shall be permissible in such Recreational open space, as prescribed in the regulation of Green Belt as mentioned above, provided that no such construction shall be allowed within the blue line.

19.8.3 If the land under green belt zone, excepting open space therein if any, is required by Metropolitan Commissioner for the public purposes mentioned above, the owner shall hand over the possession of such land for the development and maintenance of public purposes. Thereafter, such land shall remain open and accessible to general public for recreational activities.

Provided that, FSI of such land under Green Belt zone shall be permissible only after handing over such land to the PMRDA free of cost and free from encumbrances.

19.8.4 The side/rear marginal distances for the proposed building adjoining to river / nala shall be maximum of-side / rear marginal distance, to be measured from river/nala, as required according to height of building or 4.5 m. from the dividing line between green belt zone and the other developable zone.

19.9 Hill Top & Hill Slope Zone in PMR: These areas shall be exclusively used for tree plantation & no construction of any sort including farmhouse/forest house shall be permitted in this zone.

19.10 PUBLIC /SEMI PUBLIC ZONE.

A) User to be permitted- The following uses shall be permissible:

- (i) Schools, Colleges, Educational Complex, Training institutions, Hostels for students and essential staff quarters.
- (ii) Home for the aged, Hospitals, Sanatoria, Dispensary, Maternity Homes, Health Centre, and related health facilities with ancillary structures like quarters, Dharmashala, veterinary hospital, etc,
- (iii) Offices and essential staff quarters of the Government/ Semi Government and/or its authority/ Local Self-Government.
- (iv) Public/semi-public sector utility and transport establishments / institutions of research, education and health
- (v) Library, Mangal karyalaya, Gymnasium, Gymkhana, Stadium, Community hall, Civic and Cultural Centres, Religious Structures, auditorium etc.
- (vi) Commercial use upto 15% of proposed built-up area by considering the permissible basic FSI, subject to following conditions
 - a) Shop/permit rooms for liquor/wine/beer, pan, cigarette, tobacco, lottery tickets and such other uses which do not serve public purpose, similarly storage of domestic gas cylinders, kerosene etc., which are dangerous to public health, shall not be permitted.
 - b) Additional F. S. I., if otherwise permissible under these regulations, shall be permitted only on the plot area remained after deducting the notional plot area utilised for commercial user.
 - c) The Metropolitan Commissioner shall not allow sub - division of S. No. / Gat No. / Plot No. on which such a Development which may cause/ has taken place/ would take place.
 - d) The retail commercial user is permitted upto a depth of 12 m. or in separate building
 - e) The plots in which there is an existing development; such commercial use shall be restricted to maximum 15% of the existing and proposed development taken together.
 - f) The land owner / developer / institution shall give guarantee in writing to the Metropolitan Commissioner for following all the stipulated conditions scrupulously. Provided that, in case of lands owned by Zilla Parishad and Panchayat Samiti, which are earmarked as public and semi-public zone, the limit of such commercial user shall be upto 33%.
- (vii) Petrol/LPG/CNG Pumps as per Regulation no.20.2.2(5).
- (viii) Nursery, crèches, Spastic rehabilitation centres, orphanages, hostel for Autistic persons and Mentally Retarded persons.
- (ix) Fire stations,
- (x) Traffic and Transport related facilities,
- (xi) Student Hostels and working women's hostel, Special Housing Schemes such as EWS, HDH, PMAY, Old Age Homes and such additional public utility users as decided by the Metropolitan Commissioner of PMRDA.

B) In case any private property is included within the boundary of public and semi-public use and if the owner can establish that the private/ individual ownership of land vest with him, the land use existing/ adjoining to the PSP zone shall be assigned to this piece of land with special written permission of the Metropolitan Commissioner.

19.11 TRAFFIC AND TRANSPORTATION ZONE – Deleted

19.12 DEFENCE ZONE - The developments as may be required by the Ministry of Defence or its Authorities, as per their requirements, shall only be permissible on the lands owned and possessed by the Ministry of Defence or it's Authorities.

19.13 FOREST ZONE - The developments as may be required by the Ministry of Forest or its Authorities, as per their requirements shall only be permissible on the lands owned and possessed by the Ministry/ Department of Forest or it's Authorities.

19.14 RESTRICTIVE ZONE – The area affected by the notification under Works of Defence Act- 1903, is earmarked in the Regional Plan as such and no any development in contravention with the notification shall be permissible.

Provided that, it shall be permissible to treat the area under such restrictive zone as marginal distance at time of construction of any building proposed on contiguous unaffected area.

Provided further that, it shall be permissible to utilise the FSI and also the receiving potential of the land under this zone, as otherwise permissible, on the remaining contiguous unaffected land of the same land owner.

19.15 AFFORESTATION ZONE: The following uses shall be permissible:

In addition to the plantation of trees, forest houses, farm houses meant for the servants/technicians/owner and for storing of fertilizes/forest tourist etc., may be permitted subject to the following regulations-

- A. Building for the residential purposes such as forest house, farm house shall have built-up area not exceeding 100 sq.mt. provided that, forest plot area is not less than 0.4 hect., Additional area of 50 sq.mt. may also be permitted for ancillary users. Structures to be erected for these purposes should be of ground floor only and should not have height more than 5 mt. and should be of such material as would blend with the surroundings:

Provided further that, no forest house, farm house should be permitted unless owner has planted at least 800 trees per hect. (or such lesser nos. on the basis of the species selected and approved by the forest department), and only after such trees are reared for one year.

Provided further that, no forest house, farm house will be permitted i) within distance of 100 mtrs, from H.F.L./F.S.L. of the lake ii) and on hill slope steeper than 1:5. Layout of the forest houses may be permitted for areas more than 0.4 hect.

- B. Tourist Resort Complexes as per Regulation No. 38.8.
- C. Land in the afforestation zone may be permitted to be used for agricultural purposes.
- D. Construction of buildings including quarters for essential staff for public utility concerns such as electrical substations, receiving stations, chilling plants, waterworks, sewage disposal works etc.
- E. Construction of any communication route, road, railway, airstrips, electric lines etc.
- F. In a village, residential development may be permitted within a belt of 200 mts. of gaathan limit along with social amenities necessary with such development. Such developments shall be governed by the Regulations laid under the Residential Zone of these Regulations, provided that the restrictions as laid down in Regulation No. 13.1 (SITES NOT ELIGIBLE

FOR CONSTRUCTION OF BUILDING) shall apply to these developments.

G. Ropeway Projects as stipulated in Regulation No. 40.2

H. Planetarium / Astronomical / Astrophysical facilities / projects as stipulated in Regulation No. 40.3

I. Trekking Routes / nature trails / nature walks as stipulated in Regulation No. 40.4.

J. Uses stipulated in 19.7 (xiv. d))

K. Registered Public & Private Institutions of repute, mainly engaged in community development, Human Resources Development & ancillary Development, rural upliftment, public health, education & charitable activities may be permitted with F.S.I. restricted to 0.20 of net plot area with structures not more than ground plus one storeyed and trees are planted at the rate of 500 trees per hectare.

PART - IV
GENERAL BUILDING REQUIREMENTS –
SETBACK, MARGINAL DISTANCE, HEIGHT AND PERMISSIBLE FSI

20.0 GENERAL

Following regulations for congested area shall be applicable for the lands included in congested area as shown on the plan. For the areas outside congested area in the development plan, regulation for outside-congested area shall apply. However, in congested area, if the original land holding is more than 0.40 Hect., then regulations of non-congested area shall apply.

20.1 REGULATIONS FOR CONGESTED AREA

20.1.1 MARGINAL OPEN SPACES, AREA AND HEIGHT LIMITATIONS AND PERMISSIBLE FSI FOR BUILDINGS SITUATED WITHIN CONGESTED AREA

20.1.2 RESIDENTIAL BUILDINGS

(a) Floor Space Index.

Maximum permissible FSI shall be 1.50 for purely residential building and in case of mix residential with commercial or other user, additional FSI, limited to 0.5 only in R-2 zone for non-residential user may be permitted

(b) Marginal Open Spaces/Setback - The minimum front setback from the existing or proposed road shall be as under:-

S.No.	Road width	For Purely Residential	For Mixed Users
(i)	For streets 7.5 m. to less than 12 m. in width	1.00 m.	2.00 m.
(ii)	For streets 12 m to less than 18 m. in width	1.50 m	2.50 m.
(iii)	For streets 18 m & above in width	2.00 m	3.00 m

(c) Side & rear open spaces in meter shall be as below :

Residential Plot Area	Side	Rear
Upto 250 sq. m	0.00	0.00
Above 250 & upto 500 sq. m	1.00	1.00
Above 500 sq. m. & upto 1000 sq.m	2.00	2.00
Above 1000 sq.m.	As per regulation no. 15	

NOTE :-

i) For light and ventilation, provisions in Regulation No.17.4 shall apply.

ii) For common wall construction, length of common wall shall not be more than 8 m.

d) For streets less than 7.5 m. in width, no setback shall be prescribed subject to condition that no lane shall be less than 4.5 m. in width clear of structural projection. For lanes less than 4.5 m. in width, a setback of 2.25 m. shall be prescribed from the centre line of such lane. Streets less than 4.5 m. shall be treated as lanes only when they serve as access to the properties fronting on them

e) Structural projections such as balconies, cornices, weather sheds, roof projections etc. shall be allowed in the setback distance prescribed above as per regulation No. 17.6.

f) Height- The height of the building shall be governed by Regulation No. 17.8.

g) Ground Coverage- The maximum ground coverage shall be 60% of the net plot area

- 20.1.3 Cinema Theatre, multiplex, assembly-building, shopping malls and like buildings:** For these buildings, regulations prescribed in non- congested area, except FSI, shall apply.
- 20.1.4 Educational, Medical, Institutional, Commercial, Mercantile, and Other Buildings:**
(a) **Floor Space Index** - Maximum FSI permissible shall be 2.00.
(b) **Open Space** - For these buildings open spaces shall be 3 m. on all sides.
(c) **Ground Coverage** – The maximum ground coverage shall be 50% of the net plot area
- 20.1.5** Pathway for access to the internal building or interior part of the building. The pathway shall not be less than 3.6m. (12 ft) in width.
- 20.1.6** If the width of property is less than 3.6 m. (12 ft), the entire ground floor shall be on stilts.
- 20.1.7** Front open space as prescribed by the Highway or any other rules shall be applicable if they are over and above as prescribed in these regulations.
- 20.1.8** The provisions mentioned in above Rule No.20.1.1 to 20.1.6 may be relaxed by the Metropolitan Commissioner in consultation with the Divisional Head of concerned division of the Town Planning Department, Pune, in special circumstances.

20.2 REGULATIONS FOR OUTSIDE CONGESTED AREA.

20.2.1 Marginal Distances for Residential Buildings Height 15 mt. and Below.

The provisions for minimum marginal distances as given in **Table No. 16 below** shall apply for the Residential buildings, Residential with mix uses permissible in non-congested areas and ancillary Residential buildings permissible in industrial zones having height upto 15 m. and below.

Table No. 16							
Sr. No.	Description of the road	Min Plot Size in Sq. m.	Min width of plot in meter	Min set back from road side in meter	Min. side margins in meter	Min. rear margins in meter	remarks
1	NH/SH	450	15	6.0 mt. for NH and 4.5 m. for SH or as specified by Highway rule whichever is more	3.0	3.0	--
2	MDR/ODR	450	15	6.00 mt. or as specified by Highway rule whichever is more	3.0	3.0	--
3	Roads 24 meters and above	300	12	4.50 mt for residential & 6.00 m. for residential with mix use	3.00	3.0	--
4	Roads of width below 24 m and upto 18 m.	250	10	4.50 mt for residential & 6.00 m. for residential with mix use	3.00	3.0	--
5	Roads of width below 18 m. and upto 15 m.	250	10	3.00 mt for residential & 4.50 m. for residential with mix use	2.25	2.25	--
6	Roads of width below 15 m. and above 9 m.	150	8	3.00 mt for residential & 4.50 m. for residential with mix use	1.50 (in case of semi-detached building, only one side open space shall be permissible)	1.50	Side and rear margins shall be 2.25 m. for building more than G+2 or stilt + 3 structure

7	Road of width upto 9 mt.	100	7	3.00	1.50 (in case of semi-detached building, only one side open space shall be permissible)	1.50	--do--
8	Row Housing on roads of 12 mt. and below	30 to 125	3.50	2.25	0.00(In case of corner plot, 1.50 or building line of adjoining road whichever is more)	1.50	Side and rear margins in this row only for G+1 or stilt + 2 structure
9	Row Housing for EWS/LIG/Slum Up gradation etc. by public authority.	20 to 50	3.00	0.90 mt from pathway or 2.25 mt from road boundary	0.00(In case of corner plot, 1.50 or building line of adjoining road whichever is more)	0.90m	Side and rear margins in this row only for G+1 or stilt + 1 structure

Note:-

- (1) Higher height may be permitted subject to marginal distance mentioned in Regulation No.17.3.
- (2) The minimum area of plots fronting on service roads along highways shall be with reference to the width of service road.
- (3) For semidetached buildings, side margin shall be on one side only.
- (4) Row-housing plots at the junction of two roads shall be larger to maintain the setback from both roads. Not more than 12 and not less than 3 plots shall be allowed in each block of row housing. Each block shall be separated from the other by 6 m. road or 6 m. side margin distance of the plot or space including side marginal distance of the plot.
- (5) No garage shall be permitted in a building having stilt or basement provided for parking.
- (6) Construction of ottas, railings, barricades or supporting columns for canopy or porch shall not be allowed in front marginal distances. However, steps may be permitted within 1.2 m. from the building line. Also supporting columns for canopy or porch may be allowed within building line.
- (7) In no case ribbon development rules shall be relaxed without consent of the Highway Authority.
- (8) In case of special building, marginal distances shall be as per said regulations.
- (9) The plot width to depth ratio shall be 1:1.5 to 1:2.5, as far as possible in case of plotted layout development permission.
- (10) In Public Housing Schemes for E.W.S. undertaken by government or semi-government organizations, marginal distances shall be as per their respective schemes and rules.
- (11) The front setback set-out in already approved and partially developed layouts / schemes, may be retained as per said approval, so as to maintain the building line.

- (12) The pattern of development like semi-detached, row housing, etc. in already approved layout shall be as per said approved layout.
- (13) Where commencement certificate is granted prior to publication of any draft/ revision of Regional/ Development Plan and the said plot is affected by new road proposed in the Revised Regional/Development Plan, then front margin stands relaxed to that extent.

20.2.2 Other Buildings: The Provision as given in Table No.17. below shall apply for different categories of other buildings.

Table No. 17				
Sr. no.	Type of building	minimum road width required	Minimum marginal distances	Other stipulations
1	2	3	4	5
1	Medical buildings			
	a) Hospital, Maternity Homes, Health Club, Public Semi-public buildings being special building	12 m.	6 m. on all sides	Other requirements shall be as mentioned in the table no.20 of regulation no.21.1
	b) Hospital, Maternity Homes, Health Club, Public Semi-public buildings not being special buildings	12 m.	Margins as per Table no. 16	Other requirements shall be as mentioned in the table no.20 of regulation no.21.1
	c) Clinics on plot upto area 300 sq.m.	9 m.	Margins as per Table no. 16	
2.	Educational buildings			
	a) Pre-primary School	6m.	Margins as per Table no. 16	Other requirements shall be as mentioned in the table no.20 of regulation no.21.1
	b) Primary School	9m.	6.00 m. on all sides	
	c) Other Educational Buildings	12 m.	6.00 m. on all sides	
3.	Cinema Theatre/ Drama Theatre/ Assembly Hall/ Multiplex / Shopping Malls	15 m.	Front – 12 m. (only on one major road) Remaining 6 m. on all sides	Construction of Cinema Theatre/Multiplex shall confirm to the provisions of Maharashtra Cinema (Regulations) Rules, 1966 and as amended from time to time.
4.	Mangal karyalaya like buildings	12 m.	Front – 12 m. (only on one major road) Remaining 6 m. on all sides	-

5.	Petrol/Fuel Filling Stations with or without service bays	12 m.	6.00 m. on all sides	1) Fuel filling station shall not be permitted within a distance of 90 meter from the nearest gate of school, hospital and theatre, place of assembly or stadium. 2) In the case of kiosks and other buildings for sales office, snack bars etc. within the plot for fuel filling stations, the setbacks from the boundaries shall be 4.50 m. Further the other clearances for the installations shall be as per the Petroleum Rules of 1937.
6.	Mercantile/ Business/ hotel/ Commercial/ mix use with residential buildings.	12 m.	Front 6.00 m. Side & rear 4.5 m.	i) Shops may also be allowed fronting side and rear margins. ii) Minimum area of Shops shall be 6 Sq.mt with a minimum width of 2.00 m.
7.	Stadium / Pavilion	12 m.	6 m. on all sides	Covered portion shall not exceed 20 % of plot area. The spectators' gallery of the stadium shall not be counted towards FSI. Shops below spectator's gallery may be permissible.

NOTE:

- i) In case of plots fronting on National Highway, State Highway and Major District Roads, the building line shall be as per Ribbon Development Rules as given in Table above, whichever is more.
- ii) Side and rear marginal distances mentioned in above Table shall be subject to Regulation No.17.3, whichever is more.
- iii) In case of special building, marginal distances shall be as per said regulations.

20.3 PERMISSIBLE FSI:-

Permissible basic FSI, additional FSI on payment of premium, Permissible TDR Loading on a plot in non-congested area for **Residential and Residential with mix uses** shall be as per the following Table No. 18

Table No. 18					
Sr.no.	Road width in meter	Basic FSI	Additional FSI on payment of premium	Maximum permissible TDR loading	Maximum building potential on plot
1	2	3	4	5	6
1	Below 9.0 meter	1.0	0.20	0.00	1.20
2	9.00 meter and upto 12.00 meter	1.0	0.20	0.20	1.40
3	12.00 meter and upto 15.00 meter	1.00	0.20	0.30	1.50
4	15.00 meter and upto 24.00 meter	1.10	0.20	0.40	1.70
5	24.00 meter and upto 30.00 meter	1.20	0.20	0.50	1.90
6	30.00 meter and above	1.20	0.20	0.60	2.00

Note-

- The above FSI shall be applicable for existing as well as proposed roads, provided that the plot is physically made accessible as per Regulation No. 14.3.
- The Premium FSI shall not be allowed without utilization of TDR.
- Maximum permissible building potential on plot mentioned at column no.6 shall be inclusive of FSI allowed for handing over RP/DP Road and the Amenity Space to the PMRDA. Such in-situ FSI may be considered as a part of maximum permissible TDR loading given in column no. 5.
- The restrictions of road width mentioned above shall not be applicable in cases where, the permissible FSI is more than the basic FSI in various schemes such as, MHADA buildings, MRTs and BRTs routes, TPS Area and any special projects of Govt. of Maharashtra/Public Undertakings etc.
- The maximum limits of FSI prescribed above shall be applicable to fresh permission and also to an existing building which has not been granted full occupation certificate but subject to production of stability certificate from structural engineer in respect of such existing building. However, in no case the rights of the flat owner / unit holders shall be adversely affected.
- Premium** - Rate of premium for the additional FSI as mentioned in column no 4 above shall be decided by Government from time to time. The premium collected shall be shared 50:50 between State Government & PMRDA respectively. The premium of the Government shall be deposited by the planning authority in a Government head account.
- The Metropolitan Commissioner shall deposit the amount collected through the charges for premium in a separate development fund called as — PMRDA Infrastructure fund and shall utilize the same only for the purpose of developing new/ up-gradation of infrastructure as well as implementation of Regional Plan/Development Plan proposals and creation of civic amenities.
- Basic FSI for the plots of sizes having area up to 0.2 ha shall be 0.75 and the values of column no. 4, 5 and 6 shall vary proportionately.

20.4 INDUSTRIAL BUILDINGS

Minimum plot area, marginal space, Permissible FSI, Additional FSI with payment of premium for industrial building shall be as per the Table No. 19 given below:-

Minimum plot area, marginal space, Permissible FSI-

Table No. 19						
Sr. No.	Min. road width	Plot Size in sq.m.	Basic Permissible FSI	Additional FSI on payment of premium	Min. Front Margins	Min. Side & Rear Margins
1	2	3	4	5	6	7
1	12m.	Upto1000	1.10	0.20	4.50	3.00
2	12m.	1001 to 5000	1.10	0.20	6.00	4.50
3	12m.	5000 and above	1.10	0.20	9.00	6.00

Note-

- In case of plots fronting on National Highway, State Highway and Major District Roads, the building line / control line shall be as per Ribbon Development Rules as given in Table above, whichever is more.
- Front, side and rear marginal open spaces shall be as per above Table.
- Minimum and maximum height shall be 3.60 m. & 4.2 m. respectively for industrial buildings. The greater height may be permitted as per the requirement.
- In addition of provisions of these regulations, regulations prescribed under Factory Act shall be applicable.
- Premium** - Rate of premium for the additional FSI as mentioned in column no 5 above shall be decided by Government from time to time. The premium collected shall be shared 50:50 between State Government & PMRDA respectively. The premium of the Government shall be deposited by the planning authority in a Government head account
- Buffer open space**-For construction of industrial building, buffer open space of 23 m. wide shall be left from residential or incompatible zone, wherever necessary. Such buffer open space shall be part of sizable required recreational open space. Roads and marginal distance is may also be treated as a part of Buffer open space. However, area of such buffer open space shall be counted in gross area for computation of FSI. Where green belt is shown in Regional/Development Plan between residential and industrial zone, area of such green belt shall be counted in gross area for calculation of FSI. Provided also that marginal distance for a building shall not be exclusive of buffer open space. The floor height for industrial building shall be as per requirement.

20.5 FSI of Green Belt

FSI of the green belt zone shown on the regional plan/development plan may be allowed on remaining land of the owner by counting area of green belt in gross area of plot subject to condition that the area shall always be under tree cover. The owner shall plant trees in this area with proper planning at the rate of minimum 100 trees per hectare and should have been survived for at least one year prior to issuance of occupation certificate.

Provided that, such FSI shall not be allowed if such green belt area is included in recreational open space to be left as per regulation no. 15.3.5

PART - V
HIGHER FSI FOR CERTAIN USERS

21.0 GENERAL

Additional/higher Floor space index may be allowed in certain categories in non-congested area, except as otherwise specified and subject to following conditions:

- a) Permissible **additional FSI** for the buildings as mentioned in Table no. 20 shall be the maximum permissible building potential according to road width as mentioned in Table no. 18 of Regulation no. 20.3 (wherever applicable) **minus** Basic FSI. No restriction to avail the additional FSI in the form of FSI only.
- b) Such additional FSI shall be available for use for which additional FSI is granted only and other permissible uses shall be allowed within the basic Permissible FSI.
- c) **Premium** –Premium for additional F.S.I. shall be per column 4 of the table. Rate of the premium is based on the land rate mentioned in ASR for respective S.No./CTS No. The premium collected shall be shared 50:50 between State Government & PMRDA respectively. Premium to be paid to the Government shall be deposited in the concerned Account Head of Urban Development Department at Government Treasury by the Planning Authority. The following quantum of premium shall be subject to the orders of the Government from time to time.
- d) The additional FSI shall also be permissible to existing authorised users subject to structural stability.
- e) The other conditions as mentioned in the Government Directives issued under section 154 of the M.R.&T.P.Act 1966 vide Resolution no TPS-1815/2647/CR-13/15/UD 13/Dated 14/03/2016 shall also be applicable.
- f) If the owner / developer desire to avail such additional FSI in future for new buildings , then while seeking building permission at first instance, the building plan shall be submitted considering the Marginal distances as required for the height of buildings for such additional FSI. No condonation in the required open spaces, parking and other requirements in these regulations shall be allowed. However for the existing building proposals, such condition need not be insisted. But proposal shall be cleared only after strictly confirming structural and fire safety norms.
- g) Exit Requirements, Requirements of Water Supply, Drainage and Sanitation Parking spaces requirements, Fire provision requirements shall conform the provisions as mentioned in these regulations
- h) No Amenity Spaces shall be required to be provided for the uses mention in Table No.20, except at sr.no.(I)

Table No. 20

21.1 - Permissible Marginal spaces, permissible basic FSI, Additional FSI for buildings in non-congested area

Categories of the other buildings	Basic FSI	additional FSI	Rate of the Premium	Conditions if any,									
1	2	3	4	5									
A)Educational	As per Regulation No. 20.3, wherever required	Maximum Building Potential limit as per road width as mentioned in Table No. 18(wherever required) minus basic FSI	10 %	Educational building excepting buildings for Pre-primary School, nursery Kinder garden and Special Educational Institute for Physically handicapped/Mentally ill.									
i) Pre-primary School, nursery				a) if the total area of the plot is not less than 0.4 hect. except lands reserved in Regional/Development Plan, and for the redevelopment of existing Municipal Schools,									
ii) Primary School	As per Regulation No. 20.3 wherever required	Maximum Building Potential limit as per road width as mentioned in Table No. 18 (wherever required) minus basic FSI	20 %	b) area as mentioned below is available for playground.									
				<table><tr><th>Sr.No.</th><th>Area of land</th><th>Area of Play Ground</th></tr><tr><td>(i)</td><td>Upto 5 Hect.</td><td>40%</td></tr><tr><td>(ii)</td><td>Above 5 Hect.</td><td>For first 5 hect. 40% and for remaining 20%</td></tr></table>	Sr.No.	Area of land	Area of Play Ground	(i)	Upto 5 Hect.	40%	(ii)	Above 5 Hect.	For first 5 hect. 40% and for remaining 20%
Sr.No.	Area of land	Area of Play Ground											
(i)	Upto 5 Hect.	40%											
(ii)	Above 5 Hect.	For first 5 hect. 40% and for remaining 20%											
iii) Other Educational Buildings including boys/ girls / youth hostels within 500 m. periphery from the recognised educational institutions.	As per Regulation No. 20.3 wherever required	Maximum Building Potential limit as per road width as mentioned in Table No. 18(wherever required) minus basic FSI	30 %	Provided that, it shall not be necessary to increase area of existing playground; if any, when utilisation of additional FSI as otherwise permissible in these regulations, is proposed on upper floor of existing building. Provided further that, in case of existing building wherein utilisation of additional FSI is proposed, area of playground shall not be less than 40% or the existing area of playground whichever is minimum. Provided further that, in case of existing building wherein utilisation of additional FSI on upper floors is not possible and it is necessary to expand the existing building to accommodate number of students, then in such exceptional circumstances, area of playground may be permitted to be reduced, with the prior permission of Government.									

Other Conditions-	
i) The Educational Institute shall be of Government/Semi Government public authorities, Charitable Institutions or Private Institutions	
ii) Educational buildings shall not be permissible within 60 m. from the existing assembly building and 90 m. from the existing petrol pump.	
iii) Educational building shall only be permitted if 40% area is available for playground. However, this provision shall not be applicable to already approved existing building wherein construction of additional floor is proposed.	
iv) No classroom shall admeasure less than 38 sq. m. with a minimum dimension of 5.50 m. The height of any classroom shall not be less than 3.60 m.	
v) While granting Additional FSI to Educational Institutions offering primary and secondary education 5 % seats shall be reserved for admission for Government nominees. Deputy Director, Education Department shall be competent to decide such nominations. However, this condition shall not be applicable for Higher Education, Technical Education and Medical Education.	
vi) As and when required, some rooms of Educational Buildings shall be made available to the Government by the concerned institutions.	
vii) The Educational Institution shall maintain records regarding free / concessional education rendered to the needy persons, which shall	

				be made available to the Director of School Education, Higher and Technical Education on demand. viii) The Director of School Education, Government of Maharashtra shall be the competent authority to monitor as to whether the Educational Institution is observing the terms and conditions referred to at (i), (ii) and (iii) above and, in case of any breach thereof or in case the Education being rendered by the Educational Institution are not to the satisfaction of the said Department, the Director of School Education shall have the right to suitably penalise the Education Institution. ix) The Educational Institution shall file an undertaking that it shall abide by the above enumerated terms and conditions. x) Adequate Parking facilities as required per prevailing Development Control Regulation shall be provided. xi) While granting occupation certificate the Metropolitan Commissioner shall intimate to the Director of school Education for compliance of afore said condition along with copy of occupation certificate and plan. xii) Maximum of height of Educational building shall be as per The Maharashtra Fire protection and Life Safety Measure, Act, 2006 xiii) Hostels shall not be misused and converted into other use. If it is found that the hostels are used for other purpose, Metropolitan Commissioner Authorised to take action as per the law.
--	--	--	--	---

B) Medical Institutions- Hospital, Maternity Homes, Health Club, buildings	As per Regulation No. 20.3, wherever required	Maximum Potential limit as per road width as mention in Table No. 18 (wherever required) minus basic FSI hospitals.	i) The Medical Institutions of Government, Semi Government, public authorities, Charitable Institutions or private owner. ii) Free medical treatment to the extent of atleast 20% of the total number of beds shall be given to persons from Economically Weaker Sections of society or to persons below the poverty line. In addition, 10% of the total number of patients in OPD shall be provided treatment at concessional rates, viz. rates that are being charged in government hospitals. The Medical Institution shall furnish the requisite periodical statements to the Director of Health Services in this regard. iii) The Medical Institution shall maintain records regarding free/concessional medical treatment rendered to the needy persons, which shall be made available to the Director of Health Services on demand. iv) Any Special ward in the hospital building shall not admeasure less than 9.0. sq.m. in area with no side less than 3 m. v) Area of the general wards shall not admeasure less than 40 sq. m. with no side less than 5.5. m. vi) Every building shall have a refuge collection area of minimum 7.50 sq. m. size with cover on top and unclosed on at least three sides. The same shall not be allowed in marginal open spaces. Modern method of incineration of the refuge may be adopted.	
--	---	---	--	--

			However maximum building potential shall be considered as 4.00 for Government Hospitals and 3.00 for other hospitals subject to Roads width 18 mt and more.	ii) Charitable Institutions 30% for private hospitals 40%	for vii) Minimum and maximum height shall be 3.00 m. & 4.2 m. respectively. The greater height may be permitted by the Authority as per the requirement. viii) The Director of Health Services, Government of Maharashtra shall be the Competent Authority to monitor as to whether the Medical Institution is observing the terms and conditions referred above and in case of any breach thereof or in case the medical services being rendered by the Medical Institution are not to the satisfaction of the Director of Health Services, the Director of Health Services shall have the right to suitably penalise the Medical Institution. ix) While granting occupation certificate the Metropolitan Commissioner shall intimate to the Director of Health Services, Government of Maharashtra for compliance of afore said condition along with copy of occupation certificate and plan. x) Maximum of height of building for hospitals, sanatorium and nursing homes, shall be as per The Maharashtra Fire protection and Life Safety Measure, Act, 2006.
--	--	--	--	--	---

C) Institutional buildings/As Nationalised banks/ Central Banks/ Scheduled Bank/ operative Bank.	As Regulation No. 20.3 where ever required	perMaximum Potential limit as per road No. 18 (wherever required) minus basic FSI	Building 30%	i) The institutional Buildings shall be of Government, Semi Government, public authorities or registered Charitable Institutions. ii) Minimum and maximum height shall be 3.60 m. & 4.2 m. respectively. The greater height may be permitted by the Authority as per the requirement.
D) Starred category hotels (two star and above)	(As Regulation No. 20.3 where ever required	perMaximum Potential limit as per road No. 18 (wherever required) minus basic FSI, above) However maximum building potential shall be consider as 3.00 for Roads having width 18 mt. and more.	Building 40% (up to four star) 50 % (five star and above)	i) The star category hotels shall be constructed on independent plot. ii) Certificate from the Tourism Department, GOI shall be necessary. iii) Minimum and maximum height shall be 3.60 m. & 4.2 m. respectively. The greater height may be permitted by the Authority as per the requirement. iv) While granting Additional FSI to starred category Residential Hotels 5% of rooms shall be reserved for Government nominees free of cost. Provided that such rooms be reserved for a period of not exceeding thirty days in a calendar year in a particular hotel. The head of respective authorities shall be competent to decide and monitor whether the institution is observing the terms and conditions as mentioned. v) While granting occupation certificate the Metropolitan Commissioner shall intimate to the Competent Authority for compliance of afore said condition along with copy of occupation certificate and plan.

E) Buildings of Government and Semi-Local Offices, Public Undertakings:	As per Government Regulation No. 20.3 where required	per Maximum Potential limit as per road wherever width as mention in Table No. 18 (wherever required) Nil. However Public Sector – maximum building shall be consider as 4.00 for Roads having width 18 mt and more.	Building Government and Semi-Local Offices – Authorities No. 18 (wherever required) Nil. However Public Sector – maximum building shall be consider as 4.00 for Roads having width 18 mt and more. ii) Minimum and maximum room height shall be 3.60 m. & 4.2 m. respectively. The greater height may be permitted by the Authority as per the requirement.	and) The Metropolitan Commissioner with the previous approval of State Govt. may exceed the additional FSI.
F) Religious Building:	As per Regulation No. 20.3 where required	Building per Maximum Potential limit as per road wherever width as mention in Table No. 18 (wherever required) minus basic FSI	Structure used for worship like temple, church, mosque, gurudwara, agyari etc. (a) For any construction, addition or alteration or repairs of existing religious building prior permission from Home Department through Urban Development Department of Govt. of Maharashtra shall be mandatory. b) The proposal shall be in consistent with the Regional/Development Plan proposals. c) while granting occupation certificate the Metropolitan Commissioner shall intimate to the concerned Police Authority and Collector along with copy of occupation certificate and plan. d) subject to other conditions as decided by Metropolitan commissioner. e) It shall be necessary to obtain the No-Objection Certificate from concerned Police Authority and Collector, before grant of permission. f) Other ancillary user like, administration office, Dharmashala or Accommodation for devotees, eateries, convenience shops, etc.	

G) Yatri Niwas, Youth Hostel	As Regulation No. 20.3 where required	per Maximum Potential limit as per road width as mention in Table No. 18 (wherever required) minus basic FSI	Building 15%	i) The building shall be on independent plot having minimum plot area of 1000 sq.mt. ii) Minimum and maximum height shall be 3.00 m. & 4.2 m. respectively. The greater height may be permitted by the Authority as per the requirement.
H) The Land in possession of Maharashtra State Road Transport Corporation, PMPML Pune, Metro Station	As Regulation No. 20.3 where required	per Additional FSI 0.5 over and above the basic permissible FSI.	No premium	Out of total FSI, maximum 1.00 FSI shall be allowed to be developed for commercial use and remaining FSI shall be for the self-use of the said principle use. Appropriate land shall be kept open for parking of buses, movement of buses and passengers.
I) Basic shelter for urban poor and Housing schemes developed for backward class of the society.	As Regulation No. 20.3, where required	per Maximum Potential limit as per road width as mention in Table No. 18 (wherever required) minus basic FSI or FSI upto 2.5, whichever is maximum	No premium	Any housing scheme undertaken by planning authority, government / semi government organisation, under the basic shelter for urban poor or similar programme / scheme of the Central / State Government, may be allowed FSI upto 2.5, or as permissible in these regulations whichever is maximum subject to following condition. i) The said scheme shall be for EWS/LIG housing having minimum width of road 9 mt. ii) The scheme shall be implemented by the PMRDA / Government/semi-Government Authority stipulated by the Government, from time to time. iii) The use of the land under the Scheme shall be in consonance with the proposals of the sanctioned regional/development plan. iv) Total permissible floor space index for the scheme shall be 2.50 of the gross plot area (excluding the area affected by the D.P. Reservations) v) The entire 2.50 FSI as made permissible shall be utilised of the scheme only. vi) Amenity spaces as required under these regulation shall be provided under this scheme

21.2 ENTITLMENT OF FSI FOR ROAD WIDENING OR CONSTRUCTION OF NEW ROADS / SURRENDER OF RESERVED LAND

The Metropolitan Commissioner may permit on the same plot, additional FSI of the area required for road widening or for construction of a new road proposed under the Regional/Development Plan and also for road widening / service road proposed to N.H./S.H./M.D.R./O.D.R. whether shown on Regional Plan or not, if the owner (including the lessee) of such land surrenders such land for road widening or construction of new road without claiming any monetary compensation in lieu thereof and hand over the same free of encumbrances to the satisfaction of the Metropolitan Commissioner. FSI generated against the surrender of land, shall be in proportion to the provisions mentioned in Regulation of TDR and may be utilised on the remaining land. If desired by the owner, TDR may be granted against such surrendered land instead of utilizing FSI on remaining land. Such TDR shall be allowed to be utilised as a Development Rights in accordance with the provisions of regulating Transfer of Development Rights (TDR). Thereafter, the road shall be transferred in the city survey records/revenue records in the name of the PMRDA and shall vest in it becoming part of a public street.

21.3 DEVELOPMENT / REDEVELOPMENT FOR CONSTRUCTION OF STAFF QUARTERS OF THE STATE GOVERNMENT OR ITS STATUTORY BODIES OR PMRDA ON PRIVATE LANDS

21.3.1 Regulation for staff quarters of the State Government or its statutory bodies or PMRDA on land belonging to such Authorities situate in developable zones such as Residential / Public Semi-public etc. except restricted zone such as Green Belt, Agricultural Zone, No development Zone, etc.

21.3.2 The basic FSI specified in these regulations may be allowed to be exceeded as per following table on the gross plot area solely for the project of construction of staff quarters (herein after referred to as —staff quarter project□) for the employees of the Government, or its statutory bodies or the PMRDA, on land belonging to such User Authority, by the PWD of the Government of Maharashtra or MHADA or Maharashtra Police Housing Corporation or PMRDA or any other Public Agency nominated by the Government for this purpose, which also include any Special Purpose Vehicle, wherein the Government or a fully owned Company of the Government holds at least 51% equity share (hereinafter collectively referred to as —□implementing Public Authority□)

21.3.3	Road width and plot area	Maximum permissible FSI including basic FSI
	18.0 mt or above minimum plot area 4000 sq.m. and above	2.50
	12.0 mt. or above but below 18.0 mt.	2.50

21.3.4 For the purpose of calculating the FSI, the entire area of the plot excluding area under Regional/Development Plan roads and Regional/Development Plan reservations, if any, shall be considered.

21.3.5 The total permissible FSI under this regulation shall be utilised for construction of staff quarters for the User Authority, subject to the following:

21.3.5.1 The area of staff quarters for various categories of employees shall be as per the norms prescribed by the concerned User Authority and in no case shall the area of staff quarters exceed the maximum limit of carpet area as prescribed therein.

- ii-a) Metropolitan Commissioner may also permit upto 1/3rd of the total permissible FSI under this regulation for construction of free sale area (hereinafter referred to as —free sale component□) to be disposed of by the Implementing Public Authority as provided herein. The free sale component shall preferably be constructed in a separate block. Sub-division of plots shall be permissible on the basis of equitable distribution of FSI, in case construction of free sale component is permitted by the Metropolitan Commissioner.

The free sale component may be utilised for commercial use as per potential of plot as decided by the following committee. The extent of commercial use, if required shall be decided by the said committee strictly within the limits as specified in these regulations

1. Metropolitan Commissioner - Chairman
2. Collector of Concerned District – Member
3. Superintendent of Police, Pune - Member
4. Superintendent Engineer (Pune Circle) – Member

- ii-b) If the User Authority required construction of staff quarters to the extent of full permissible FSI, then the User Authority shall pay full cost of construction + 5% of construction cost as establishment charges to the Implementing Public Authority.

- ii-c) The flats constructed under the free sale component shall be first offered to the Central Government, its statutory bodies, Central /State PSUs for purchase as staff quarters and if the Central Government or its statutory Bodies or Central /State PSUs do not indicate willingness to purchase the same within the prescribed time limit, such flats shall be sold in open market.

21.3.6 i) Notwithstanding anything contained in these regulations, no amount shall be charged towards Premium, Scrutiny Fee etc., for the projects proposed under this regulation.

21.3.7 For any staff quarters project under this regulations, a development agreement shall be executed between the User Authority and the Implementing Public Authority, which, inter alia, shall authorise the Implementing Authority to dispose of the flats constructed under the free sale component of the project, wherever applicable. Such development agreement shall contain the details regarding the modalities and conditions of transferring such quarters (whether free of cost or on payment/ receipt of certain amount by the User Authority) to the user authority and also conditions modalities of disposing of the flats under the free sale components by the Implementing Public Authority.

21.4 DEVELOPMENT / REDEVELOPMENT OF HOUSING SCHEMES OF MAHARASHTRAHOUSING AND AREA DEVELOPMENT AUTHORITY

Development / re-development of housing schemes of Maharashtra Housing and Area Development Authority shall be subject to the following provision.

- 1) The FSI for a new scheme of Low Cost Housing, implemented by MHADA departmentally on vacant lands for Economically Weaker Sections (EWS), Low Income Group (LIG) and Middle Income Group (MIG) categories shall be 2.50 on the gross plot area and at least 60% built-up area in such scheme shall be in the form of tenements under the EWS, LIG and MIG categories, as defined by the Government in Housing Department from time to time.

- 2) For redevelopment of existing housing schemes of MHADA, containing (i) EWS/LIG and/or (ii) MIG and/or (iii) HIG houses with carpet area less than the maximum carpet area prescribed for MIG, the total permissible FSI shall be 2.50 on the gross plot area (exclusive of the Fungible FSI).
- 2.1) Where redevelopment of buildings in existing housing schemes of MHADA is undertaken by the housing co-operative societies or the occupiers of such buildings or by the lessees of MHADA, the Rehabilitation Area Entitlement, Incentive FSI and sharing of balance FSI shall be as follows:-

A) Rehabilitation Area Entitlement:

- i) Under redevelopment of buildings in existing Housing Schemes of MHADA, the entitlement of rehabilitation area for an existing residential tenement shall be equal to sum total of -
- a) a basic entitlement equivalent to the carpet area of the existing tenement plus 35% thereof, subject to a minimum carpet area of 300 sq.ft. and
- b) an additional entitlement governed by the size of the plot under redevelopment, in accordance with the Table No. 21 below: -

Table No. 21	
Area of the Plot under Redevelopment	Additional Entitlement (As % of the Carpet Area of the Existing Tenement)
Upto 4000 sq.m.	Nil
Above 4000 sq.m. to 2 hect.	15%
Above 2 hect to 5 hect.	25%
Above 5 hect to 10 hect.	35%
Above 10 hect.	45%

Provided that the maximum entitlement of rehabilitation area shall in no case exceed the maximum limit of carpet area prescribed limit for MIG category by the Govt. as applicable on the date of approval of the redevelopment project. Provided further that the entitlement of rehabilitation area as admissible under this regulation shall be exclusive of the area of balcony.

- ii) Under redevelopment of buildings in existing Housing Schemes of MHADA, the entitlement of rehabilitation area of any existing commercial/amenity unit in the Residential Housing Scheme shall be equal to the carpet area of the existing unit plus 20% thereof.
- B) **Incentive FSI-** Incentive FSI admissible against the FSI required for rehabilitation, as calculated in (a) above, shall be based on the ratio (hereinafter referred to as Basic Ratio) of Land Rate (LR) in Rs./Sq.m. of the plot under redevelopment as per the Annual Statements of Rates (ASR) and Rate of Construction (RC)* in Rs./Sq.m. applicable to the area as per the ASR and shall be as given in the Table No.22 below:-

Table No. 22	
Basic Ratio (LR/RC)	Incentive (As % of Admissible Rehabilitation Area)
Above 6.00	40%
Above 4.00 and upto 6.00	50%
Above 2.00 and upto 4.00	60%
Upto 2.00	70%

Explanation:

* RC is the rate of construction in respect of R.C.C. Construction, as published by the Chief Controlling Revenue Authority & Inspector General of Registration, Maharashtra State in the Annual Statements of Rates.

Provided that the above incentive shall be subject to the availability of the FSI on the Plot under redevelopment and its distribution by MHADA.

Provided further that in case there are more than one land rate applicable to different parts of the plot under redevelopment, a weighted average of all applicable rates shall be taken for calculating the Average Land Rate and the Basic Ratio.

Provided further that the Land Rate (LR) and the Rate of Construction (RC) for calculation of the Basic Ratio shall be taken for the year in which the redevelopment project is approved by the authority competent to approve it.

C) Sharing of the Balance FSI: -

The FSI remaining in balance after providing for the rehabilitation and the incentive components, calculated as per (a) and (b) above respectively, shall be shared between the Co-operative Housing Society and MHADA in the form of built-up area, as given in Table No. 23 below and the share of MHADA shall be handed over to MHADA free of cost.

Table No. 23		
Basic Ratio (LR/CR)	Sharing of balance FSI	
	Share of Co-operative Society	Share of MHADA
Above 6.00	30%	70%
Above 4.00 and upto 6.00	35%	65%
Above 2.00 and upto 4.00	40%	60%
Upto 2.00	45%	55%

2.2) Where redevelopment of buildings in the existing Housing Schemes of MHADA is undertaken by MHADA or jointly by the MHADA alongwith the housing societies or the occupiers of such building or by the lessees of MHADA, the Rehabilitation Area Entitlement, incentive FSI and sharing of balance FSI shall be as follows:

A) Rehabilitation Area Entitlement: The Rehabilitation Area Entitlement shall be increased by 10% of the existing carpet area, over and above the Rehabilitation Area Entitlement calculated in (A) of 2.1 above, subject to the maximum of the size of MIG

prescribed by the Government in the Housing Department.

B) Incentive FSI: Incentive FSI shall be the same as in (B) of 2.1 above.

C) Sharing of the balance FSI: Sharing of the balance FSI shall be the same as in 2.1.

- 3) For the purpose of calculating the FSI, the entire area of the layout including Regional/Development Plan roads and internal roads but excluding the land under the reservation of public amenities shall be considered. Sub-division of plots shall be permissible on the basis of the compulsory open spaces as in these Regulations. For low cost housing schemes of MHADA for EWS/LIG categories, the prevailing Regulations of the DCPR shall apply.

Provided that there shall be no restriction on the utilization of the FSI permissible under this Regulation except for the restrictions under any law, rule or regulation.

- 4) For the purpose of this Regulation the carpet areas for EWS, LIG or MIG tenements shall be as determined by the Government from time to time.
- 5) a) For providing the requisite infrastructure for the increased population, an infrastructure charge at the rate of 7% of the Land Rate as per the ASR of the year of approval of the redevelopment project shall be chargeable for the extra FSI (excluding the fungible FSI) granted over and above the normal FSI admissible for the redevelopment schemes. 50% of the Infrastructure Charge levied and collected by MHADA shall be transferred to the PMRDA for developing necessary off site infrastructure.

b) No premium shall be charged for the FSI admissible as per the prevailing regulations

- (i) Construction of EWS/LIG and MIG tenements by MHADA on a vacant plot, or
- (ii) in a redevelopment project for the construction of EWS/LIG and MIG tenements towards the share of MHADA, or
- (iii) for rehabilitation component of a redevelopment project.

- 6) Notwithstanding anything contained in these Regulations, the relaxation incorporated in the prevailing Regulation shall apply to the Housing Schemes under this Regulation for tenements under EWS/LIG and MIG categories. However, the front open space shall not be less than 3.6m.

- 7) a) In any Redevelopment Scheme where the Co-operative Housing Society Developer appointed by the Co-operative Housing Society has obtained No Objection Certificate from the MHADA, thereby sanctioning additional balance FSI with the consent of 70% of its members and where such NOC holder has made provision for alternative accommodation in the proposed building (including transit accommodation), then it shall be obligatory for all the occupiers / members to participate in the Redevelopment Scheme and vacate the existing tenements for the purpose of redevelopment. In case of failure to vacate the existing tenements, the provisions of section 9A of the MHAD Act mutatis mutandis shall apply for the purpose of getting the tenements vacated from the not co-operative members.

b) For redevelopment of buildings in any existing Housing Scheme of MHADA under clause 2.2 hereinabove, by MHADA, the consent of the Co-operative Housing Society in the form of a valid Resolution as per the Co-operative Societies Act, 1960 will be sufficient. In respect of members not co-operating as per approval of the redevelopment project, action under section 95(A) of the Maharashtra Housing and Area Development Act, 1976 may be taken by MHADA.

- 8) A corpus fund, as may be decided by MHADA, shall be created by the Developer which shall remain with the Co-operative Housing Societies for the maintenance of the new buildings under the Rehabilitation Component.

21.5 REDEVELOPMENT OF EXISTING BUILDINGS BELONGING TO EWS / LIG GROUPS.

Reconstruction / Redevelopment of existing buildings of EWS / LIG undertaken by landlord and / or co-operative housing societies and / or occupiers having carpet area of all tenements less than the EWS / LIG norms prescribed by MHADA, which existed prior to these regulations which has ceased to exist in consequence of accidental fire / natural collapse or demolition for the reasons of the same having been declared unsafe by or under a lawful order of the Metropolitan Commissioner, shall be allowed subject to following conditions:

- 1) FSI to be allowed for such redevelopment proposal shall be base FSI permissible under these regulations or the FSI consumed by the existing authorized building whichever is more. In addition to this minimum 15 sq. m. built up area per Residential flat shall be allowed as incentive to the owner excluding bungalow.
- 2) All the occupants of the old building shall be re-accommodated in the redeveloped building.
- 3) In case of fire gutted buildings, the conditions of more than 30 years age of buildings shall not be made applicable, provided the structural stability certificate from nearest Govt. Engineering College shall be necessary.
- 4) The Committee comprises of the Metropolitan Commissioner, Chief Engineer, PMRDA, Chief Fire Officer, PMRDA and the Head of department structural Engineering of Government Engineering College shall be set-up to decide whether the building is —dangerous or dilapidated or Unsafe.
- 5) Reconstruction of the building on the plots shall conform to the provisions of the sanctioned Regional/Development Plan and sanctioned Development Control and Promotion Regulations.

21.6 REDEVELOPMENT OF OLD DILAPIDATED/DANGEROUS BUILDINGS

Reconstruction / Redevelopment in whole or in part of any tenanted building which existed prior to these regulations which has ceased to exist in consequence of accidental fire / natural collapse or demolition for the reasons of the same having been declared dangerous or dilapidated or Unsafe by or under a lawful order of the Metropolitan Commissioner, shall be allowed subject to following conditions:

- a) Redevelopment of tenanted building undertaken by landlord and / or co-operative housing societies of landlord and / or occupiers shall be allowed, with an FSI equivalent to the Rehab Area plus 50% incentive FSI of the rehab area. Provided that Rehab Area will be the authorisedly utilised Area or 27.87 sq.mt. per tenement whichever is more.

However as per the road width if the potential of the Plot is more than what is mention above, then the balance potential available on plot after deducting rehab and incentive FSI may be allowed to be utilized to that extent by the way of TDR or Additional FSI in 50- 50 proportion subject to limitation of additional FSI as mentioned in Table No. 18, if any.

- b) All the certified tenants of the old building shall be re-accommodated in the redeveloped building. Each **tenant** shall be rehabilitated and given free of cost the carpet area occupied by him for residential purpose in the old building subject to the minimum carpet area of **27.87sq. mt.** or existing carpet area whichever is more **subject to** maximum carpet area upto 70 sq.mt. (753 sqft.) . In case of non-residential occupier the area to be given in the reconstructed building **shall** be equivalent to the area occupied in the old building.

Provided that if the carpet area under Residential use exceeds 70 sq.mt., the cost of construction **for Area exceeding 70 sq.mt.** shall be paid by tenant / occupant to the developer. The cost of construction shall be as per the ready reckoner rate of that year. The carpet area exceeding 70 sq.mt. shall be considered for rehab FSI but shall not be consider for incentive FSI.

- c) In case of fire gutted buildings the conditions of more than 30 years age of buildings shall not be made applicable, provided the structural stability certificate from nearest Govt. Engineering College shall be necessary.
- d) The Committee comprises of M e t r o p o l i t a n Commissioner, Chief Engineer, PMRDA, Metropolitan Planner, PMRDA, Chief Fire Officer, PMRDA and the Head of department structural Engineering of Government Engineering College shall be set-up to decide whether the building is —dangerous or dilapidated or unsafe□.

Note-

1. For the purpose of deciding authenticity of the structure if the approved plans of existing structure are not available, the Metropolitan Commissioner shall consider other evidences such as Assessment Record or City Survey Record or Sanad.
2. In case where there are number of buildings. on plot, in such cases, equivalent land component of the buildings which is declared unsafe shall be worked out and incentive FSI shall be based on such land component.
3. Reconstruction of the building on the plot shall conform to the provisions of the sanctioned Regional/Development Plan and sanctioned Development Control and Promotion Regulations.
4. The new building may be permitted to be reconstructed in pursuance of an agreement to be executed on stamp paper by atleast 70 percent of the landlord / occupants in the original building, within the meaning of the Bombay Rents, Hotel and Lodging House Rents Control Act, 1947 or Apartment Act and its related provision and in such agreement provision for accommodation for all occupants in the new building on agreed terms shall be made and a copy of such agreement shall be deposited with the PMRDA before commencement or undertaking reconstruction of the new buildings.
The carpet area of part or parts of the new building intended to be used as non-residential use shall not exceed the carpet area of part or parts of the original building so used
5. No new tenancy shall be created
6. An amount as may be decided by the Government shall be paid by the Owner /Developer / Society as additional Development Cess for the built up area over and above the Base FSI. A corpus fund as decided by the Metropolitan Commissioner is to be created by the Developer which will take care of the maintenance of the building for a period of 10 years.

21.7 REDEVELOPMENT OF EXISTING BUILDINGS

Reconstruction / Redevelopment schemes undertaken by the PMRDA / Owners for the existing residential development.

The FSI to be allowed for such proposal shall be FSI permissible under these regulation no. 20.3 wherever applicable or the FSI consumed by the existing authorized building whichever is more.

21.8 TRANSIT ORIENTED DEVELOPMENT (TOD)

21.8.1 Definitions

- (i) **TOD zone:** - It is the area along/around the proposed MRTS/Metro corridor as will be delineated by PMRDA with approval of the State Government.
- (ii) **Base permissible FSI:** - It is the FSI that is otherwise permissible on any land with respect to zone shown as per the sanctioned Regional/Development Plan and the relevant provision of the Principal DCR excluding the TDR and the premium FSI, redevelopment incentive FSI that can be received.
- (iii) **Gross plot area:** - Gross Plot Area means total area of land after deducting area under reservation or deemed reservation like amenity space if any, area under R.P./D.P. Road and Road widening.
- (iv) **Principal DCPR:** - Principal DCPR means these DC&P Regulations excluding the provisions regarding TOD zone.

21.8.2 Date of coming into force :- The date of coming into force of these regulations shall be the date as notified by the Government.

21.8.3 Maximum Permissible FSI :- The maximum permissible total FSI in TOD zone shall be 4.00 including the base permissible FSI, subject to condition that, the additional FSI over and above the base permissible FSI shall be allowed within the overall limit of maximum permissible FSI, as given in the Table below-

Sr. No.	Road width in m.	Min. Plot Area in sq.m.	Maximum Permissible FSI
1	2	3	4
1	9 m. and up to 12 m.	Below 1000	2.00
2	12 m. and up to 18 m.	1000 or above	2.50
3	18 m. and up to 24 m.	2000 or above	3.00
4	24 m. and up to 30 m.	3000 or above	3.50
5	30 m. and above	4000 or above	4.00

Explanation: -

- 1) The maximum permissible FSI as per the above Table shall be determined by satisfaction of both the criteria's viz. Minimum Road width as well as plot area, simultaneously. However, in case, both these criteria's are not satisfied simultaneously, the maximum permissible FSI shall be the minimum of that permissible against each of these two criteria's, as illustrated below:

Illustrations: -**Utilization of
FSI**

Plot Area in sqm	Road width					
	Less than 9mt.	9 m. and up to 12 m	12 m. and up to 18 m	18 m. and up to 24 m.	24 m. and up to 30 m.	30 m. and above
Below 1000	Principal DCPR	2	2	2	2	2
1000 to below 2000	Principal DCPR	2	2.5	2.5	2.5	2.5
2000 to below 3000	Principal DCPR	2	2.5	3.0	3.0	3.0
3000 to below 4000	Principal DCPR	2	2.5	3.0	3.5	3.5
4000 or above	Principal DCPR	2	2.5	3.0	3.5	4.0

21.8.3.1 Premium to be Paid - Additional FSI over and above base permissible FSI of respective land use zones as per principal DCPR, may be permitted on the payment of premium equivalent as would be decided by Government from time to time.

21.8.3.2 Integrated Mobility Plan:- There shall be an Integrated Mobility Plan envisaging inter-linkages between different modes of mass transport, parking management, traffic management and pedestrianisation.

21.8.3.3 The maximum permissible FSI as given in Table under regulation 21.8.3 shall be calculated on the gross plot area.

21.8.3.4 In case of plot / plots falling partly within the TOD zone, the FSI permissible shall be as follows, provided that the total area of the plot (plot falling within TOD zone plus plot falling outside TOD zone) shall be as prescribed in the table in regulation no. 21.8.3 :-

1. Where 50% or more area of such plot / plots falls within TOD zone, these regulations including FSI shall apply to the total area of such plot / plots.
2. Where less than 50% area of such plot / plots falls within TOD zone, these regulations including FSI shall be applicable to the part of plot / plots falling within TOD zone, whereas for the part of plot / plots falling outside TOD zone, these regulations except provisions regarding FSI shall be applicable. The FSI permissible for the part falling outside TOD zone shall be as per Principal Development Control and Promotion Regulations.

Notwithstanding anything contained in any other provision of this DCPR the Parking, Double height terraces up to 20% and 15% balconies not enclosed, Stair cases, Lift wells with machine rooms, Refuge areas, Voids, Service Floor & Entrance lobbies of the building in TOD zone shall be free of FSI.

Notwithstanding anything contained in any other provisions of these regulations, TDR shall not be allowed to be received on the plots within TOD zone, irrespective of its location in congested area / non congested area as per the Regional/Development Plan of PMRDA.

21.8.4 Tenement Size

For any development or redevelopment within TOD zone, size of tenement shall be minimum 25 sqm and maximum 120 sqm of built-up area and out of total proposed tenements, the tenements equivalent to at least 50% of total FSI shall be of a size equal to or less than 60 sqm. These tenements shall not be allowed to be clubbed/amalgamated in any case.

21.8.5 Permissible mixed use in TOD zone:

Mixed use in the form of residential and commercial may be permissible on the residential plot in TOD zone fronting on the road width of 12 mt. and above.

21.8.6 Other provisions regarding marginal open spaces shall be governed by the proposed height of structure, as given in the provisions 21.8.7 below and should conform to the Maharashtra Fire Prevention and Life Safety Measures Act, 2006 (Maharashtra Act no. III of 2007) as amended from time to time. No building permission shall be issued without NOC of the Chief Fire Officer, PMRDA. Other regulations regarding room sizes, apertures for light and ventilation shall be as per the principal DCPR in force.

21.8.7 Marginal Spaces

Sr. No.	Building Height	Side and Rear Margins	Remark
a	15.0 mt and below	H/2-4	Minimum 3.0 mt. for Residential minimum 4.5 mt. for Commercial and Minimum 6.0 m. for Special Buildings.
b	Above 15.0 mt. and upto 24.0 mt.	H/4	
c	24.0 mt and above	H/5 subject to Maximum 12.0 mt.	

Note- However if Developer / Owner provides more than 12.00 mt. side and rear margins, it shall be permissible.

- 21.8.7.1** No projections shall be allowed in marginal spaces so that minimum 6 mt. marginal spaces remain free from all encumbrances for the movement of fire tenders. In case if ramp is necessary from accessibility, such ramp may be allowed after living 6 mt. clear margin.
- 21.8.7.2** For calculation of marginal distances the height of the parking floors (Maximum two floors above the Ground Level) shall not be taken in account, However height of such parking floors will be counted towards the total height of the building for deciding the building as high rise building and for civil Aviation purpose.
- 21.8.7.3** Car lift / mechanical parking shall be permissible, as per Principal DCPR as amended from time to time.

21.8.8 Parking

Parking in the TOD zone shall be provided as per the table given below:

Sr. No.	Occupancy	One parking space for every	Transit Oriented Development Influence Zone		
			Car	Scooter / Motorcycle	Cycle
1	Residential	For 4 units having carpet area From 25 and upto 40 sq.mt.	0	1	2
		For 2 units above 40 and upto 60 sq.mt.	1	1	2
		For every unit above 60 and upto 80 sq.mt.	1	2	2
		For every unit above 80 sq.mt	1	1	1
2	Govt. & Semi Govt. Private business buildings	100 sq.mt carpet area or fraction thereof	1	2	2

Note: i) Parking spaces for differently – abled persons shall be provided as per Indian Road Congress Code No. IRC 103:2012 in each new construction / development / re-development in the TOD zone.

ii) No on street parking shall be permissible, unless specifically allowed in the integrated mobility plan report.

21.8.8.1 Incentive for providing Public Parking in the area falling within the radius of 200 mt. from the Metro/MRTS Station.

If the owner / developer of the plot falling within the radius of 200 mt. from the Metro Station/MRTS, is willing to provide Public Parking space over and above the parking spaces required as per the table given in regulation No.21.8.8 of these regulations, the same shall be allowed and in that case the premium to be paid by such developer / owner as per regulation No.23.8.3.1 shall be reduced by the amount equal to the premium worked out for 25% of the area earmarked for such additional Public Parking space, subject to following conditions:-

- Such parking area shall be in the built-up form and shall be handed over to PMRDA free of cost before granting the Occupation Certificate to the project. The PMRDA should enter into an agreement with owner / developer for such parking space at the time of granting Commencement Certificate to the project. Such Public Parking area shall be clearly shown on the proposed building plan / layout and a condition to above effect shall be incorporated in the Commencement Certificate.
- The parking area shall have independent access from major road adjacent to the plot and with proper entry and exits.
- The parking area to be made available at individual site shall be at minimum 100 sq.mt. at one place either at Ground floor / Stilt floor or first floor.
- The maximum parking area that can be provided shall be decided by the Metropolitan Commissioner, PMRDA, as the case may be, on considering the location of such site and the parking requirement.
- A board showing the location of such public parking space should be displayed at suitable places by the PMRDA.

6. Area covered under such parking shall not be counted towards FSI consumption.
7. Concerned land owner / developer / society / public company shall not be allowed to operate the public parking.
8. The proposed development shall be further subject to such conditions as may be decided by the Metropolitan Commissioner.

- 21.8.9** In case of metro rail, development or redevelopment, proposed by the Authority / individual applicant / any other Planning Authority, from the edge of the Metro Rail, within 20 mt. distance from the Metro Rail, on its either side, the concerned Planning Authority i.e. the PMRDA before granting such permission for development / redevelopment shall seek prior NOC from the concerned Metro Railway Authority as required under the Metro Railways (Construction of Works) Act, 1978/PMRDA from the point of view of safety of the Metro Railway and such other related matters.
- 21.8.10** In case of any conflict between these Regulations and any other Regulation/s of the DCPR, these Regulations shall prevail for the TOD zone.
- 21.8.11** No Compound wall / fencing shall be permissible on the boundary of plot fronting on road and 50% front marginal distance (subject to minimum of 3.0 mt.) shall be kept accessible and to be used as foot paths, for pedestrians. However, it shall be permissible for the applicant to construct / erect fencing, on the boundary, after leaving the space for pedestrians as specified above.
However, for the plots situated on 9mt. and 12mt. wide Roads having 100% residential use therefore above rule shall not be made applicable.
- 21.8.12** Large wholesale stores, car dealer showrooms, warehouses/storages, auto service centres, Garages etc. shall not be permissible in TOD zone.
- 21.8.13** Provision of Inclusive housing shall not be applicable in TOD zone.
- 21.8.14** For Gunthewari development regularized under the provisions of Maharashtra Gunthewari Development Act, 2001 and falling in TOD zone, seeking provisions for redevelopment, these regulations shall apply.
- 21.8.15** The width of passage shall be minimum 1.5 mt. for residential use & 2.0 mt. for commercial use.

21.9 DEVELOPMENT OF HOUSING FOR EWS/LIG/PMAY

If the owner constructs the housing for EWS / LIG / PMAY in the form of tenements of size upto 60 sq. mt. carpet area on his plot, then he shall be exempted from requirement of premium as mentioned in regulation No. 20.3 Table No. 18 subject to following conditions.

- i) Out of the total tenements, at least 40% tenements shall be of area not more than 30sq.mt.
- ii) Only one tenement should be sold to a family. Adjoining tenement should not be sold to a close relative of such tenement owner. Affidavit to that effect shall be obtained from the land owner / developer and purchaser.
- iii) The size of tenement of 30 or 60 sq. mt. shall be exclusive of common areas like staircases, passages etc. and balcony, double height terraces.
- iv) Concessions in marginal spaces may be allowed by the Metropolitan Commissioner.

21.10 REGULATIONS FOR DEVELOPMENT OF INFORMATION TECHNOLOGY ESTABLISHMENT

Development of Information Technology Establishments shall be regulated as per the Information Technology & Information Technology Enabled Services (IT/ITES) Policy 2015 as declared by Industries Department vide Government Resolution No. ITP 2013/CR-265/IND-2 dated 25/08/2015, along with the special regulations sanctioned by the Government vide notification No. TPB 4316/CR-167/2016/(3)/UD-11/dated 15th July, 2016 and amended time to time which are mentioned below:

- 1) The Metropolitan Commissioner may permit additional FSI upto 200 % over and above the basic permissible F.S.I. to all registered Public and Private IT/ITES Parks/AVGC Parks /IT SEZs or IT Parks in SEZs / Stand-alone IT/ITES units in public IT Park (including IT/ITES units located in Residential / Industrial/No Development/ Green/Agriculture Zone or any other land-use zone in which such users are permissible), which have been approved by the Directorate of Industries, proposed to be set up or already set up under present / previous IT/ITES policies, (hereinafter referred to as the "said unit") by charging premium of 30% of the land rate for the said land as prescribed in Annual Statement of Rates for the relevant year of granting such additional F.S.I. for PMRDA

In case of the Navi Mumbai Notified Area, the CIDCO as land owner may recover lease premium for additional F.S.I. if applicable under land disposal policy of CIDCO.

Provided that additional FSI above 100% and upto 200% shall be permissible only on plots having an access road of minimum 18 meters width.

Provided further that, the premium so collected shall be shared between the Planning Authority and the Government in the proportion of 50 : 50. The share of the Government shall be paid to the concerned Branch office of the Town Planning Department. (Explanation: - Premium charges shall be calculated on the value of lands under such zones, determined by considering the land rates of the said land as prescribed in Annual Statement of Rates (ASR). These charges shall be paid at the time of permitting additional F.S.I. by considering the ASR for the relevant year without applying the guidelines)

- 2) No premium shall be chargeable in PMR areas, if they are covered under No Industry Districts and Naxalism affected areas of the State (as defined in the " Package Scheme of Incentives-2013" of the Industries, Energy & Labour Department of the State).
- 3) The total maximum permissible F.S.I. shall not exceed limit of 3.00.
- 4) Maximum 20% of total proposed Built-up area (excluding parking area) inclusive of such additional F.S.I. may be permitted for support services in IT Parks remaining built-up area shall be utilized for IT/ITES.
- 5) New said unit shall allocate at least 2% of the total proposed built-up area, for providing incubation facilities for new units. This area would be treated as a part of the Park to be used for IT activities and eligible for additional FSI benefits accordingly.
- 6) Premium to be received by the Planning Authority as per provisions in this regulation shall be deposited in a separate fund viz. "Critical Infrastructure Fund for IT/ITES Industries" and this fund shall be utilized only for creation of Critical Infrastructure for IT/ITES Industries;

Provided that in the event, the developer come forward for providing such off site infrastructure at his own cost, instead of paying premium as prescribed above, then the Planning Authority may determine the estimated cost of the work by using rates prescribed in District Schedule of Rates (DSR) of the relevant year, in which order for commencement of such work is issued. The Planning Authority shall also prescribe the standards for the work. After completion of the works, the Planning Authority shall verify and satisfy itself that the same is developed as per prescribed standards and thereafter, by deducting the cost of works, the balance amount of premium shall be recovered from such developer before issuing Occupancy Certificate.

Provided that, in case the cost of work is more than the premium to be recovered, such additional cost to be borne by such developer.

- 7) Permission for erecting towers and antenna up to height permitted by the Civil Aviation Department shall be granted by the Commissioner as per the procedure followed for development permission or otherwise as may be decided by the Government.
- 8) While developing site for IT/ITES with additional FSI, support services as defined in the IT Policy 2015, shall be allowed.
- 9) The sanctioned existing regulations in respect of I.T. Establishments, are proposed to be replaced suitably and for the Planning Authorities, which have no provisions in respect of I.T. Establishments, these regulations shall be proposed to be inserted as new regulations.
- 10) Notwithstanding anything contained in the Development Control Regulations of Planning Authorities, no amenity space is required to be left for development of plot/land upto 2.00 Hect. for IT/ITES.
- 11) Notwithstanding anything mentioned in these Regulations, special provisions mentioned in the existing Regulations of respective Planning Authority, which areas are not covered under these regulations shall continue to prevail unless otherwise specified.
- 12) The Directorate of industries will develop a web portal on which the developer of every IT park will be bound to provide / update detailed information about names of the units in the park, utilization of built-up area and activities being carried out, manpower employed in the It Park for IT/ITES and support services on yearly basis.

If a private IT park has availed additional FSI as per the provisions of IT/ITES policy and subsequently it is found that the built-up space in the park is being used for non IT/ITES / commercial activities / any other activity not permitted as per the IT/ITES policy under which the said park was approved, a penal action as below will be taken, the payment shall be shared between the concerned Planning Authority and the Government in the ratio of 3:1.

- a) The misuse shall be ascertained by physical site verification of the said private IT park by a team of officers from the Directorate of industries and the Planning Authority which has approved the building plans of the said private IT park.
- b) A per day penalty equal to 0.3% of the prevailing ready reckoner value of the built-up area that has been found to be used for non- IT/ITES activities.
- c) The penalty will be recovered from the date of commencement of unauthorized use till the day non IT use continues.

After payment of the penalty to the concerned Planning Authority which has sanctioned the building plans of the concerned private IT park, the said private IT Park will restore the use of premises to the original purpose for which LOI/ Registration was granted.

If the private IT Park fails to pay penalty and / or restore the use to its original intended use, the concerned Planning Authority will take suitable action under the Maharashtra Regional and Town Planning Act 1966, against the erring private IT Park under intimation to the Directorate of Industries. This provision will also be applicable to existing IT Parks.

21.11 REGULATION FOR DEVELOPMENT OF BIOTECHNOLOGY PARKS:

A. DEFINITION-

The Biotechnology Units/ Parks shall mean Biotechnology units/ parks which are certified by the Development Commissioner (Industries) or any officer authorised by him in his behalf. The Biotechnology Park and unit/units outside park shall have minimum land area of 2 acres or 20000 sq.ft. built up area. The said requirement of 20000 sq.ft. shall be as per normal permissible FSI and without considering permissible additional FSI/ TDR/ Free of FSI area.

B. BIOTECHNOLOGY UNITS/ PARKS TO BE ALLOWED IN INDUSTRIAL ZONE-

Biotechnology Units/Parks shall be permitted in Industrial Zone on all plots fronting on roads having width more than 12 meter.

C. BIOTECHNOLOGY UNITS/PARK TO BE ALLOWED IN NO DEVELOPMENT ZONE EARMARKED IN THE REGIONAL/DEVELOPMENT PLAN.

Biotechnology Units/Parks shall be permitted in No Development Zone subject to following conditions: -

- i) Maximum FSI limit shall be 0.20 and as far as possible the development shall be at one place of the total land.
- ii) The ground coverage shall not exceed 10% of the area of the plot.
- iii) Tree plantation shall be done at the rate of 500 Trees/Ha on the remaining land excluding the built up area and the surrounding open space/utility space.
- iv) The maximum height of buildings shall not exceed 24 mt.
- v) Essential residential development for the staff/ officer's accommodation shall be permitted upto the extent of 33% of the permissible built up area.
- vi) These users shall be permitted in No Development Zone, within a distance of 3 km. from the adjoining developable zone.
- vii) Development in plots affected by CRZ area shall be permissible subject to the notification issued by MOEF regarding CRZ.

D. ADDITIONAL FSI TO BIOTECHNOLOGY UNITS / PARK

Subject to approval by Director of Industries, the Commissioner/ Commissioner/ Competent Planning Authority or as the case may permit the floor space indices specified in these regulations to be exceeded to the extent of 100% over and above the permissible FSI (including for Biotechnology Units/Park located in No Development Zone proposed in the Regional/Development Plan) for biotechnology units/parks subject to following conditions:-

- i) Out of total built up area minimum 90% shall be used for Biotechnology purpose and maximum 10% (by deducting parking space) shall be used for ancillary users such as specified in the Govt. Resolution of Industry, Energy and Labour Department. No. BTP 2008/CR-1608/Ind-2, dated 10/2/09.
- ii) Additional FSI to Biotechnology units would be available to Biotechnology Parks duly approved by the Directorate of Industries and after observance of all the regulation of environment.
- iii) Parking spaces, as per the provision of Development Control Regulation shall be provided subject to minimum requirement of one parking space per 100 sq.mt. built up area.

- iv) The additional FSI shall be granted upon payment of premium which shall be paid in the manner as may be determined by the Government. Such premium shall be recovered at the rate of 25% of the present day market value of the land under reference as indicated in the Ready Reckoner.
- v) 25% of the total premium shall be paid to the Govt. and remaining 75% amount shall be paid to the said Authority.
- vi) The premium so collected by the Planning Authorities shall be primarily used for development of offsite infrastructure required for the Biotechnology Parks.
- vii) In the event, the developer comes forward for provision of such off site infrastructure at his own cost, then the said Planning Authority shall determine the estimated cost of the works and shall also prescribe the standards for the work. After completion of the works the said Planning Authority shall verify as to whether the same is as per prescribed standards and thereafter, by deducting the cost of works, the balance amount of premium shall be recovered by the said Planning Authority.
- viii) No condonation in the required open spaces, parking and other requirement prescribed in the regulations shall be allowed in case of additional FSI.
- ix) Development of biotechnology park shall be done as per the guidelines issued by Industries Department vide the said resolution.

21.12 DEVELOPMENT OF PUBLIC TOILET

The owner if constructs public toilet in addition to the number of toilets required for his proposed development at the location required and as prescribed by the Metropolitan Commissioner, preferably on ground floor having separate access, he may be granted additional FSI equal to the built up area of such additional toilets. Provided such toilet shall be maintained by the owner at his own cost to the satisfaction of Commissioner.

PART – VI

FIRE PROTECTION REQUIREMENTS

22.1 General: All buildings shall be planned, designed and constructed to ensure fire safety and this shall be done in accordance with Part IV of Fire Protection of National Building Code of India and Maharashtra Fire Prevention and Life Safety Measures Act, 2006. as amended from time to time, and Part IV of Fire Protection of National Building Code of India (for the provisions which are not covered in these regulations.) In case of special buildings, the building schemes shall also be cleared by the Fire Officer, Fire Brigade Department of the PMRDA.

22.2 Construction materials

All materials of constructions in load bearing elements, stairways and corridors and facades shall be non-combustible.

The interior finish materials shall not have a flame spread ability rating exceeding Class I (see 3.4.15.2 of Part 4 of National Building Code)

The internal walls or staircase shall be of brick or reinforced concrete with a minimum of 2 h. fire rating.

The staircase shall be ventilated to the atmosphere at each landing and a vent at the top; the vent openings shall be of 0.5sq.m in the external wall and the top. If the staircase cannot be ventilated, because of location or other reasons, a positive pressure 50 Pa shall be maintained inside. The mechanism for pressurizing the staircase shall operate automatically with the fire alarm. The roof of the shaft shall be 1 m. above the surrounding roof. Glazing or glass bricks, if used in staircase, shall have fire resistance rating of minimum 2 h.

22.3 Lifts

General requirements of lifts shall be as follows:

- a) Walls of lift enclosures shall have a fire rating of 2 h; lifts shall have a vent at the top of area not less than 0.2 sq.m.
- b) Lift motor room shall be located preferably on top of the shaft and separated from the shaft by the floor of the room.
- c) Landing doors in lift enclosures shall have a fire resistance of not less than 1 h.
- d) The number of lifts in one row for a lift bank shall not exceed 4 and the total number of lifts in the bank (of two rows) shall not exceed 8. A wall of 2 h. fire rating shall separate individual shafts in a bank.
- e) Lift car door shall have a fire resistance rating of half an hour.
- f) Collapsible gates shall not be permitted for lifts and shall have solid doors with fire resistance of at least 1 h.
- g) If the lift shaft and lobby is in the core of the building, a positive pressure between 25 and 30 Pa shall be maintained in the lobby and a positive pressure of 50 Pa shall be maintained in the lift shaft. The mechanism for pressurization shall act automatically with the fire alarm; it shall be possible to operate this mechanically also.
- h) Exit from the lift lobby, if located in the core of the building, shall be through a self closing smoke stop door of half an hour fire resistance.
- i) Lifts shall not normally communicate with the basement; if, however, lifts are in

communication, the lift lobby of the basements shall be pressurized as in (g), with self-closing door as in (h)

- j) Grounding switch(es), at ground floor level, shall be provided on all the lifts to enable the fire service to ground the lifts.
- k) Telephone or other communication facilities shall be provided in lift cars for building of 30 m. in height and above. Communication system for lifts shall be connected to fire control room for the building.
- l) Suitable arrangements such as providing slope in the floor of lift lobby, shall be made to prevent water used during fire-fighting, etc., at any landing from entering the liftshafts.
- m) A sign shall be posted and maintained on every floor at or near the lift indicating that in case of fire, occupants shall use the stairs unless instructed otherwise. The sign shall also contain a plan for each floor showing the locations of the stairways. Alternate source of power supply shall be provided for all the lifts through a manually operated changeover switch.
- n) **Fire Lifts** -Following details shall apply for a fire lift :
 - i) To enable fire services personnel to reach the upper floors with the minimum delay, one fire lift per 1200 sq.m. of floor area shall be provided and shall be available for the exclusive use of the firemen in an emergency.
 - ii) The lift shall have a floor area of not less than 1.4 sq.m. It shall have loading capacity of not less than 545 kg (8 persons lift) with automatic closing doors of minimum 0.8 m. width.
 - iii) The electric supply shall be on a separate service from electric supply mains in a building and the cables run in a route safe from fire, that is, within the lift shaft. Lights and fans in the elevators having wooden paneling or sheet steel construction shall be operated on 24 V supply.
 - iv) Fire-fighting lift should be provided with a ceiling hatch for use in case of emergency, so that when the car gets stuck up, it shall be easily openable.
 - v) In case of failure of normal electric supply, it shall automatically trip over to alternate supply. For apartment houses, this changeover of supply could be done through manually operated changeover switch. Alternatively, the lift shall be so wired that in case of power failure, it comes down at the ground level and comes to stand-still with door open.
 - vi) The operation of a fire lift is by a simple toggle or two-button switch situated in a glass-fronted box adjacent to the lift at the entrance level. When the switch is on, landing call-points will become inoperative and the lift will be on car control only or on a priority control device. When the switch is off, the lift will return to normal working. This lift can be used by the occupants in normal times.
 - vii) The words 'Fire Lift' shall be conspicuously displayed in fluorescent paint on the lift landing doors at each floor level.
 - viii) The speed of the fire lift shall be such that it can reach the top floor from ground level within 1 minute.

22.4 Basements -

- i) Each basement shall be separately ventilated. Vents with cross-sectional area (aggregate) not less than 2.5% of the floor area spread evenly round the perimeter of the basement shall be provided in the form of grills or breakable stall board lights or pavement lights or by way of shafts.

Alternatively, a system of air inlets shall be provided at basement floor level and smoke outlets at basement ceiling level. Inlets and extracts may be terminated at ground level with stall board or pavement lights as before, but ducts to convey fresh air to the basement floor level have to be laid. Stall board and pavement lights should be in positions easily accessible to the fire brigade and clearly marked 'SMOKE OUTLET' or 'AIR INLET' with an indication of area served at or near the opening.

ii) The staircase of basements shall be of enclosed type having fire resistance of not less than 2 h and shall be situated at the periphery of the basement to be entered at ground level only from the open air and in such positions that smoke from any fire in the basement shall not obstruct any exit serving the ground and upper storeys of the building and shall communicate with basement through a lobby provided with fire resisting self-closing doors of 1 h resistance. For travel distance, if the travel distance exceeds as given therein, additional staircases shall be provided at proper places.

iii) In multi-storey basements, intake ducts may serve all basement levels, but each basement levels and basement compartment shall have separate smoke outlet duct or ducts. Ducts so provided shall have the same fire resistance rating as the compartment itself. Fire rating may be taken as the required smoke extraction time for smoke extraction ducts.

iv) Mechanical extractors for smoke venting system from lower basement levels shall also be provided. The system shall be of such design as to operate on actuation of heat / smoke sensitive detectors or sprinklers, if installed, and shall have a considerably superior performance compared to the standard units. It shall also have an arrangement to start it manually.

v) Mechanical extractors shall have an internal locking arrangement, so that extractors shall continue to operate and supply fans shall stop automatically with the actuation of fire detectors.

vi) Mechanical extractors shall be designated to permit 30 air changes per hour in case of fire or distress call. However, for normal operation, air changes schedule shall be as given in Part 8, Building Services, Section 3, Air-conditioning, Heating and Mechanical Ventilation of National Building Code.

vii) Mechanical extractors shall have an alternative source of supply.

viii) Ventilating ducts shall be integrated with the structure and made out of brick masonry or reinforced cement concrete as far as possible and when this duct crosses the transformer area or electrical switchboard, fire dampers shall be provided.

ix) Use of basements for kitchens working on gas fuel shall not be permitted, unless air conditioned. The basement shall not be permitted below the ward block of a hospital/nursing home unless it is fully sprinkled. Building services such as electrical sub-stations, boiler rooms in basements shall comply with the provisions of the Indian Electricity Act / Rules.

x) If cut-outs are provided from basements to the upper floors or to the atmospheres, all sides cut-out openings in the basements shall be protected by sprinkler head at close spacing so as to form a water curtain in the event of a fire.

xi) Openable windows on external wall shall be fitted with such locks that can be opened by a fireman's axe.

xii) All floors shall be compartmented with area not exceeding 750 sq.m. by a separation wall with 2 h fire rating, for floors with sprinklers the area may be increased by 50 percent. In long building, the fire separation walls shall be at distances not exceeding 40 m. For departmental stores, shopping centres and basements, the area may be reduced to 500 sq.m. for compartmentation.

Where this is not possible, the spacing of the sprinklers, care should be taken to prevent spray from one sprinkler impeding the performance of an adjacent sprinkler head.

22.5 Service Ducts/Shafts

- a) Service ducts and shafts shall be enclosed by walls of 2 h and doors of 1 h. fire rating. All such ducts/shafts shall be properly sealed and fire stopped at all floor levels.
- b) A vent opening at the top of the service shaft shall be provided having between one- fourth and one-half of the area of the shaft.

22.6 Refuse chutes

shall have opening at least 1 m. above roof level for venting purpose and they shall have an enclosure wall of non-combustible material with fire resistance of not less than 2 h. They shall not be located within the staircase enclosure or service shafts, or air-conditioning shafts inspection panel and doors shall be tight fitting with 1 h fire resistance; the chutes should be as far away as possible from exit.

22.7 Refuge Area

Provisions contained in Regulation No 18.28.6 shall apply for all buildings -

22.8 Electrical services shall conform to the following :

- (a) The electric distribution cables / wiring shall be laid in a separate duct. The duct shall be sealed at every floor with non-combustible materials having the same fire resistance as that of the duct. Low and medium voltage wiring running in shaft and in false ceiling shall run in separate conduits;
- (b) Water mains, telephone lines, intercom lines, gas pipes or any other service line shall not be laid in the duct for electrical cables; use of bus ducts / solid rising mains instead of cables is preferred;
- (c) Separate circuits for fire-fighting pumps, lifts, staircases and corridor lighting and blowers for pressurizing system shall be provided directly from the main switch gear panel and these circuits shall be laid in separate conduit pipes, so that fire in one circuit will not affect the others. Such circuits shall be protected at origin by an automatic circuit breaker with its no- volt coil removed. Master switches controlling essential service circuits shall be clearly labelled;
- (d) The inspection panel doors and any other opening in the shaft shall be provided with air-tight fire doors having fire resistance of not less than 2 h;
- (e) Medium and low voltage wiring running in shafts and within false ceiling shall run in metal conduit. Any 230 V wiring for lighting or other services above false ceiling shall have 660 V grade insulation. The false ceiling including all fixtures used for its suspension, shall be of non-combustible material and shall provide adequate fire resistance to the ceiling in order to prevent spread of fire across ceiling. Reference may be made to good practice;
- (f) An independent and well ventilated service room shall be provided on the ground level or first basement with direct access from outside or from the corridor for the purpose of termination of electric supply from the licensees' service and alternative supply cables. The doors provided for the service room shall have fire resistance of not less than 2 h.

Note : If service room is located at the first basement, it should have automatic fire extinguishing system.

- (g) If the licensees agree to provide meters on upper floors, the licensees' cable shall be segregated from consumers' cable by providing a partition in the duct. Meter rooms on upper floors shall not open into staircase enclosures and shall be ventilated directly to open air outside; and
- (h) Suitable circuit breakers shall be provided at the appropriate points.

22.9 Gas supply shall conform to the following:-

- a) Town Gas / L.P. Gas Supply Pipes – Where gas pipes are run in buildings, the same shall be run in separate shafts exclusively for this purpose and these shall be on external walls, away from the staircases. There shall be no interconnection of this shaft with the rest of the floors. LPG distribution pipes shall always be below the false ceiling. The length of these pipes shall be as short as possible. In the case of kitchen cooking range area, apart from providing hood, covering the entire cooking range, the exhaust system should be designed to take care of 30 cu.m. per minute per sq.m. of hood protected area. It should have grease filters using metallic grill to trip oil vapours escaping into the fume hood.

Note:- For detailed information on gas pipe installations, reference may be made to Para.9 Plumbing Services, Section 3 Gas Supply, of National Building Code of India.

- b) All wiring in fume hoods shall be of fibre glass insulation. Thermal detectors shall be installed into fume hoods of large kitchens for hotels, hospitals and similar areas located in high rise buildings. Arrangements shall be made for automatic tripping of the exhaust fan in case of fire. If LPG is used, the same shall be shut off. The voltage shall be of 24 V or 100 V dc operated with the external rectifier. The valve shall be of the hand re-set type and shall be located in an area segregated from cooking ranges. Valves shall be easily accessible. The hood shall have manual facility for steam or carbon dioxide gas injection, depending on duty condition; and
- c) Gas meters shall be housed in a suitably constructed metal cupboard located in a well-ventilated space, keeping in view the fact that LPG is heavier than air and town gas is lighter than air.

22.10 Illumination of means of exit

Staircase and corridor lights shall conform to the following:

- a) The staircase and corridor lighting shall be on separate circuits and shall be independently connected so as it could be operated by one switch installation on the ground floor easily accessible to fire-fighting staff at any time irrespective of the position of the individual control of the light points, if any. It should be of miniature circuit breaker type of switch so as to avoid replacement of fuse in case of crisis;
- b) Staircase and corridor lighting shall also be connected to alternative supply. The alternative source of supply may be provided by battery continuously trickle charged from the electric mains;
- c) Suitable arrangements shall be made by installing double throw switches to ensure that the lighting installed in the staircase and the corridor does not get connected to two sources of supply simultaneously. Double throw switch shall be installed in the service room for terminating the stand-by supply.
- d) Emergency lights shall be provided in the staircase and corridor; and
- e) All wires and other accessories used for emergency light shall have fire retardant property.

22.11 A stand-by electric generator shall be installed to supply power to staircase and corridor lighting circuits, fire lifts, the stand-by fire pump, pressurisation fans and blowers, smoke extraction and damper systems in case of failure of normal electric supply. The generator shall be capable of taking starting current of all the machines and circuits stated above simultaneously. If the stand-by pump is driven by diesel engine, the generator supply need not be connected to the stand-by pump. Where parallel HV / LV supply from a separate sub-station is provided with appropriate transformer for emergency, the provision of generator may be waived in consultation with the Authority.

22.12 Transformers shall conform to the following:-

- a) A sub-station or a switch-station with oil filled equipment shall not be located in the building. The sub-station structure shall have separate fire resisting walls/surroundings and shall necessarily be located at the periphery of the floor having separate access from fire escape staircase. The outside walls, ceiling, floor, openings including doors and windows to the sub-station area shall be provided

with a fire resisting door of 2 h fire rating. Direct access to the transformer room shall be provided, preferably from outside fire escape staircase.

- b) The sub-station area needs to be maintained at negative air pressures and area in sub-station shall not be used as storage / dump areas.
- c) When housed inside the building, the transformer shall be of dry type and shall be cut off from the other portion of premises by walls/ doors / cut-outs having fire resistance rating of 4h.

22.13 Air-conditioning shall conform to the following:

- a) Escape routes like staircases, common corridors, lift lobbies, etc. shall not be used as return air passage.
- b) The ducting shall be constructed of substantial gauge metal in accordance with good practice.
- c) Wherever the ducts pass through fire walls or floors, the opening around the ducts shall be sealed with materials having fire resistance rating of the compartment.
- d) Where duct crosses a compartment which is fire rated, the ducts shall be fire rated for same fire rating. Further depending on services passing around the duct work, which may get affected in case of fire temperature rising, the ducts shall be insulated.
- e) As far as possible, metallic ducts shall be used even for the return air instead of space above the false ceiling.
- f) Where plenum is used for return air passage, ceiling and its fixtures shall be of non-combustible material.
- g) The materials used for insulating the duct system (inside or outside) shall be of non-combustible material, glass wool shall not be wrapped or secured by any material of combustible nature.
- h) Area more than 750sq.m. on individual floor shall be segregated by a fire wall and automatic fire dampers for isolation shall be provided.
- i) Air ducts serving main floor areas, corridors, etc. shall not pass through the staircase enclosure.
- j) The air-handling units shall be separate for each floor and air ducts for every floor shall be separated and in no way inter-connected with the ducting of any other floor.
- k) If the air-handling unit serves more than one floor, the recommendations given above shall be compiled with in addition to the conditions given below:
 - i) Proper arrangements by way of automatic fire dampers working on smoke detector / or fusible link for isolating all ducting at every floor from the main riser shall be made.
 - ii) When the automatic fire alarm operates, the respective air-handling units of the air-conditioning system shall automatically be switched off.
- l) The vertical shaft for treated fresh air shall be of masonry construction.
- m) The air filters of the air-handling units shall be of non-combustible materials.
- n) The air-handling unit room shall not be used for storage of any combustible materials.
- o) Inspection panels shall be provided in the main trunking to facilitate the cleaning of ducts of accumulated dust and to obtain access for maintenance of fire dampers.
- p) No combustible material shall be fixed nearer than 150 mm to any duct unless such duct is properly enclosed and protected with non-combustible material (glass wool or spyglass with neoprene facing enclosed and wrapped with aluminium sheeting) at least 3.2 mm thick and which would not readily conduct heat.

q) Fire Dampers:-

- 1) These shall be located in conditioned air ducts and return air ducts/ passages at the following points:

- i) At the fire separation wall.
 - ii) Where ducts/passages enter the central vertical shaft.
 - iii) Where the ducts pass through floors.
 - iv) At the inlet of supply air duct and the return air duct of each compartment on every floor.
- 2) The dampers shall operate automatically and shall simultaneously switch off the air-handling fans. Manual operation facilities shall also be provided. (Note- For blowers, where extraction system and duct accumulators are used, dampers shall be provided).
- 3) Fire/smoke dampers (for smoke extraction shafts) for buildings more than 24 mt in height.
- a) For apartment houses in non-ventilated lobbies / corridors operated by fusible link / smoke detectors and with manual control.
 - b) For other buildings on operation of smoke detection system and with manual control.
- 4) Automatic fire dampers shall be so arranged as to close by gravity in the direction of air movement and to remain tightly closed on operation of a fusible link / smoke detector.

22.14 Provisions of boiler and boiler rooms shall conform to Indian Boiler Act. Further, the following additional aspects may be taken into account in the location of boiler room:

- a) The boilers shall not be allowed in sub-basement, may be allowed in the basements away from the escape routes.
- b) The boilers shall be installed in a fire resisting room of 4 h fire resistance rating and this room shall be situated on the periphery of the basement. Catch-pits shall be provided at the low level.
- c) Entry to this room shall be provided with a composite door of 2 h fire resistance.
- d) The boiler room shall be provided with fresh air inlets and smoke exhausts directly to the atmosphere.
- e) The furnace oil tank for the boiler, if located in the adjoining room shall be separated by fire resisting wall of 4 h rating. The entrance to this room shall be provided with double composite doors. A curb of suitable height shall be provided at the entrance in order to prevent the flow of oil into the boiler room in case of tank rupture.
- f) Foam inlets shall be provided on the external walls of the building near the ground level to enable the fire services to use foam in case of fire.

22.15 Provision of first-aid and fire-fighting appliances.

The first-aid fire-fighting equipment shall be provided on all floors, including basements, lift rooms, etc. in accordance with good practice in consultation with the Authority.

22.16 Fire alarm system :

- i) All buildings with heights of 15 m or above shall be equipped with manually operated electrical fire alarm (MOEFA) system automatic fire alarm system in accordance with good practice. However, apartment buildings between 15 m and 30 m in height may be exempted from the installation of automatic fire alarm system provided the local fire brigade is suitably equipped for dealing with fire in a building of 15 m in height or above and in the opinion of the Authority, such building does not constitute a hazard to the safety of the adjacent property or occupants of the building itself.
- ii) Manually operated electrical fire alarm system shall be installed in a building with one or more call boxes located at each floor. The call boxes shall conform of good practice.
- iii) The installation of call boxes in hostels and such other places where these are likely to be misused shall as far as possible be provided. Location of call boxes in dwelling units shall preferably be inside the building.

22.17 Lightning protection of buildings:-

The lightning protection for buildings shall be provided as given in Para.8 _Building Services, Section

2, Electrical Installations^४ of National Building Code of India.

22.18 Fire control room:-

For all buildings 15 mt in height or above and apartment buildings with a height of 30 m and above, there shall be a control room on the entrance floor of the building with communication system (suitable public address system) to all floors and facilities for receiving the message from different floors. Details of all floor plans alongwith the details of fire-fighting equipment and installations shall be maintained in the fire control room. The fire control room shall also have facilities to detect the fire on any floor through indicator board connections; fire detection and alarm systems on all floors. The fire staff in-charge of the fire control room shall be responsible for the maintenance of the various services and fire-fighting equipment and installations in co-ordination with security, electrical and civil staff of the building.

22.19 Housekeeping:-

To eliminate fire hazards, good housekeeping, both inside and outside the building, shall be strictly maintained by the occupants and / or the owner of the building.

22.20 Fire drills and fire orders:-

Fire notices/orders shall be prepared to fulfil the requirements of fire-fighting and evacuation from the buildings in the event of fire and other emergency. The occupants shall be made thoroughly conversant with their actions in the event of emergency, by displaying fire notices at vantage points and through regular training. Such notices should be displayed prominently in broad lettering.

For guidelines for fire drills and evacuation procedures for high-rise buildings, Annexure E of National Building Code of India may be referred.

22.21 Compartmentation:-

The building shall be suitably compartmentalized so that fire/smoke remain confined to the area where fire incident has occurred and does not spread to the remaining part of the building.

22.22 Materials for interior decoration / furnishing

The use of materials, which are combustible in nature and may spread toxic fume / gases should not be used for interior decoration / furnishing, etc.

For various types of occupancies, requirements given in National Building Code, Part IV shall be followed.

22.23 Fire Escape Chutes/ Controlled Lowering Device for evacuation:-

(A) High rise building having height more than 70 mt., shall necessarily be provided with;

- (i) fire escape chute shaft/s for every wing adjacent to staircase.
- (ii) Walls of the shaft shall have 4 hours fire resistance.
- (iii) One side of the shaft shall be at external face of the building with proper ventilation.
- (iv) The dimension of the shaft shall not be less than 2.5 m X 1.5m.
- (v) The access to the fire escape chute's shaft shall be made at alternate floor level from staircase mid-landing with self-closing door having fire resistance of at least one hour.
- (vi) The fire chute shall be of staggered type with landing of each section at the vertical height of not more than 21 m.

Alternatively,

(B) For High rise building having height more than 70 mt., —Controlled Lowering Device for evacuation[॥] or —External Evacuation System[॥] as approved by Chief Fire Officer of PMRDA, shall be provided.

22.24 Fire Check Floor A high rise building having height more than 70 m, shall be provided with fire check floor (entire floor) at every 70 m. level. Height of the fire check floor shall not be more than 1.8 m. The fire check floor shall not be used for any purpose and it shall be the responsibility of the owner/occupier to maintain the same clean and free of encumbrances and encroachments at all times. Periphery of the Fire Check floor shall not be enclosed. Fire Drenchers shall be provided at the periphery of the each fire check floor externally.

22.25 The PMRDA shall charge Fire Infrastructure charges as may be decided by Metropolitan Commissioner with the approval of the Government, such charges shall be deposited in the separate account under the head of Fire Infrastructure charges and such amount shall only be used for establishment and expansion of Fire Infrastructure facilities.

22.26 Fire officer for hotels, business and mercantile buildings with height more than 30 m

22.26.1) A qualified Fire Officer with experience of not less than 3 years shall be appointed who will be available on the premises.

22.26.2) The Fire Officer shall:

- i) maintain the firefighting equipment in good working condition at all times,
- ii) prepare fire orders and fire operational plans and get them promulgated,
- iii) impart regular training to the occupants of the buildings in the use of firefighting equipment's provided on the premises and keep them informed about the fire emergency evacuation plan,
- iv) keep proper liaison with City Fire Brigade, and
- v) ensure that all fire precautionary measures are observed at the times.

Note: Competent Authority having jurisdiction may insist on compliance of the above rule in case of buildings having very large areas even if the height is less than 30 m.

PART – VII

STRUCTURAL SAFETY, WATER SUPPLY, DRAINAGE & SANITARY REQUIREMENTS, OUTDOOR DISPLAY AND OTHER SERVICES

23.0 STRUCTURAL DESIGN

- 23.1** The structural design of foundations, elements made of masonry, timber, plain concrete; reinforced concrete, pre-stressed concrete and structural steel shall be carried out in accordance with Part 6. Structural design Section 1-Loads, courses and effects, Section 2-Soils and Foundation, Section-3-Timber and Bamboo, Section 4-Masonry, Section5-Concrete, Section 6-Steel, Section-7-Prefabrication, systems building and mixed / composite construction of National Building Code of India, amended from time to time. Proposed construction shall be as per the norms as specified by Indian Standard Institute, for the resistance of earthquake, Fire Safety and natural calamities. Certificate to that effect shall be submitted by the Licensed Structural Engineer of the developer / land owner, along with the proposal for development permission.

24.0 QUALITY OF MATERIALS AND WORKMANSHIP

- 24.1** All materials and workmanship shall be of good quality conforming generally to accepted standards of Public Works Department of Maharashtra and Indian Standard Specifications and Codes as included in Part 5 - Building Materials and Part 7 - Construction Practices and Safety of National Building Code of India, amended from time to time

- 24.2** All borrow pits dug in the course of construction and repair of buildings, roads, embankments etc. shall be deep and connected with each other in the formation of a drain directed towards the lowest level and properly stopped for discharge into a river stream, channel or drain and no person shall create any isolated borrow pit which is likely to cause accumulation of water which may breed mosquitoes.

25.0 ALTERNATIVE MATERIALS, METHODS OF DESIGN & CONSTRUCTION AND TESTS

- 25.1** The provision of the regulations are not intended to prevent the use of any material or method of design or construction, not specifically prescribed by the regulations, provided any such alternative has been approved.
- 25.2** The provision of these regulations is also not intended to prevent the adoption for architectural planning and layout conceived as an integrated development scheme.
- 25.3** The authority may approve any such alternative provided it is found that the proposed alternative is satisfactory and conform to the provisions of relevant parts regarding material, design, and construction and that material, method or work offered is, for the purpose intended, at least equivalent to that prescribed in the rules in quality, strength, compatibility, effectiveness, fire rating and resistance, durability and safety.
- 25.4** Tests: Whenever there is insufficient evidence of compliance with the provisions of the regulations of evidence that any material or method of design or construction does not conform to the requirements of the rules or in order to substantiate claims for alternative materials, design or methods of construction, the Metropolitan Commissioner may require tests sufficient in advance as proof of compliance. These tests shall be made by an approved agency at the expense of the owner.
- 25.5** Test method shall be as specified by the regulations for the materials or design or construction in question. If there are no appropriate test methods specified in the regulations, the Authority shall determine the test procedure. For methods of tests for building materials; reference may be made to relevant Indian standards as given the National Building Code of India, published by the Bureau of Indian Standards. The latest version of the National Building Code of India shall be taken into account at the time of enforcement of these rules.
- 25.6** Copies of the results of all such tests shall be retained by the authority for a period of not less than two years after the acceptance of the alternative material.

26.0 BUILDING SERVICES

- 26.1** The planning, design and installation of electrical installations, air-conditioning and heating work shall be carried out in accordance with Part 8 - Building Services, Section 2-Electrical and allied Installations, Section 3-Air Conditioning, heating and mechanical ventilation of National Building Code of India, amended from time to time.
- 26.2** The planning design including the number of lifts, type of lifts, capacity of lifts depending on occupancy of building; population on each floor based on occupant load, height of building shall be in accordance with Section-5 installation of Lifts and Escalators of National Building Code of India, amended from time to time. In existing buildings, in case of proposal for one additional floor, existing lift may not be raised to the additional floor.
- 26.3** The lifts shall be maintained in working order properly.

27.0 WATER SUPPLY, DRAINAGE AND SANITARY REQUIREMENTS.

- 27.1** The planning, design, construction and installation of water supply, drainage and sanitation and gas supply systems shall be in accordance with the provisions of Part 9 - Plumbing Services- Section 1 Water Supply, Drainage and Sanitation, Section 2 - Gas supply of National Building Code of India as amended from time to time.
- 27.2 Requirements of water supply in building.**

The total requirements of water supply shall be calculated based on the population as given below:

Occupancy	Basis
Residential Building	5 persons per tenement
Other Buildings	No. of persons on occupant load and area of floors given in Table No.13.

- 27.2.1** The requirements of water supply for various occupancies shall be as given in Table No.24 and Table No.25 or as specified by the Metropolitan Commissioner from time to time.

Table No. 24		
PER CAPITA WATER REQUIREMENTS FOR VARIOUS OCCUPANCIES/USES		
Sr. No	Type of Occupancy	Consumption per head per day (in liters)
1	Residential	
	(a) in living units	135
	(b) Hotels with lodging accommodation (per bed)	180
2	Educational:	
	(a) Day Schools	45
	(b) Boarding Schools	135
3	Institutional (Medical Hospitals):	
	(a) No. of beds not exceeding 100	340
	(b) No. of beds exceeding 100	450
	(c) Medical quarters and hostels	135
4	Assembly-Cinema theatres, auditorium etc. (per seat of accommodation).	15
5	Government and Semi-public business.	45
6	Mercantile (Commercial)	
	(a) Restaurants (per seat)	70
	(b) Other business buildings.	45
7	Industrial	
	(a) Factories where bathrooms are to be provided	45
	(b) Factories where no bath-rooms are required to be provided.	30
8	Storage (including warehousing)	30
9	Hazardous	30
10	Intermediate / Stations (excluding mail and express stops).	45 (25)*
11	Junction Stations	70 (45)*
12	Terminal / Stations.	45
13	International and domestic Airports.	70

The value in parenthesis is for stations where bathing facilities are not provided.

Note: The number of persons for Sr. No. (10) to (13) shall be determined by the average number of passengers, handled by the station daily; due consideration may be given to the staff and workers likely to use the facilities.

Table No. 25		
FLUSHING STORAGE CAPACITIES		
Sr.No.	Classification of building	Storage capacity.
(1)	(2)	(3)
1	For tenements having common convenience	900 liters net per w. c. seat.
2	For residential premises other than tenements having common convenience	270 liters net for one w. c. seat and 180 liters for each additional seat in the same flat.
3	For Factories and Workshops	900 liters per w. c. seat and 180 liters per urinal seat.
4	For cinemas, public assembly halls, etc.	900 liters per w. c. seat and 350 liters per urinal seat.

28.0 DRAINAGE AND SANITATION REQUIREMENTS

28.1 General

There should be at least one water tap and arrangement for drainage in the vicinity of each water- closet or group of water-closets in all the buildings.

- 28.1.1 Each family dwelling unit on premises (abutting on a sewer or with a private sewage disposal system) shall have, at least, one water-closet and one kitchen type sink. A bath or shower shall also be installed to meet the basic requirement of sanitation and personal hygiene.
- 28.1.2 All other structures for human occupancy or use on premises, abutting on a sewer or with a private sewage disposal system, shall have adequate sanitary facilities, but in no case less than one water- closet and one other fixture for cleaning purposes.

28.2 For Residences

28.2.1 Dwelling with individual convenience shall have at least the following fitments:

- One bathroom provided with a tap and a floor trap,
- One water-closet with flushing apparatus with an ablution tap; and
- One tap with a floor trap or a sink in kitchen or wash place.

28.2.2 Dwelling without individual conveniences shall have the following fitments:

- One water tap with floor trap in each tenement,
- One water-closet with flushing apparatus and one ablution tap, bath for every two tenements, and
- One bath with water tap and floor trap for every two tenements.

28.3 For Buildings Other than Residences

- 28.3.1 The requirements for fitments for drainage and sanitation in the case of buildings other than residences shall be in accordance with Tables given in Appendix-M (1 to 14). The following shall be, in addition, taken into consideration:

- a) The figures shown are based upon one (1) fixture being the minimum required for the number of persons indicated or part thereof.
- b) Building categories not included in the tables shall be considered separately by the Metropolitan Commissioner.
- c) Drinking fountains shall not be installed in the toilets.
- d) Where there is the danger of exposure to skin contamination with poisonous, infectious or irritating material, washbasin with eye wash jet and an emergency shower located in an area accessible at all times with the passage / right of way suitable for access to a wheel chair, shall be provided.
- e) When applying the provision of these tables for providing the number of fixtures, consideration shall be given to the accessibility of the fixtures. Using purely numerical basis may not result in an installation suited to the need of a specific building. For example, schools should be provided with toilet facilities on each floor. Similarly toilet facilities shall be provided for temporary workmen employed in any establishment according to the needs; and in any case one WC and one washbasin shall be provided.
- f) All buildings used for human habitation for dwelling work, occupation, medical care or any purpose detailed in the various tables, abutting a public sewer or a private sewage disposal system, shall be provided with minimum sanitary facilities as per the schedule in the tables. In case the disposal facilities are not available, they shall be provided as a part of the building design for ensuring high standards of sanitary conditions in accordance with this section.
- g) Workplaces where crèches are provided, they shall be provided with one WC for 10 persons or part thereof, one washbasin for 15 persons or part thereof, one kitchen sink with floor tap for preparing food / milk preparations. The sink provided shall be with a drinking water tap.
- h) In all types of buildings, individual toilets and pantry should be provided for executives and for meeting / seminar / conference rooms, etc. as per the user requirement.
- i) Where food is consumed indoors, water stations may be provided in place of drinking water fountains.

29.0 SIGNS AND OUTDOOR DISPLAY STRUCTURES

- 29.1** The display of advertising signs on buildings and land, shall be in accordance with Part 10, Section-2 "Signs and outdoor display structures" of National Building Code of India as amended from time to time and, shall be in accordance with respective rules/by-laws, directive given by Government, and also rules/by-laws framed by the PMRDA in this regards from time to time.

Prohibition of advertising signs and outdoor display structure in certain cases - Notwithstanding the provisions of sub-regulations no advertising sign or outdoor display structures shall be permitted on buildings of architectural, aesthetical, historical or heritage importance as may be decided by the Commissioner or on Government Buildings save that in the case of Government buildings only advertising signs or outdoor display structure may be permitted if they relate to the activities for the said buildings' own purposes or related programmers.

PART - VIII
SPECIAL PROVISIONS FOR CERTAIN BUILDINGS

30.0 PROVISIONS OF FACILITIES FOR DIFFERENTLY ABLED PERSONS

Provisions for Barrier Free access in buildings for differently abled persons ("Divyang") shall be as given in **Appendix-N**

31.0 INSTALLATION OF SOLAR ASSISTED WATER HEATING (SWH) SYSTEM/ ROOF TOP PHOTOVOLTAIC (RTPV) SYSTEM

SWH or RTPV systems shall be mandatory in all types of buildings to be constructed on plot area of more than 4000 sq m

In order to facilitate the installation of SWH/RTPV System, the new buildings shall have the following provisions:

- i. All such buildings where SWH/RTPV are to be installed will have open sunny roof area available for the installation of SWH/RTPV.
- ii. The roof loading adopted in the design of such building should be atleast 50 kg per sq.m. for the installation of SWH/RTPV.
- iii. At least 25% of the roof area shall be utilized for installation of the SWH/RTPV system.
- iv. Precaution should be taken that architectural elevation treatment should not cast shadow on terrace space. As far as possible, parapet of south, east and west sides of the terrace shall be of railing type (above 1 feet) such that it will not cast shadow on the solar collectors and maximum terrace space can be utilized.
- v. All such new buildings installed with SWH shall have an installed hot water line from the rooftop and insulated distribution pipelines to each of the points where hot water is required in the building.

32.0 RAIN WATER HARVESTING

The provision for Rain Water Harvesting shall be made as under:

- i. All the layout open spaces/amenity spaces of housing societies and new constructions/ reconstruction/ additions on plots having area not less than 500sq.mt., in non-congested areas shall have one or more Rain Water Harvesting structures having a minimum total capacity as detailed in Schedule.

Provided that the Commissioner may approve the Rain Water Harvesting structures of specifications different from those in Schedule, subject to the minimum capacity of Rain Water Harvesting being ensured in each case.

- ii. The owner/society of every building mentioned in the (a) above shall ensure that the Rain Water Harvesting System is maintained in good condition for storage of water for non- potable purposes or recharge of groundwater at all times.
- iii. The Authority may impose a levy of not exceeding Rs.1000/- per annum for every 100 sq.mt. of built-up area for the failure of the owner of any building mentioned in the (a) above to provide or to maintain Rain Water Harvesting structures as required under these regulations. Failure to provide Rain Water Harvesting System shall deem to be breach of the conditions on which the development permission has been granted.

SCHEDULE

Rain Water Harvesting in a building site includes storage or recharging the ground water by rainwater falling on the terrace or any paved or unpaved surface within the building site.

1. The following systems may be adopted for harvesting the rainwater drawn from terrace and the paved surface.
 - i) Open well of a minimum 1.00 mt diameter and 6mt in depth into which rain water may be channelled and allowed to filter for removing silt and floating material. The well shall be provided with ventilating covers. The water from the open well may be used for non-potable domestic purposes such as washing, flushing and for watering the garden etc.
 - ii) Rain Water Harvesting for recharge of groundwater may be done through a bore-well around which a pit of 1m width may be excavated upto a depth of at least 3m and refilled with stone aggregate and sand. The filtered rain water may be channelled to the refilled pit for recharging the bore-well.
 - iii) An impressive surface/underground storage tank of required capacity may be constructed in the setback or other open spaces and the rain water may be channelled to the storage tank. The storage tank shall always be provided with ventilating covers and shall have drawn-off taps suitably placed so that rain water may be drawn off for domestic, washing, gardening and such other purposes. The storage tank shall be provided with an overflow.
 - iv) The surplus rain water after storage may be recharged in to ground through percolation pits or trenches or combination of pits and trenches. Depending on the geo-morphological and topographical conditions, the pits may be of the size of 1.20 m width X 1.20 m length X 2 m to 2.50 m depth. The trenches can be of 0.60 m width X 2 to 6 m length X 1.50 to 2 m depth. Terrace water shall be channelled to pits or trenches. Such pits or trenches shall be back filled with filter media comprising the following materials:
 - a) 40 mm stone aggregate as bottom layer upto 50% of the depth.
 - b) 20 mm stone aggregate as lower middle layer upto 20% of the depth.
 - c) Coarse sand as upper middle layer upto 20% of the depth.
 - d) A thin layer of fine sand as top layer.
 - e) Top 10% of the pits/trenches will be empty and a splash is to be provided in this portion in such a way that roof top water falls on the splash pad.
 - f) Brick masonry wall is to be constructed on the exposed surface of pits/trenches and the cement mortar plastered. The depth of wall below ground shall be such that the wall prevents loose soil entering into pits/ trenches. The projection of the wall above ground shall at least be 15 cm.
 - g) Perforated concrete slabs shall be provided on the pits/trenches.
 - h) If the open space surrounding the building is not paved, the top layer up to a sufficient depth shall be removed and refilled with coarse sand to allow percolation of rain water into ground.
 - v) The terrace shall be connected to the open well/bore-well/storage tank/ recharge pit/trench by means of HDPE / PVC pipes through filter media. A valve system shall be provided to enable the first washing from roof or terrace catchment, as they would contain undesirable dirt. The mouth of all pipes and opening shall be covered with mosquito (insect) proof wire net. For the efficient discharge of rain water, there shall be at least two rain water pipes of 100 mm dia. for a roof area of 100 sq.m.

- vi) Rain Water Harvesting structures shall be sited as not to endanger the stability of building or earthwork. The structure shall be designed such that no dampness is caused in any part of the walls or foundation of the building or those of an adjacent building.
- vii) The water so collected/recharged shall as far as possible be used for non-drinking and non-cooking purpose. Provided that when the rain water in exceptional circumstances will be utilised for drinking and/or cooking purpose, it shall be ensured that proper filter arrangement and the separate outlet for bypassing the first rain water has been provided. Provided further that, it will be ensured that for such use, proper disinfectants and the water purification arrangements have been made.

33.0 REGULATION FOR WASTE WATER RECYCLING

33.1 Type of Waste Water

The Waste Water is of following types:--

- i. Black Water.- means Waste Water from W.C. Urinals and M.S.W.
- ii. Grey Water.--means Waste Water from Bathrooms, Sinks, Shower and Wash Areas etc.
- iii. Apart from Residential Waste Water, Waste Water generated from Industrial, Medical, Commercial and Waste generated from Garbage shall also be treated as per the guidelines given by the Maharashtra Pollution Control Board.

33.2 APPLICABILITY

These Regulations shall be applicable to all Developments/ Redevelopments/part Developments for the uses as mention under (C-1) to (C-6) shall have the provision for treatment, recycling and reuse of Waste Water. The applicant shall along with his application for obtaining necessary layout approval/ building permission shall submit a plan showing the location of Waste Water Treatment Plant, furnishing details of calculations, references, implementation, etc. This Plan shall accompany with the applicant's commitment to monitor the system periodically from the date of occupation of the respective building.

33.3 REGULATIONS

33.3.1 (C-1) For Layout Approval/Building Permission

- (i) In case of Residential layouts, area admeasuring 10000 sq.m. or more, in addition to 10 % open space, prescribed in the bye-laws, a separate space for Waste Water Treatment and Recycling Plant should be proposed in the layout.
- (ii) On the layout Plan, all Drainage lines, Chambers, Plumbing lines should be marked in different colour and submit the layout for approval to the PMRDA.
- (iii) The Recycled Water shall be used for Gardening, Car Washing, Toilet Flushing, Irrigation, etc. and in no case for drinking, bathing, washing utensils, clothes, etc
- (iv) In the Estimate of Waste Water Recycling Plant only provision for basic civil work and required machinery will be proposed by the PMRDA other than these provisions, additional machinery, plumbing, Water tank pipe, landscape should be provided by Owner or Developer on his Own Cost.
- (v) A clause must be included by the Owner/ Developer in the purchase agreement that the purchaser, Owner of the Premises/Organization or Society of the purchasers shall ensure that:

- a. The Recycled Water is tested every six months either in Municipal Laboratory or in the laboratory approved by PMRDA or by State Government and the result of which shall be made accessible to the Competent Authority/ EHO of the respective Ward Office.
- b. Any recommendation from testing laboratory for any form of corrective measures that are needed to be adopted shall be compiled. Copy of any such recommendation and necessary action taken shall also be sent by the testing laboratories to the Competent Authority/ EHO of respective Wards.
- c. Maintenance of Recycling Plant should be done by the Developer or Housing Society or Owner.

33.3.2 (C-2) Group Housing/Apartment Building

In case of Group Housing if the area admeasuring 4000 sq.m. and above or if consumption of Water is 20,000 litres per day or if a multi-storeyed building where there are 20 or more tenements then Waste Water Recycling Plant as mentioned in (C-1) above should be constructed.

33.3.3 (C-3) Educational, Industrial, Commercial, Government, Semi-Government Organizations, Hotels, Lodgings etc.

For all above buildings having built-up area 1500 sq.m. or more or if Water consumption is 20,000 litre per day whichever is minimum, then provision for Waste Water Treatment Plant as mentioned in (C-1) is applicable.

33.3.4 (C-4) Hospitals

Those Hospitals having 40 or more beds, Waste Water Recycling Plant as mentioned in (C-1) is applicable.

33.3.5 (C-5) Vehicle Servicing Garages

All Vehicle servicing garages shall ensure that the Waste Water generated through washing of vehicles is treated and recycled back for the same use as mentioned in (C-1)

33.3.6 (C-6) Other Hazardous uses

All other Establishments/ Buildings where chances of Waste Water generated containing harmful chemicals, toxins are likely and where such water cannot be directly led into public sewers, the concerned Competent Authority may direct the Owners, users of such Establishments, Buildings to treat their Waste Water as per the directions laid in (C-1)

33.4 INCENTIVE

The Owner/Developer/Society setting up and agreeing to periodically maintain such Waste Water Treatment and Recycling Plant entirely through their own expenditure shall be eligible for an incentive in the form of fiscal benefits in Property Tax to the extent of 5% to Tenement holder/Society.

33.5 Penalty Clause

- (i) Any person / Owner / Developer / Organization / Society violating the provisions of these bye-laws, he shall be fined Rs. 2,500/- on the day of detection and if the violation continues, then he shall be fined Rs.100/- for every day as concrete action after written Notice from PMRDA.
- (ii) If any person / Owner /Developer / Organization / Society fails to operate as determined by the Authorised Officer of the PMRDA and from the observations of test results and/or physical verification of the Recycling plant, then he will be charged a penalty of Rs.300/- per day and disconnection of Water connection also.

34.0 SOLID WASTE MANAGEMENT

It shall be mandatory for:

- i. Housing complexes, Commercial establishments, hostels, hospitals having aggregate built-up area more than 4,000 sq.m. or more;
- ii. All three star or higher category hotels;

to establish a dedicated Solid waste management system to treat 100% wet waste and home-compostable plastic being generated in such buildings.

The treatment of wet waste shall be done through an organic waste composters/ vermiculture pits or other similar technologies of suitable capacity installed through reputed vendors.

The disposal of dry waste, e-waste, hazardous waste shall be carried out through authorised recyclers or any other system as specified by the Metropolitan Commissioner.

35.0 INCENTIVE FOR GREEN BUILDINGS

The PMRDA shall strive to promote green building concepts within the PMR area. In order to do so it may empanel agencies of repute as listed/ recognised by the State / Central Government. The following incentives shall be provided for green rated buildings.

- i. Green buildings shall be entitled for incentive FSI as below:
GRIHA Three star / IGBC Silver or equivalent rating – 3% incentive FSI on basic FSI.
GRIHA Four star / IGBC Gold or equivalent rating – 5% incentive FSI on basic FSI.
GRIHA Five star / IGBC Platinum or equivalent rating – 7% incentive FSI on basic FSI.
Provided, achieving minimum GRIHA Three star / IGBC Silver or equivalent rating for construction projects shall be mandatory for all buildings belonging to Government, Semi- Government, local bodies and public sector undertakings.
- ii. Incentive FSI will be awarded after pre-certification from the empanelled agency. This FSI shall be exclusive of the limits specified in this DCPR.
- iii. In case that the developer fails to achieve committed rating as per pre-certification at the time of final occupancy, a penalty shall be imposed at the rate 2 times of the land cost as per ASR for the incentive FSI for the rating not achieved.

PART - IX
SPECIAL SCHEMES/ ACTIVITIES

36.0 SPECIAL REGULATION FOR DEVELOPMENT OF "INTEGRATED TOWNSHIP PROJECT (ITP)"

(Modifications suggested in the earlier sanctioned Integrated Township Project Regulations sanctioned vide notification dated 26/12/2016. Modifications are shown as bold letters, strikethrough in the following Draft Regulations).

1. Applicability:-

These regulations shall be applicable to the areas under Regional Plan / Development Plans including areas under jurisdiction of SPAs and ADAs within Regional Plan / Development Plan sanctioned under the provisions of Maharashtra Regional and Town Planning Act, 1966 (hereinafter referred to as "the said Act"). **These Regulations shall also be applicable to all Local / Planning Authority areas.** These Regulations shall be applicable only after final sanction by Government under the **related Section 20(4) of the said act.** Till then existing regulations shall remain in force.

Provided that, if the Development Control Regulations regarding development of Integrated Township Project for an area over which a Planning Authority /Special Planning Authority/Area Development Authority has been appointed or constituted or deemed to have been appointed are yet to be sanctioned, then in considering the application for permission, these regulations, shall be applicable, *mutatis mutandis*, till such Authority adopts the Regulations in this regard.

If the ITP falls within the jurisdiction of more than one authority **then** in such cases Government ~~will~~ **can** issue directives at the time of Locational Clearance **or at any time** regarding **which authority will give permission and supervise the project implementation of these regulations subject to terms and conditions as may be specified.**

2. Requirements of Site:-

The area proposed for Integrated Township shall fulfill the following requirements:-

- i) Any suitable area having area of 40 hect. (100 Acres) or more at one place.
- ii) The area shall be one, contiguous, unbroken and uninterrupted. Provided that, such area if divided by one or more water courses (such as nalas, canals, etc.), existing or proposed roads of any width or by railways etc., shall be treated as one, contiguous, unbroken and uninterrupted, subject to condition that the Project Proponent/s shall construct necessary connecting roads or bridges as per site requirements at his own cost with due permission from concerned authorities. **Integrated Township area may also include;**
 - a) **Lands in afforestation zone provided that such land is not a forest land and subject to no construction being allowed on land having slope more than 1:5.**
 - b) **Lands area under notified SEZ subject to denotification from concerned authority before granting LoI.**
 - c) **Lands within the buffer zone of National Park subject to restriction on development permissible in such buffer zone and subject to NOC of Forest Department.**
 - d) **Tribal land if permission granted under MLR code, Government lands allotted to project proponent subject to clause 13.2.**
 - e) **Private forest land that have been restored back after completion of section 22(a) Enquiry of Maharashtra Private Forest Act, 1975 shall be allowed to be part of the ITP with the condition that development permission shall be granted on such land only after necessary permission under**

the provision of forest conservation Act, 1980.

- f) Eco-sensitive Zone notified subject to all restriction on development and FSI permissible in such buffer zone.
- g) Areas under flood line / flood zone subject to clearance from Water Resource Department.
- h) Areas under Hill Top / Hill Slope Zone, Buffer Zone etc. as shown on Regional Plan / Development Plan / Development Plan subject to condition as mentioned in Clause 7.1.3. However total of these areas shall be restricted to maximum 40% of total area under ITP.

iii) If the Integrated Township area is more than 200 Ha., it can be segregated as long as each parcel is more than 40 Ha. and is located within a radius of 5 kms. Provided that the land use mix is maintained in each parcel.

iii)iv) The area shall have an access by means of an existing, or proposed road having minimum width of 18 mt In case of proposed road, such area shall have an access by existing road having width 12 m. for the purpose of declaration locational clearance and LoI of such project to be "Integrated Township Project" (ITP) but it is necessary to the project proponent to have an existing access of 18 mt before sanction of Commencement Certificate beyond 25% of project.

iv)v) Such area The ITP Area shall not include the area under:-

a) Notified forest, (excluding the private forest land subject to NOCs of forest Department.)

b) Water bodies like river, creek, canal, reservoir, etc. Mangroves, Tidal Zone, Mud Flats

~~c) Lands belonging to Tribal~~

d) c) ~~Such area shall not include~~ The area under Notified National Parks.

e) d) Defense Estates

f) e) Cantonment Boards

~~g) Such area shall not include the area under Eco-sensitive Zone Notified under Environmental (Protection) Act, 1986.~~

h) f) Any restricted area.

i) g) ~~Quarry Zone, Notified SEZ,~~ designated port/harbour areas, wildlife Corridor and biospheres reserves, Gaothan/Congested Area.

j) h) The historical and archeological places notified under the relevant act.

k) i) Any other area that may be declared by the Govt. of Maharashtra from time to time.

3. Ownership of Lands:-

The project proponent/s shall have the ownership of all the land parcels under project.

(Explanation - for this clause, ownership includes rights accrued vide one or more registered Development Agreement/s or Power of Attorney (PoA) for such development and disposal, on behalf of land owner/owners).

4. Permission and Declaration of Project by State Government:-

4.1 The Project Proponent/s shall apply to the State Government for obtaining permission and declaration of such project to be a "Integrated Township Project". Such application shall be accompanied by the following attested documents in two sets:-

a) Details of ownership of land viz. extracts of V.F.No. 7/12 or Property Register Cards, in original having date not more than six months prior to the date of submission. In case of rights accrued through registered Development Agreement or PoA, attested copies of such documents.

b) Self-attested list of S.No./G.No./CTS showing name of owner as per record of rights, total area of such land parcel, area owned by the applicant in such land parcel, the name of person/ company owning the

Development Rights, area proposed to be included in project from such land parcel.

- c) Part plan of sanctioned Regional Plan / Development Plan, showing all the lands falling in the project.
- d) No Objection Certificate from **the officer at Divisional level**, Water Resources Department in respect of lands falling in "Command Area" of any Irrigation Project **unless these powers are exercisable by the higher authority**.
- e) Village maps showing the lands falling in the project.
- f) Certificate from concerned Forest Officer not below the rank of Dy. Conservator of Forests **at Divisional level (unless these powers are exercisable by higher authority)**, showing that the lands under project do not form part of and not included in reserved forest or protected forest or non-classified forest or not acquired under the provisions of the Maharashtra Private Forest (Acquisition) Act, 1975 and also, confirming that such lands do not form part of the Notified National Parks, prohibited area of Notified Wildlife Sanctuaries and Notified Bird Sanctuaries.
- g) Certificate from the concerned revenue officer not below the rank of Tahasildar, showing the lands under project do not include lands belonging to **tribal or that tribal land included in ITP have necessary permission under MLR code**.
- h) Certificate from the Director of Archaeological Department, Maharashtra State, showing that the lands under project do not include monuments notified by the Archaeological Department, Heritage buildings and Precincts. Such certificate should also mention the distance to be kept around such places, if any.
- i) Receipt of processing fee (non-refundable) paid, at the concerned branch office of the Town Planning Department, at the rate of Rs.5000/- per ha. for the current year with the yearly rise of Rs.500/- per ha. starting from the month of January every year.

4.2 On receipt of an application under Clause 4.1 above, the Government may, after consulting the Director of Town Planning, Maharashtra State, by notification in the *Official Gazette*, grant the locational permission and declare such project to be a "Integrated Township Project", subject to such general and/or special conditions or, reject the application, under the provisions of Section 18(3) of the said Act, within a period of 90 days from the date of receipt of application or reply from the Project Proponent/s in respect of any requisition made by the Government, whichever is later. **If the project proponent fails to comply with the conditions specified while granting location clearance within the specified time limit, then in such cases location clearance given earlier stands automatically cancelled and no refund or adjustment of premium / fees / expenses etc. shall be eligible.**

(Explanation - In circumstances described in proviso of Clause 4.2, such grant of permission and declaration of project shall be made under the provisions of Section 18(3) read with Section 44(2) of the Maharashtra Regional and Town Planning Act, 1966)

4.3 Every such permission and declaration shall remain in force for a period of two years, if not applied for Letter of Intent under Clause 5, from the date of issue of Locational Clearance Notification and thereafter it shall lapse.

Provided that, the Director of Town Planning, Maharashtra State, Pune may, on application made by Project Proponent/s before expiry of the above period extend such period by two years in aggregate. Provided also that, it is not mandatory on Project Proponent/s to submit all the papers afresh as prescribed under Clause 4.1, however the affidavit regarding the ownership of land about any dispute shall be mandatory.

4.4 Such lapse shall not bar any subsequent application for fresh proposal.

4.5 The Director of Town Planning, Maharashtra State, on the request of Project Proponent/s, by notification in the Official Gazette, may grant to add or delete any area, not exceeding 25% of the total area under Locational Clearance, subject to condition that the remaining area shall not be less than 40 Hect. The permissible FSI and other parameters shall increase or decrease accordingly.

5. Letter of Intent (LOI) by the Collector:-

5.1 The Project Proponent/s shall apply to the Collector for obtaining the Letter of Intent for such project.

Such application shall be accompanied by the **ownership** documents as prescribed in Clause 4.1(a) & 4.1(b) and **with locational clearance notification issued by the Government** ~~also the documents as may be directed by the Collector in respect of ownership only.~~

5.2 The Collector shall verify and satisfy himself that Ownership and Development Rights of all the lands under project are with the Project Proponent/s before issuing the Letter of Intent.

5.3 On receipt of an application under Clause 5.1 the Collector shall grant the Letter of Intent for the whole area or separately for any part thereof, which shall not be less than 40 Ha. at the first instance, subject to conditions as may be deemed fit, or reject the application, within a period of 45 days from the date of receipt of application or reply from the Project Proponent/s in respect of any requisition made by the Collector, whichever is later.

Provided that, in case of rejection, the Collector shall ~~state-mention~~ the grounds for such refusal.

5.4 Every such Letter of Intent shall remain in force for a period of two years, if not applied for Development Permission under Clause 6, from the date of issue of Letter of Intent, unless renewed. Provided that, the Collector may, on application made by Project Proponent/s before expiry of the above period extend such period by two years in aggregate. Provided also that letter of intent granted by collector under earlier regulations may also be extended subject to other conditions of these regulations.

6. Master Layout Plan Approval by the Collector:-

6.1 The project proponent/s shall apply to the concerned Collector for obtaining the approval to the Master Layout Plan of the entire area as per Letter of Intent. Such application shall be accompanied by the documents in two sets as prescribed below:-

- a) Attested copy of Gazette Notification issued by the Government under Clause 4.2.
- b) Attested copy of Letter of Intent issued by Collector under Clause 5.
- c) Part plan of sanctioned Regional Plan / Development Plan, showing the lands under the Master Layout Plan.
- d) Village Map showing the lands under the Master Layout Plan.
- e) In case, project has no access from existing road having right of way of 18 m. then documents showing the ownership of Project Proponent/s in lands proposed for 18 m. wide access road.
- f) Bank Guarantee of requisite amount as prescribed in Clause 12.6
- g) Undertaking and Affidavit as may be prescribed by the Collector.
- h) Copies of Master Layout Plan with or without Building Plans in three sets with sign of owner/developer and architect.
- i) Contour map showing contour levels of lands under Master Layout Plan. Trueness of the contour shall be certified and attested by the surveying agency and the Project Proponent/s under their signature and seal.
- j) Colored satellite google earth image showing lands under Master Layout Plan.
- k) Phased Program for development of **physical** infrastructure with amenities under project.

6.2 If the application is not accompanied by the documents mentioned in Clause 6.1, the Collector shall **return convey** the same to the Project Proponent/s immediately within 10 working days **giving specific time period for fulfilment of such documents and if the same are not submitted by the said project proponent in given time then return the proposal** at his level only.

6.3 On receipt of application, complete in all respects, as prescribed under Clause 6.1, the Collector shall forward the same to the concerned Divisional Joint Director of Town Planning for technical consultation within 10 working days.

6.4 The office of the Divisional Joint Director of Town Planning shall send its remarks to Collector within two months from the receipt of proposal from the Collector or receipt of reply from the Project Proponent/s in respect of any requisition made by him, whichever is later. Such master layout approval will be given with the condition that project proponent will not commence work without environmental clearance. Such environmental clearance shall be submitted at the time of sanction to the building permission. Sanctioned master Plan layout alongwith complete set of drawings shall be endorsed to the concerned branch office of Town Planning Department, for the ~~inspection purpose at the time of Occupancy Certificate~~ **further permissions.**

6.5 Approval to the Master Plan:- The Collector shall grant approval to the master layout or reject the application, under Section 18 of the said Act, within one month from the receipt of reply from the Divisional Joint Director of Town Planning as mentioned in 6.4.

6.6 Approval to the building plan:- Detailed building permission under the master layout plan sanctioned as per clause 6.5 shall be granted by the Assistant Director of Town Planning/Town Planner of concerned Branch within 30 days from the receipt of the proposal from the project proponent as mentioned in 6.6.1.

6.6.1 - The Project Proponent/s shall apply to the concerned head of the Branch office of the Town Planning Department, for grant of building permission, alongwith all relevant documents and attested copy of Environment Clearance for the project from MoEF or the Authority empowered by the MoEF.

6.6.2 - The Project Proponent/s shall submit the certificate of Architect regarding completion of plinth stating that the construction of plinth is as per the approved building Plans to the concerned branch office of the Town Planning along with approved Plan. The Branch Office of the Town Planning verify the same **within stipulated time period**. If it is found that the construction of plinth is not as per the building permission sanctioned, the said office shall reject such plinth checking certificate. In such circumstances, the Project Proponent/s shall **either** demolish the said plinth ~~and also the action against the Project Proponent/s and the concerned architect or get the revised plan sanction according to changes.~~ shall be initiated by the Collector/Appropriate Authority. If it is found that the construction of plinth is as per the building permission sanctioned, then grant the plinth checking certificate is not necessary:-

7. Planning Considerations:-

7.1 Permissibility in respect of Zoning:-

7.1.1 Notwithstanding anything contained in any regulation for the time being in force, the project to be notified under this regulation may be permissible in any land-use zone/s of sanctioned Regional Plan / Development Plan, excepting areas mentioned in Clause 2(iv).

7.1.2 For the areas falling in zones, other than residential, commercial and U1 & U2 zone as per the sanctioned Regional Plan / Development Plan, the Project Proponent/s shall have to pay a premium for permitting project in such zones at the rates prescribed below:-

Sr. No.	Type of Zone	Premium Charges	Revised Premium
a	Afforestation Zone, Hill Top & Hill Slope Zone as shown on Regional Plan / Development Plan ~~subject to clause 2 (ii)~~	20 %	10 %
b	Public / Semi-public Zone, Industrial Zone, TH & LP	10 %	5 %
c	Agriculture/ No Development Zone/G1 zone / Low Density Residential Zone / Buffer Zone of ESZ and other zones excepting at Sr. No. a & b above.	15 %	8 %

(Explanation: Premium charges shall be calculated by considering the agriculture land rate of the said land as prescribed in Annual Statement of Rates (ASR) without applying the guidelines. **If agriculture land rate is not mentioned in ASR, in such cases the premium is calculated considering guideline of ASR for converting into agriculture rate.** Out of total premium 20% **10 %** shall be paid at the time of Locational Clearance, 20% **10 %** paid at the time of letter of Intent, 20 % at the time of sanctioning of Master Layout Plan and remaining 40% **60 %** shall be in four equal instalments per year **and subject to interest as decided by the authority**)

7.1.3 Restriction on development - No construction shall be permitted on the lands within the HFL. ~~Also on~~ Land in Hill Top & Hill Slope Zone and ~~on~~ lands having slope equal to or more than 1:5 in the said Project, whether specifically marked as such on the Regional Plan / Development Plan or not. No development of any sort and activity involving cutting / leveling / filling shall be permissible on such **sloping** lands.

Provided that, it shall be permissible to use such lands for Plantation, Park, Garden purposes, access road to township development with minimum cutting and other users as otherwise permissible in respective Regional Plan / Development Plans and the FSI of such lands shall be permissible to the extent as prescribed in Clause 7.2.

7.1.4. In the Buffer zone of notified ESZ and in ESZ's, only those development activities and FSI as permissible under MoEF notification of the ESZ (as amended from time to time) under Environment Protection Act, 1986 shall be permitted. All the development in this buffer zones shall be in accordance with MoEF notifications.

7.2 Permissible Floor Space Index (FSI):-

7.2.1 Notwithstanding anything contained in any regulation for the time being in force, **if premium as mentioned in 7.1.2 is paid by the proponent then** the basic permissible FSI for such project shall be 1.0 to be calculated on Gross Plot Area under Master Layout Plan without deducting any areas under the slopes, etc. to be calculated on Gross Plot Area.

7.2.2 Further, **additional FSI on payment of premium** built-up area as mentioned below shall be permissible on payment of premium at the rate of 20 % **10%** of the weighted average land rate of the said land as prescribed in Annual Statement of Rates for the relevant year, without applying the guidelines therein. Such premium shall be paid at the time of Building permission.

Area under Township	Additional built-up area on payment of premium
40 hec. and up to 200 Hecor.	Up to 70 % of basic permissible FSI
More than 200 hec. and up to 500 Hecor	Up to 80 % of basic permissible FSI
More than 500 hec. Hecor	Up to 100 % of basic permissible FSI

7.2.3 Over and above the FSI as prescribed above, an additional FSI in lieu of construction of tenements for social housing shall be permissible as prescribed in Clause 9, without charging premium.

7.2.4 It shall be permissible to utilise the maximum permissible built-up area as prescribed above, anywhere in the area under sanctioned Master Layout Plan.

7.3 Mandatory Town-Level Amenities - Area and FSI Allocations:-

Master Layout Plan shall provide for town-level area and FSI allocation, to be kept at one or more places, as follows:-

a) Spaces for Recreation:-

Sr. No.	Particulars	Minimum Area Required	Conditions
i	Garden/s and Parks/s	5% of Master Layout Area.(out of this 50% area may be allowed on Hill Top Hill Slope Zone and Buffer Zone of ESZ)	Out of this at least 1000 sq. mt. area shall be kept open for Town Plaza/Town Square. Such area shall be kept open and may be allowed to be proposed at suitable places. Major public amenities/activities shall be cluster around this area.
ii	Playground/s	7.5% of Master Layout Area (may be allowed in Buffer Zone of ESZ having slope less than 1: 5)	Maximum 10% of area under Play Ground which may accommodate indoor games, stadiums and allied users only.

(Note - These spaces shall be exclusive of open spaces to be required at sector-level layouts. Notwithstanding anything contained in DCR of the authorities, 10% open space shall be provided in sector level layout)

b) Spaces for combined School/s (Primary School/s + High School/s) -

Sr. No.	Particulars	Minimum Area Required	Minimum Built-up Area required
i	For Master Layout area of 40 Ha.	5,000 sq.m.	5,000 sq.m.
ii	For Master Layout area more than 40 Ha.	To be increased proportionately with increase in Master Layout area and be proposed at one or more locations, as per requirements.	

Note-

a) The requirements prescribed above are by considering School to be run in double shift,

b) Requirement of plot area and built up area shall be exclusive of Play Ground spaces. Hence it is mandatory to show separate Play Ground adjoining to school building at the rate of 7 sq. m. / student. 40% area to be kept open for Play Ground purpose

c) Community Health Care Facilities:-

Primary and Secondary Health Care Facilities like Dispensary, Maternity Home, Hospital etc.

Sr. No.	Particulars	Minimum Area Required	Minimum Built-up Area required
i	For Master Layout area of 40 Ha.	1,000 sq. m.	1500 sq. m.
ii	For Master Layout area more than 40 Ha.	To be increased proportionately with increase in Master Layout area and be proposed at one or more locations, as per requirements.	

d) Community Market:-

a) Community Market:			
Sr. No.	Particulars	Minimum Area Required	Minimum Built-up Area required
i	General Market including Mutton and Fish Market		
	For Master Layout area up to & inclusive of 200 Ha.	1000 sq. m.	As per requirement
	For Master Layout area more than 200 Ha.	To be increased proportionately with increase in Master Layout area and be proposed at one or more locations, as per requirements.	
ii	Fish Market & Vegetable Market		
	For Master Layout area up to & inclusive of 200 Ha.	1000 sq. m.	As per requirement
	For Master Layout area more than 200 Ha.	To be increased proportionately with increase in Master Layout area and be proposed at one or more locations, as per requirements.	

Note- Users mentioned in (i) & (ii) above may be clubbed together for convenience purpose, without altering the requirements in plot area and built-up area.

e) Public Assembly Facilities:- Town Hall and/or Auditorium including Library

Sr. No.	Particulars	Minimum Area Required	Minimum Built-up Area required
i	For Master Layout area up to & inclusive of 100 Ha	5000 Sq.mt	5000 Sq.mt
ii	For Master Layout area more than 100 hac. and up to 200 Ha.	10000 sq. mt.	10000 sq. mt.
iii	For Master Layout area more than 200 Ha.	To be increased proportionately with increase in Master Layout area and be proposed at one or more locations, as per requirements.	

f) Economic Activities:-

Economic activities including users such as Market, Multiplex, Mall, Information Technology & Information Technology enabled Services (IT & ITes) including SEZs, Essential Shopping,

Recreational Centers, Trade & Commerce, Education, Hospitals, Non-polluting Industries, Service Industries, Entertainment, Tourism, Star Category Hotels, Convention Centers, Gymnasiums, Socio-economic activities, such as workshop, hostel for Autistic persons and ~~Mentally Retarded~~ **challenged persons old age home etc.** except independent residential tenements, etc. as per requirements.

Sr. No.	Particulars	Minimum Area Required	Minimum Built-up Area required
i	For Master Layout area of 40 Ha.	40000 sq. mtr.	80000 sq. mtr.
ii	For Master Layout area more than 40 Ha.	To be increased proportionately with increase in Master Layout area and be proposed at one or more locations, as per requirements.	

Note-

- i) Users as mentioned in b, c, d, e & f may be clubbed together, in Economic Activities Component, subject to condition that, total built-up area should not be less than the summation of minimum required for all such users, irrespective of their individual plot area requirements.
- ii) The required parking spaces for all such amenities as per norms shall be provided in same plot.

g) Public Utilities:-

For Master Layout area up to & inclusive of 200 Ha.

Sr. No.	Particulars	Minimum Area Required	Permissible Built-up Area
i	Fire Brigade Station-	3000 sq.m. or as prescribed by the Director of Fire Services, Maharashtra State/ Chief fire Officer of the concern Authority.	As per recommendations of the Director of Fire Services, Maharashtra State/Chief fire Officer of the concern Authority.
ii	Sewage Waste Management Project (SWMP)	4000 sq.m.	As per requirements
iii	Cremation Ground	2000 sq.m.	As per requirements
iv	Burial Ground	2000 sq.m.	As per requirements
v	Bus Station / Transport Hub	3000 sq.m.	
vi	Police Station	1000 sq.m.	
vii	Electric Sub-station	As per requirement	
viii	Other Public Utilities	As per requirement	
ix	Public Parking Facilities	As per prevailing DCR	
x	Solid waste management	As per requirement	

Note: i) If the facility of Cremation Ground/ Burial Ground is available in the village where the Township is located in such case these requirements need not be insisted subject to NOCs of respective Gram Panchayat.

- ii) If Police Station is available within 1k.m. area from the proposed Township, then such facility need not to be provided.

h) Transport & Communication:-

- i) The entire area of the project shall be well-knitted with proper road pattern, taking into consideration the linkages with existing roads within the project and outside area as well. All such roads shall be developed by the Project Proponent/s as per standard prescribed by the Indian Road Congress.

ii) The width of the -

- i) Classified Road should not be less than as may be prescribed by concerned public authority;
- ii) Main / Arterial / Ring Road should be minimum right of way of 18 mt.

- iii) Other Sub-Arterial roads, Collector streets, local streets, etc., shall be proposed as per the requirements to cater to the need of occupancies on such roads including for pedestrians.
- iv) Network of cycle track in entire Township area of minimum width of 3 meter shall be provided without clashing **with** the vehicular traffic.
- iii) It may be permissible for Project Proponent/s, to realign the Regional Plan / Development Plan Roads, and earlier existing roads passing through the project area, without changing the entry and exit points of such roads.
- iv) All the Regional Plan / Development Plan Roads and all the Main / Arterial / Ring Roads, shall always be open for general public, irrespective of the fact that, they resides in the project or not.

General Note for Amenities (a) to (h):

- i) The requirements prescribed above for items (a) to (f) are by considering FSI proposed for the project is only 1.0. If the FSI proposed is increased or decreased then the only built up area requirement shall be increased or decreased proportionately.
- ii) The requirements prescribed above for items (g) are for Master Layout area ~~up to & inclusive~~ of 200 Ha. It shall be increased or decreased proportionately and may be proposed at one or more locations, as per requirements.

7.4 Residential Activities:-

Sr. No.	Particulars	Area	Built-up Area
i	Residential Activities (including lands required for social housing, infrastructure such as water storage, drainage and garbage disposal, etc.)	The land excluding the land required for purposes as shown 7.3 (a) to (h).	Remaining built-up area subject to minimum 60% of the total proposed built-up area.

7.5 Share of Local/Planning Authority-

The Integration of Integrated Township Projects included in the Local/Planning Authority, an area @ 2% of the gross area shall be earmarked and shall be handed over free of cost to the respective Authority for Development of the City Level Facilities.

For determining eligibility of ITP, the above 2% area shall be considered in area calculation. This area shall not contain area under hill slopes, and shall be accessible by major road. Base FSI of such 2 % land shall be made available to the applicant on remaining land.

8. Development Control Regulations:-

For those aspects which are not covered under this regulation, the prevailing provisions as prescribed in the Standardised Development Control and Promotion Regulations for Regional Plan / Development Plans in Maharashtra **or DCR of Respective Authorities**, shall apply *mutatis-mutandis*. The provisions of MoEF CRZ notifications amended from time to time shall also be applicable.

However **where in prevailing DCR of the respective authority the maximum height of building is not mentioned in such cases the maximum height** shall be allowed subject to provisions of ~~National Building Code~~ and Maharashtra Fire Prevention and Life safety measures Act 2006 and also any restriction imposed by Chief Fire Officer.

9. Social Housing:-

- 9.1 The Master Layout Plan shall provide sufficient space for construction of small tenements for persons from EWS and LIG categories (hereinafter referred to as the "Social Housing Component"), as a social responsibility with FSI as mention in Clause No 9.3. Out of this Social Housing Component 25 % FSI shall be utilised exclusively for construction of EWS tenements and remaining 75 % FSI shall be used for LIG tenements. Out of the total tenements constructed as Social Housing component, one third (1/3rd) tenements shall be kept for Rental Housing tenements which will be disposed on Rent only by

the project Proponents.

- 9.2 Social Housing tenements shall be constructed with ~~carpet~~ area as specified by the MHADA for EWS and LIG category respectively.
- 9.3 The minimum Social Housing component shall be constructed at 15% of the Residential basic FSI of the area available for Residential Development as prescribed in Clause 7.4 (hereinafter referred to as the "Social Housing component").
- 9.4 Social Housing tenements shall be constructed as per the general and special specifications prescribed by concerned unit of MHADA for their projects.
- 9.5 The Project Proponent/s, after getting commencement certificate of Social Housing component as mentioned above shall immediately intimate to MHADA regarding the numbers of Social Housing Component to be disposed by them to the allottee. Upon such intimation, MHADA within a period of six months, from the date of receipt of such intimation after following procedure of lottery system shall prepare the list of the allottees and forward it to the Project Proponent/s. The project proponent shall dispose of such EWS housing tenements to the allottees ~~at the rate fixed by the MHADA from time to time.~~ **at the construction cost mentioned in ASR applicable of the year of disposal plus 20% additional cost. Out of this 20% additional cost, 10% shall be paid to MHADA towards administration charges.**

If the allottees fails to deposit the amount within specified time limit, then the allotment shall stand cancelled and MHADA can give fresh names of allottees from waiting list within one month.

Provided that if the MHADA is unable to provide the list of the allottee as mentioned above then the project proponent shall dispose of such social housing tenements in the market ~~at the rate fixed by the MHADA from time to time~~ **at the construction cost in ASR applicable to the land of the year of disposal plus 10% additional cost.**

- 9.6 Every Occupation Certificate for the regular tenements shall be granted only alongwith the Occupation Certificate in proportionate with Social Housing component.
- 9.7 Amalgamation of such Social Housing tenements shall not be permitted in any case.
- 9.8 The purchaser of tenement under social housing shall deposit an amount equivalent to 10% of the construction cost of tenement, as prescribed in Annual Statement of Rates prevailing at the time of occupation, with the Project Proponent/s as one-time maintenance deposit for onsite infrastructure maintenance.
- 9.9 The Project Proponent/s shall maintain the premises and common spaces outside the building/s of social housing including concerned all basic infrastructure and amenities, in good condition in the same manner with the maintenance of remaining area of the project.
- 9.10 The purchaser of tenement under social housing shall have to pay all the government taxes, duties like stamp duty, VAT, service tax, etc. at actual, to the Project Proponent/s, as per the requirement, from time to time.

10 Liability of Project Proponent/s:-

- 10.1 The entire project shall be an integrated one with all facilities within the boundaries of such project. All the on-site infrastructure i.e. internal roads, approach road, street lights, water supply and drainage system shall be mandatory and constructed / maintained in future by the Project Proponent/s. Proposed internal roads and Open Spaces in the layouts shall be used only for ITP.
- 10.2 The Regional Plan / Development Plan Roads & Reservations which are included in ITP shall be Developed by project proponent and after development made available to the general public. Such reservations may be allowed to shift within 500 mt. (within Township Area Only) in consultation with Director of Town Planning M. S. Pune.

10.3 It shall be the responsibility of the Project Proponent/s to **develop and maintain** all the infrastructure in good condition **till handing over to the appropriate authority. at his own cost and management, during and after completion of the project.**

Provided that, the Project Proponent/s ~~may~~ **shall** handover the infrastructure, for maintenance purpose, only after the completion of the project, to the Urban Local Body **or appropriate authority**, when constituted in the area comprised by the project **along with the unutilized corpus fund collected for maintenance purpose.**

10.4 Project Proponent/s shall mandatorily provide facilities for making the project SMART -

- i) **For** the people residing in the project area, an efficient and timely public transportation system up to the nearest public transportation station/hub/depot/stand. **He** shall develop **it himself** or tie with Government / Semi Government or private transport agency for such efficient public transportation. The number of buses and trips will be decided by MSRTC / Local Transport Authority.
- ii) Continuous unobstructed footpath of minimum 2 m. width on either sides of all street / roads width ROW 12 m. or more.
- iii) Dedicated and physically segregated bicycle track with a width of 3 mt. or more, should be provided for entire Township Area.
- iv) Pedestrian friendly pathways, encouragement to non-motorized transport, intelligent traffic management, non-vehicle street / zones, smart parking, energy efficient street lighting visible improvement in the area i.e. replacing **existing** overhead electric wiring with underground wiring, encroachment free public areas,
- v) **Arranging** generation of power through non-conventional energy sources like solar, wind and other shall be mandatorily provided with at least 10% of total requirement **of common physical infrastructure of the project;**
- vi) **To provide** energy management by adopting advanced technology like installing Solar Water Heating System, Solar Lamps/Lights in common areas, LED Lamps, auto-operated street lights, solar pumps, etc. all external lighting shall be of LED, Solar Water Heating System, Solar Lamp shall be compulsorily provided;
- vii) **To provide** effective water management by adopting water harvesting techniques like rain water harvesting, recycling of used water, metered water supply to the users under project, double plumbing pipeline .The recycled water shall be used for flush system, gardening, carwash and industrial use;
- viii) **To provide** effective safety & security measures like CCTV surveillance at strategic locations, centralized control room, etc.;
- ix) **Arranging** smart and fast internet/broad band connectivity to all residences, e-governance online system for grievance redressed;
- x) **Encouraging and providing platform for** citizens participations in decision making about public community issues.
- xi) **Arranging** real time environmental monitoring i.e. air pollution, noise pollution etc. shall be observed
- xii) **Encouraging and providing platform for** e-DCR for building plans with BIM, 3-D maps on GIS of the utility services network and properties in the city, central command, control and emergency response center for all infrastructure facilities. Project Proponent/s shall also provide urban design concept plans along with Master Plan.
- xiii) It shall be obligatory on the part of Project Proponent/s to provide ~~and be provided for~~, the infrastructure and green building norms that are necessary as per the guidelines as may be laid down by the Government, under the policy of development of 'Smart City' from time to time.
- xiv) Ensure that the buildings have at least 3 star ratings from GRIHA.

10.5 Project Proponent/s shall also mandatorily provide for:-

- a) Water Supply** - Safe and potable drinking water at the rate of 90 liters per capita per day, exclusive of requirement of water for firefighting and gardening purposes. The storage capacity of the same shall be at least 1.5 times of the actual required quantity as determined by expected population (Resident and Floating) and other uses. The Project Proponent/s would be required to develop proper internal distribution with double pipe plumbing **for reuse of treated water at appropriate places** and maintenance system along with smart metering and shall specially undertake rain water harvesting, groundwater recharging and waste water recycling within the project.

Provided that, the Project Proponent/s should not use groundwater as a source of water, to meet the above requirement.

- b) Drainage and Garbage Disposal:-** The Project Proponent/s shall make suitable and environment friendly arrangements for the disposal and treatment of sewage and solid waste generated in the project at source, as per the norms of the Maharashtra Pollution Control Board. The Project Proponent shall provide zero discharged in ITP for solid as well as liquid based.

The Project Proponent/s should provide facilities for water conservation by different means such as Rain Water Harvesting, Recycling of Waste Water, etc. and also set-up, in the project area itself, the Solid Waste Management Project (SWMP) with a sufficient capacity for processing of 100% garbage and solid waste so that it should be zero liquid discharge to city from the area.

- c) Power:-** The Project Proponent/s shall ensure continuous and quality power supply for the project area. The Project Proponent/s may draw the power from any existing supply system or may go in for arrangement of captive power generation with the approval from the concerned authority. If power is drawn from any existing supply system, the Project Proponent/s shall, before commencement of development, procure a firm commitment of power for the entire Township from the power supply company.

11 Occupancy Certificate and sale permission:-

- 11.1** Application for obtaining the Occupancy Certificate for project, in full or part shall be submitted by Project Proponent/s to the Collector. Such application shall be accompanied by -

- a) All the relevant documents alongwith coloured satellite **Google Earth** image showing the area under Master Layout Plan;
- b) Documents showing compliance of the conditions prescribed while according sanctions from time to time;
- c) Appropriate declaration/s and undertaking/s made by the Project Proponent/s and his technical personnel's;
- d) Any other requirement as may be prescribed by the Collector.

- 11.2** On receipt of application as prescribed under Clause 11.1, the Collector shall forward the same to the concerned branch office of Town Planning Department for technical consultation, within 10 working days.

- 11.3** The concerned branch officer of the Town Planning Department shall send his remarks to the Collector within one month from the receipt of proposal from the Collector or receipt of reply from the Project Proponent/s in respect of any requisition made by him, whichever is later.

- 11.4** The Collector shall grant Occupancy Certificate or reject the application **giving specific reason** within ~~one month~~ **fifteen days** from the receipt of reply from the concerned branch office of Town Planning Department.

- 11.5** The Collector, before issuing the Occupancy Certificate for the project as a whole, shall verify and satisfy himself about the completion of erection / development / construction of all the basic required infrastructure in Master Layout plan. In case, an application for part occupancy, such completion shall be as prescribed in phase programme.

12. General Stipulations:-

12.1 Development of basic infrastructure and amenities shall be completed by the Project Proponent/s to the satisfaction of the Collector either for whole or as per phases, of the project.

12.2 It shall not be mandatory for the Project Proponent/s to provide Amenity Space as otherwise required as per regulation of Regional Plan / Development Plan, if any.

12.3 The Project Proponent/s shall plant indigenous trees at the rate of at least 150 trees per ha. and maintain it properly. The certificate to that effect issued by the Deputy Conservator of Forest or an Officer nominated by him for this purpose shall be produced by Project Proponent/s at the time of application for Final Occupation Certificate under Clause 11.

12.4 ~~In circumstances described in Clause-1,~~ All the powers and functions, that are supposed to be exercised by the Collector under this regulation shall be exercised by the Chief Officer / Chief Executive Officer of the concerned Planning Authority wherever applicable, excepting the powers to grant Letter of Intent under Clause-5 of this regulation.

Provided that, before grant or refusal to the Master Layout Plan, the Chief Officer / Chief Executive Officer of the Authority shall, consult the, concerned Divisional Joint Director of Town Planning as prescribed in Clause-6.3 and 6.4, if the Planning Officer posted in such Authority is below the rank of Joint Director of Town Planning, and to the concerned branch office of Town Planning as prescribed in Clause-6.6 and 11, if the Planning Officer posted in such Authority is below the rank of Assistant Director of Town Planning.

12.5 All the amounts of scrutiny fees, charges, premium etc. payable to the Government shall be deposited with the concerned Branch office of the Town Planning. In circumstances described in proviso of Clause 1 above, 50% of such amount shall be deposited with the concerned Branch office of the Town Planning, and 50% to the concerned Planning Authority.

12.6 The Project Proponent/s shall submit a bank guarantee of an amount equal to the 15% of estimated development cost required for development of the basic **Physical** infrastructure such as roads, water supply, drainage & garbage disposal, **Trunk** installations for power supply, fire brigade station & fire engines. Such development cost be worked out as per respective phases taking into consideration the phased programme for development of infrastructure with amenities under project as submitted and as required under clause 6.1. Certificate regarding estimated development cost shall be produced by the respective Architect of the project.

12.7 The Project Proponent/s shall construct and maintain the Fire Station at their cost. The project proponent post a well-trained staff at fire station as per the recommendations of the Director of Fire Services, Maharashtra State/Chief fire officer of the concerned Authority. The amount of all expenditure on such staff shall be the responsibility of the Project Proponent/s. After completion of fire station and as per requirement such fire brigade/station shall be handed over to the nearest respective authority on the terms and condition decided by the respective authority and project proponent.

12.8 Developer shall complete the Special Township Project within 10 years **or such period as allowed by the Government** from the approval to the master plan. Developer shall develop and maintain the all infrastructure (internal street light, roads etc.) up to the completion of the STP project. Within such **period or till the authority is formed as per clause no.12.9, the concession in property tax levied by the respective Grampanchayat or the respective Planning Authority shall be 66% 50% of normal rate as prescribed under the Grampanchayat Act or under Maharashtra Municipal Council, Nagar Panchayat and Industrial Town ship Act 1965 or Maharashtra Municipal Corporation ACT. Such property tax shall be levied after the actual possession or issuing of Occupancy Certificate whichever is earlier.** Respective Grampanchayat /Planning Authority shall provide mandatory provisions like Birth and Death Registration Certificate etc. for the same period in such STP. Provided that the utilities like fire brigade, police station/chauki etc. shall be handed over to the nearest respective Authority **at the** terms and condition decided by the respective authority.

12.9 A local Authority shall be formed under section 3 read with section 341 of the Maharashtra Municipal Council, Nagar Panchayat and Industrial Town ship Act 1965 according to population of

such town ship. The newly formed respective authority shall take over the operation maintenance of infrastructure in the Integrated Township Project area with the previous approval of Government. However, if the area under ITPs merged in any Local Authority then operation and maintenance of infrastructure in such Integrated Township Project area shall be made by the respective Local Authority.

12.10 Licensing to the Project Proponent/s - The respective Authority shall provide licenses to the Project Proponent/s for telephone Connection, Power and other utilities in the Town ship area. After granting the license from the respective Authority, the project proponent/s shall provide utilities in the Town ship area as per the conditions laid down by the respective authority.

12.11 It shall be mandatory for the Project Proponent/s to provide ~~at least 9 mt. wide~~ **appropriate width of road** to the land not owned by the project proponent which is surrounded by the Township Area

13. Special Concessions:-

13.1 Deemed conversion for Non-Agricultural (N.A.) Use:- The lands under approved Master Layout Plan shall be considered as deemed N.A. No separate permission shall be required under the provisions of Maharashtra Land Revenue Code, 1966. **The amount of nonagricultural assessment shall be exempted to the extent of 50% of the normal rate for the land under Integrated Township Project.**

13.2 Grant of Government land:- The Government land/s, if surrounded **or adjacent** by the lands owned by the Project Proponent/s, may preferably be granted to the Project Proponent/s, as per the rules and regulations to that effect, by the Revenue and Forest Department of the State Government. Maximum 10% of the total area under township shall be allowed to be included in such township.

13.3 Concession in Stamp Duty:- For the purchase of land by project proponent for township area or first transaction, from Project Proponent/s to Purchaser, of any unit under any user, from approved Master Layout Plan or subsequent building plan under this Regulation, concession ~~to the extent of~~ 50% of stamp duty as otherwise required under the Mumbai Stamp Act, shall be granted. **This concession will be available only at one stage i.e. either at the time of land purchase or at the time of sale of units. Also, if the project proponent assigns the rights to his own subsidiary companies for the running of the Amenities in such Township project as per the approved plan in such cases concession of 50 % of stamp duty as otherwise required under the Mumbai Stamp Act, shall be granted.**

13.4 Exemption in payment of Development Charges:- The amount of Development Charges under sub-section (3) of Section 124F of the said Act shall be exempted to the extent of 50% for institution of use or, change of use of any land or building or, development of any land or building, proposed for project undertaken by a Project Proponent/s under this Regulation.

13.5 Relaxation from Mumbai Tenancy and Agriculture Land Act:- The condition that, only the agriculturist will be eligible to buy the agriculture land shall not be applicable to the Project Proponent/s for purchasing agriculture land for Integrated Township under this Regulation.

13.6 Exemption from Ceiling for holding agriculture land:- The limit for holding agriculture land, stipulated in the Maharashtra Agricultural Lands (Ceiling and Holdings) Act, 1961 shall not be applicable to the Project Proponent/s for development of Integrated Township Project under this Regulation.

13.7 Exemption from scrutiny fee:- The amount of scrutiny fee shall be exempted to the extent of **50% of the normal rate for building permission under Integrated Township Project.**

13.8. Exemption from royalty on minor minerals:- The amount of royalty on minor minerals as per the Maharashtra Minor Mineral Extraction (Development and Regulation) Rules shall be exempted to the extent of 50% for the earth which is extracted while developing the land within Township area and fully exempted if the said excavated material is used in the same project.

14. Transition Policy:-

14.1 It shall be permissible for the Project Proponent/s, to whom Special Township Project has already been notified granted location clearance and / or LOI or the project is ongoing wherein part Occupancy Certificate is granted before 26/12/2016 to -

- a) Continue such Integrated Township Project under the erstwhile regulations under which LC is granted **without considering these regulations and for that limited purpose erstwhile regulations for Integrated Township Project shall remain in force;**
- b) If the project proponent wish to develop township according to this regulations then he may apply for grant of Letter of Intent or Master Layout Plan as the case may be **wherever required**, under this regulation and **allow to be developed** ~~subject to payment of premium as prescribed in Clause 7.1 and 7.2, wherever applicable.~~ **The premium already paid may get adjusted as per the percentage mentioned in clause no.7.1 and 7.2 of this regulations.**

14.2 If in case as described in Clause 14.1(b), the construction of the project is on-going and the Occupation Certificate, either in fully or partly has granted or not been granted, it shall be permissible for the Project Proponent/s to choose an option to prefer this regulation subject to payment of premium as prescribed in Clause 7.1 and 7.2. **In such cases premium shall be calculated on balance area.**

15. Appeal: - Anyone aggrieved by an order passed under prevailing byelaws may within forty days of the date of communication of the order prefer an appeal to the Director of Town Planning, Maharashtra State, Pune. The appeal shall be ~~cleared~~ **decided** within 60 days.

16. Control by the State Government - Director of Town Planning M.S Pune is authorised on behalf of Government to monitor the Township Project and submit his report once in six months to Government.

17. Government may relax any provisions from these regulation considering the site condition of the particular project.

18. Read the concern Planning Authority / Special Planning Authority constituted under relevant Acts instead Collector, wherever applicable.

19. The rate of premium mentioned in the Regulation No.7.1.2 and 7.2.2 can be revised by the Government from time to time.

37.0 REGULATION FOR INCLUSIVE HOUSING

37.1 (a) For the sub-division or layout of the land admeasuring **10000 sq.mt.** or more for residential purpose minimum 20% of the net plot area shall have to be provided,

- i) Either in the form of developed plots of 30 to 50 sq.mt. size for Economically Weaker Sections/ Low Income Groups (EWS/LIG), (hereinafter referred to as "affordable plots") in which plots of 30 sq.mt. size shall be kept for EWS; or,
- ii) In the form of equivalent 20% net plot area, for constructing EWS/LIG tenements;

(b) The Land Owner/Developer shall sell the said affordable plots as mentioned at (i and ii) to MHADA at the land rate prescribed in the Annual Statement of Rates prepared by the Inspector General of Registration, Maharashtra State, Pune. If MHADA declines to purchase the same within a reasonable time of six months, then he can sale the affordable plots in the open market.

37.2 For a plot of land, admeasuring **10000 sq.mt.** or more to be developed for a Housing Scheme consisting of one or more buildings (hereinafter referred to as 'the said Scheme'), EWS/LIG Housing in the form of tenements of size ranging between 30 to 50 sq.mt, (hereinafter referred to as 'affordable housing tenements') shall be constructed at least to the extent of 20% of the basic zonal F.S.I., subject to the following conditions:-

- a) The built-up area of the EWS/LIG tenements constructed under the Scheme shall not be counted towards F.S.I.

b) The Land Owner / Developer shall construct the stock of the affordable housing tenements in the same plot and the PMRDA shall ensure that the Occupation Certificate for the rest of the development 'under the said Scheme is not, issued till the Occupation Certificate is issued for the Affordable Housing tenements under the said Scheme.

Provided further that the Affordable Housing tenements of equivalent value as per ASR subject to minimum 20 % of built-up area as per original location may also be provided at some other location (s) within the same village.

c) The Project Proponent/s, after getting the Commencement Certificate for the scheme, shall immediately intimate to MHADA regarding the numbers of **affordable housing tenements** to be disposed by them to the allottee. Upon such intimation, MHADA within a period of six months from the date of receipt of such intimation shall duly after following procedure of lottery system prepare the list of the allottee and forward it to the Project Proponent/s. The project proponent shall dispose of such EWS housing tenements to the allottees at the construction cost in ASR applicable to the land under the Scheme plus 20 % additional cost. Out of this 20 % additional cost, 10 % shall be paid to MHADA towards their administration charges.

d) There shall be no obligation to construct affordable Housing tenements in the redevelopment project of any co- operative Housing Society in which the carpet area of all existing individual residential tenements does not exceed 80 sq.mt.

e) In case of Redevelopment of Individual bungalow these provisions shall not apply. However if redevelopment proposed on area more than 10000 sq.mt. these provisions shall be applicable.

f) There shall be no obligation to construct affordable housing tenements in accordance with these provisions in any Housing Scheme or residential development project wherein, owing to the relevant provisions of the Development Control and Promotion Regulations, 20% or more of the basic Zonal FSI is required to be utilized towards construction of residential tenements for the EWS/LIG and also for the development / redevelopment of any land, owned by the Government or any Semi-Government organization. Provided such development / redevelopment is undertaken by the Government or such Semi- Government Organization by itself or through any other agency under BOT or PPP model.

Provided that in case of Development of reservations of Public Housing, Housing for Dishoused, Public Housing / High Density Housing and the EWS/LIG tenements constructed under the provisions of any other Act, these provisions shall not be applicable.

37.3 Amalgamation of affordable plots / affordable tenements shall not be allowed.

37.4 These provisions shall be applicable prospectively and shall not be applicable to any Housing Scheme or residential development project wherein Commencement Certificate for full area had been issued prior to the date of coming into force of these provisions and was valid on such date. In case of revised approval this provision shall not be applicable. However, in case of part Commencement Certificate or revision of proposal where newly proposed area is more than 10000 sq.mt. then to that extent these regulations shall apply.

38.0 Tourism Development

38.1 The Metropolitan Commissioner, PMRDA shall allow the development of tourism activities as per following terms and conditions.

38.2 These regulations shall be applicable for Tourism Development in No Development Zone as set out herein below.

38.3 Tourism Development Project may be developed by individual or company or partnership firm or Government / Semi-government Organisations / Corporations

38.4 **Size of plot & FSI** – Minimum requirements regarding the size of the plot for Tourism Development Project and other features, shall be as follows:

i) Tourism Development Project shall be granted FSI as permissible as per Table No. 26 of

these regulations.

Table No. 26

No Development Zone		
Total Area	Max. TD Project Area	Max. built up area permissible (FSI)
Area in hectare	Area in hectare	Area in sq. m.
2.0	1.0	5000 square meter
2.00-3.00	1.1	5500 square meter
3.00-4.00	1.2	6000 square meter
4.00-5.00	1.4	7000 square meter
5.00-6.00	1.6	8000 square meter
6.00-7.00	1.7	8500 square meter
7.00-8.00	1.8	9000 square meter
8.00-9.00	1.9	9500 square meter
9.00-10.00	2.0	10000 square meter
Above 10.00	1/5th of the holding	Half of the area of TDZ (0.5 FSI of TDZ area.)

Note:

- After deducting the area of Tourism Development, remaining land in No Development shall be entitled for FSI as permissible in respective zones.
- For plots each more than 2 hectares in area in No Development Zone, no sub-division of plots shall be permitted.

38.4(a) Smaller Plots: - For existing landholders having smaller plots in No Development Zone, the provisions of promotion of tourism through bed & breakfast type of the arrangement for tourism shall be permissible. There shall be the same FSI as in No Development Zone for plots, according to Development Control Regulations.

38.5 Prohibition Tourism Development Project - Lands falling in categories specified below shall not be allowed for Tourism Development projects:

- Lands affected beyond permissible levels by pollution in land, water or air, as may be decided and certified by the Maharashtra Pollution Control Board.
- Areas from No Development Zone directly abutting the Residential Zone without being separated by road having width not less than 18 m.

38.6 Infrastructural Facilities – All the infrastructural facilities required in site as specified by the Metropolitan Commissioner, PMRDA shall be provided by the developer at his own cost on the site. Proper arrangement for treatment and disposal of sewage and sullage and solid waste shall be made to the satisfaction of Metropolitan Commissioner, PMRDA & Maharashtra Pollution Control Board. No untreated effluent shall be allowed to pass into the sea or any waterbody.

38.6(a) Reserved sites for TDZ – Where the lands are located in unique/unusual area, particularly suitable for development of tourism in view of existing water body, scenic beauty, tree plantation or geological formation etc. but are designated/ reserved in the Regional Plan for the purpose of park or gardens or recreation ground or private garden or private recreational ground, it can be specified as Tourism Development Zone. The minimum area of such site, however, shall not be less than 1.00 Ha. The floor space index available for development in such a site shall be 0.20. This FSI is to be consumed on only 15% of the area of the lands declared as Tourism Development Zone; out of the site designated for open user such as Recreation Ground, Parks etc.

38.7 Environment & Education – Places where rare species of migratory birds are known to visit and where there is a heritage of flora & fauna shall be given preference in development of Tourism Development Projects. Actions shall be taken by the developer for creating environmental awareness among the local population & especially among school going children in nearby area as directed by Metropolitan Commissioner, PMRDA.

38.8 In addition to above tourism development shall be permitted as following as per table no. 27 in the Afforestation Zone:

i) Permissible Use

The following building user will be permissible in the Tourism Development Zones (T.D.Z.) as indicated in Table No. 27

- Conventional hotels, including cottages for Tourist.
- Canteens/restaurants and tea stalls including pan and cigarette booths;
- Baths and toilets for camping sites providing for tents/caravans;
- Public utilities and services like information centre, tourist reception centre, telephone booths, first aid centre, structures for recreation purpose such as health farms, water sports facilities, marine jetties and pantoons for docking of boats, swimming pools, boat house, badminton halls and the like.

- ii) Minimum area of plot and maximum built up area etc, should be governed by the rules given in Table No. 27.

Table No. 27

Sub-Zone	Minimum area of plot/land	Maximum built up area (inclusive of temporary structures)	Maximum height of structures
1	2	3	4
1) Tourism Development Zones around lakes (a belt of 500 mtrs from FSL/HFL of Lake)	1 hect. (0.4 hect in case of development by local residents)	F.S.I. of 0.10 in case of tourist resort with minimum 10 rooms accommodation and ancillary users. Provided further that in case of Tourist Resort	1) Within a belt of 100 to 300 mtrs. From HFL/FSL of the Lake only Ground floor structures with maximum height of 5 mtrs with slooping roof.
		Development undertaken by local residents, concessional FSI of total 0.15 will be permitted for their already developed plots comprising extension of existing building. For Farm House/Forest House development 100 sq.mt. per 0.4 hect. Of plot + 50 sq.mt. per 0.4 hect. For ancillary structures	2) Within a belt of 300 to 500 mtrs. From HFL/FSL of the lake Ground + one with maximum 9 mtr. height.

2) Lands falling within the belt of 200 mtrs to 1.5 km from the historical monuments and places of archeological importance.	1 hect. (0.4 hect) in case of development by local residents.	F.S.I. of 0.10 in case of tourist resort with minimum 10 rooms accommodation and ancillary users. Provided further that in case of Tourist Resort Development undertaken by local residents, concessional FSI of total 0.15 will be permitted for their already developed plots comprising extension of existing building. For Farm House/Forest House development 100 sq.mt. per 0.4 hect. Of plot + 50 sq.mt. per 0.4 hect. For ancillary structures	Ground + one with maximum height of 9 mtrs.
3) Afforestation Zones (except Govt. reserved forests) catchment areas of the lake & area in the 500 mt. to 1500 mt. belt around lakes (where low density is essential).	1 hect.	100 sq. mt. per 0.4 hect. of plot + 50 sq. mt. per 0.4 hect. for ancillary structures.	Only Ground floor with maximum height of 5 mt. and sloping roof.

- iii) Tree Plantation: Maximum number of appropriate species of trees, preferably 500 trees per hect. (except where the forest department's certificate is obtained about larger area per tree being required for the selected species) should be given only after a certificate from the competent forest authority about the survival of the required number of trees is obtained.
- iv) Further restrictions about building – No building including temporary structures, nor and camping ground will be permitted in areas having slopes steeper than 1 in 5. Similarly, no structures including temporary structures and tents/caravan sites (except boat house and jetties) will be permitted in the belt of 50 mtrs, from the High Flood Level of lakes and 200 mtrs. From boundary of protected monuments and temples of tourist importance. However, temporary removable ground floor structures including tents, camping grounds may be permitted in the belt of 50 mtrs. to 100 mtrs from HFL/FSL of the lake. Provided further that, no toilet Blocks (Bath, W.C.etc) are allowed within 100 mtrs from HFL/FSL of the lake.
- v) Treatment of effluent etc. – Proper arrangement for treatment and disposal of sewage and sullage and solid wastes shall be made to the satisfaction of the Water Pollution Control Board. No treated/untreated effluent should be allowed to pass into the lake waters.
- vi) Open spaces along all sides – Minimum Open Spaces on all sides shall be 10 mtrs.
- vii) No basement shall be allowed in the construction of Tourist Resorts within the belt of 100 to 500 mtrs. from the HFL of the lake.
- viii) In order to prevent clustered development, a notional plot of minimum 1000 sq. mt. shall be designated to each cottage.
- ix) Other features of buildings- Normal Rules shall apply in respect of building features other than the above. However, the construction shall be consistent with the surrounding landscape and local architectural style.

39.0 Innovative Development Proposals: If any development proposal is submitted by the owner or developer, consisting of new concepts, innovative ideas, then such proposal may be approved by the PMRDA in its Authority meeting, if it is, otherwise, in accordance with the spirit of these regulations.

40.1 Research and Development Centers as approved by the authorities identified by the PMRDA in any Zone excluding Hill Top Hill Slope Zone and Eco sensitive zone shall be allowed on following conditions:

- a) The area of land shall be minimum 2 hectare.
- b) The basic permissible FSI shall be as per residential zone and additional incentive FSI of 100% of basic FSI shall be allowed free of premium.
- c) Out of the total allowable FSI, not more than 25 % shall be used for supplementary activities such as office use, staff Quarters, guest houses, convenience shopping, banking, clinics, library, health facilities and other amenities.
- d) At least 80 trees per hectare shall be planted and maintained.
- e) The violation of any of above (a) to (d) clauses shall lead to cancellation of permission.

40.2 Ropeway Projects: The landings of any rope way approved by competent authority shall be allowed in any excluding hill top hill slope / Eco sensitive zone of the plinth area not exceeding 1000 sq.mt. subject to other compliances and other utilities like water, drainage, sanitation as per these regulations.

The pylons/foundations for the rope way may be allowed as per the structural design requirement on the land / water following in any zone provided that the project proponent holds the rights to erect such structures and also provided that no habitable use is allowed under the pylons.

a) Following users shall be permitted in the landing areas

- i) Ticketing,
- ii) Tourist facilitation center,
- iii) Service facilities/utilities,
- iv) Restaurants/cafes,
- v) Souvenir shops,
- vi) Museums
- vii) Amphitheaters.

40.3 Planetarium / Astronomical / Astrophysical Facilities / Projects:

These facilities may be allowed in any zone excluding Hill Top and Eco sensitive zone. It shall be used as an entertainment and learning center featuring shows about *space* in a domed or any specially designed theatre and *star gazing* and any such similar astronomical and astrophysical facilities for laboratory and large-scale research projects as well as for recreation subject to other compliances and other utilities like water, drainage and sanitation as per these regulations

- i. The area shall be minimum 2 hectares.
- ii. Permissible FSI shall not exceed 0.1.
- iii. There shall be no restrictions on sizing of various functional parts for planetarium / Astronomical / Astrophysical facilities only.

40.4 Trekking Routes / Nature Trails / Nature Walks:

These facilities may be allowed in any zone including Hill Top Hill slope and Eco Sensitive zone. One unit of following users shall be permitted along PMRDA recognized nature treks / nature walks at both the ends in case of minimum length of 10 kms and only at the beginning in case of total length not exceeding 5 kms subject to other compliances and other utilities like water, drainage, sanitation as per these regulations.

- a) Utilities including drinking water, toilets,
- b) First aid cabin,
- c) Emergency log room,
- d) Pantry facility not exceeding 10 sqm.

Provided that for every intermediate 10 kms length of trek one unit of utilities mentioned in (a) above may be permitted.

40.5 Proposed Town Planning Scheme (TPS) Area:

40.5.1 These Regulations shall be applicable for the TP Scheme Notified areas in the PMRDA Area.

41.0 SPECIAL REGULATIONS:

41.1 SPECIAL REGULATIONS FOR DEVELOPMENT OF TOURIST RESORTS/ HOLIDAY HOMES/ TOWNSHIP IN HILL STATION TYPE AREAS: The developments under the Hill Station Policy shall be governed by the Special Regulations as sanctioned by Government vide notification no. TPS-1896-1231-CR-123-96-UD 13, dated 26/11/1996 and its amendments by the Government from time to time.

41.2 SPECIAL REGULATIONS FOR DEVELOPMENTS WITHIN 10 KMS OF TAMHINI GHAT: These regulations shall be governed by the Special Regulations as sanctioned by the Government vide notification no. WLP.2012/C.R. 325/F-1 dated 03/05/2013 and its amendments by the Government from time to time.

42.0 Commercial use of lands owned by Zilla Parishad, Panchayat Samiti & Gram Panchayat:

Notwithstanding anything contained in these Regulations or the Development Plan/Regional Plan, the land owned by Zilla Parishad, Panchayat Samiti & Gram Panchayat (excepting the lands reserved for the appropriate authority other than Zilla Parishad, Panchayat Samiti & Gram Panchayat) shall be allowed to be developed for commercial use up to the maximum extent of 33% of the Floor Space Index available & subject to the general restrictions applicable otherwise to such development & also in accordance with Rural Development and Water Conservation Departments Resolution No. Sankul 2004/ Pra.Kra.54/ Para – 8, dated 30-04-2004 & as may be modified from time to time subject to the following conditions. –

- i) The lands must be owned by Zilla Parishad / Panchayat Samiti / Gram Panchayat as the case may be.
- ii) These lands are not reserved for any other appropriate authority in Development Plan/Regional Plan Town Planning Schemes.
- iii) Independent access of appropriate width shall be separately provided for each commercial user and original user.
- iv) Parking requirement as prescribed for each type of user shall have to be provided

43.0 CONSERVATION OF HERITAGE BUILDINGS / PRECINCTS / NATURAL FEATURES

43.1 Applicability:

This regulation will apply to those buildings, artefacts, structures, areas and precincts of historic and/or architectural and /or cultural significance (hereinafter as “Listed Buildings/Heritage Buildings and listed precincts/Heritage precincts”) and those natural features of environmental significance including sacred graves, hills, hillocks, water bodies (and the areas adjoining the same) etc.

43.2 Preparation of List of Heritage Buildings, Heritage Precincts and Natural Features.

The Metropolitan Commissioner on advice of Heritage Committee shall prepare heritage list and shall issue public notice in the local newspapers declaring his intention to include the buildings, artefacts, areas and precincts of historic and /or cultural significance and the list of natural features of environmental significance, including sacred graves, hills, hillocks, water bodies etc. and invite objections and suggestions from any person in respect of the proposed inclusion within a period of 30 days from the date of such notice.

The Metropolitan Commissioner shall issue notice to the owner of the buildings, artefacts, areas and precincts of historic and/or cultural significance etc. and invite objections and suggestions from such person in respect of proposed inclusion within 30 days from the date of such notice.

The Metropolitan Commissioner, in respect of any objections or suggestions, shall decide the same after giving hearing to the objections and send to the Government for approval. Government will sanction the said heritage list with modification, if required. This list will be called **Final Heritage List**.

Thereafter, the Metropolitan Commissioner may amend the Final Heritage List from time to time as and when required, on the advice of the Heritage Committee. In such case it shall not be necessary to take approval from Government, but the procedure as laid down above in this regulation regarding publication and objection / suggestion shall be followed before finalising it.

43.3 Restriction on development, Redevelopment/repairs etc.

No development or redevelopment or engineering operations or addition, repairs renovation including the painting of buildings, replacement of special features or plastering or demolition of any part thereof of the said listed buildings, or listed precincts or listed natural features shall be allowed except with the prior written permission of the Metropolitan Commissioner. Before granting any such permissions, the Metropolitan Commissioner shall consult the Heritage Conservation Committee to be appointed by the State Government (hereinafter referred to as 'the said Heritage Conservation Committee') and shall act on the advice of the Heritage Conservation Committee.

Provided that before granting any permission for demolition or major alterations/addition to listed buildings (or buildings within listed precincts) objections and suggestions from the public shall be invited and duly considered by the Heritage Conservation Committee.

Provided that, in exceptional cases for reasons to be recorded in writing the Metropolitan Commissioner himself may overrule the advice of the Heritage Conservation Committee.

If the application for development, alteration, modification of the Heritage precincts or listed building is rejected under this regulation or while granting such permission any conditions are imposed on the owner which deprives him to use the FSI, the said owner shall be compensated by grant of Development Right Certificate.

43.4 Incentive uses for Heritage Buildings.

After the commencement of this Regulation, the Heritage Precincts or the Listed Buildings shall not be permitted to be used for any commercial or office purpose except with the permission of the Heritage Conservation Committee. However, in cases of buildings included in the Heritage Conservation List, if the owner /owners agree to maintain the listed Heritage Building as it is in the existing stage and to preserve its heritage with due repairs, the owner/owners may be allowed with the approval of the Heritage Conservation Committee to convert part of the whole of the non-commercial area to commercial /office use. Provided that, if the heritage building is not maintained suitably or if the heritage value of the building is allowed to be spoiled in any manner, the Metropolitan Commissioner shall withdraw the permission forthwith.

43.5 Grant of Transferable Development Rights to owners/lessees of heritage buildings/heritage precincts.

If the owner is deprived of using FSI on the said plot or development permission is granted to him with conditions which deprive him of use of FSI, then he shall be entitled for TDR as decided by the Commissioner in consultation of Heritage Conservation Committee. The utilization of this TDR shall be as per TDR Regulation.

43.6 Maintaining Skyline

Building included in heritage precincts shall maintain the skyline in the precincts (without any high-rise development) as may be existing in the surrounding area, so as not to demolish or destroy the value and beauty of the said heritage buildings/heritage precincts. The development within the precincts shall be in accordance with the guidelines framed by the Metropolitan Commissioner on the advice of the Heritage Conservation Committee.

43.7 Restrictive Covenants

Regulations existing as on date of this Regulation imposed under covenants terms and conditions, on the leasehold plots either by State Government or by the PMRDA shall continue to be imposed, in addition to the Development Control and Promotion Regulations. However, in case of

any conflict with the heritage preservation interest/environmental conservation and the said Development Control and Promotion Regulations, this regulation shall prevail.

43.8 Grading of the listed buildings/Listed Precincts.

The Metropolitan Commissioner shall classify the Heritage Precincts, Heritage Buildings in —Grades□ such as (I),(II), (III). The meaning of these grades and basic guidelines for development permissions are as follows:

Grade-I	Grade-II	Grade-III
(A) Definitions		
Heritage Grade-I comprises Buildings and precincts of National or Historic importance, excellence in architectural style, design technology and material usage and/or aesthetics; associated with a great historic event, personality, movement or institution. They have been and are the prime landmarks of the city and of National importance.	Heritage Grade –II (A and B) comprises buildings and precincts of Regional importance, possessing special architectural or aesthetic merit, or cultural or historical significance though of a lower scale than Heritage Grade-I. They are local landmarks, which contribute to the image and identity of the region. They may be the work of master craftsmen or may be models of proportion and ornamentation or designed to suit a particular climate.	Heritage Grade –III comprises buildings and precincts of local importance for townscape, they evoke architectural, aesthetic, or sociological interest though not as in Heritage Grade –II. These contribute to determine the character of the locality and can be representative of life-style of a particular community or region and, may also be distinguished by setting on a street line or special character of the façade and uniformity of height width and scale.
(B) Objective		
Heritage Grade-I richly deserves careful preservation.	Heritage Grade-II deserves intelligent conservation.	Heritage Grade-III deserves intelligent conservation (though on a lesser scale than Grade-II and special protection to unique features and attributes.)
(C) Scope for Change		
No interventions be permitted either on exterior or interior unless it is necessary in the interest of strengthening and prolonging the life of the buildings or precincts or any part of features thereof. For this purpose absolutely essential and minimum changes would be allowed and they must be in accordance with the original.	Grade-II (A) Internal changes and adaptive reuse and external changes may by and large be allowed but subject to strict scrutiny. Care would be taken to ensure the conservation of all special aspects for which it is included in Heritage Grade-II Grade-II (B) In addition to the above, extension of	External, internal changes and adaptive reuse would by and large be allowed. Changes can include extensions, and additional buildings in the same plot or compound. However any changes should be such that they do not detract from the existing heritage building/precinct.

	Additional building in the same plot or compound, in certain circumstances be allowed, provided that, the extension/additional building is in harmony with (and does not detract from) the existing heritage buildings or precincts especially in terms of height, and facade.	
(D) Procedure		
Development permission for the changes would be given by the Metropolitan Commissioner on the advice of the Heritage Conservation Committee.	Development permission for the changes / additional construction would be given by the Metropolitan Commissioner on the advice of Heritage Conservation	Development permission for the changes / additional construction would be given by the Metropolitan Commissioner on the advice of the Heritage Conservation Committee.
(E) Vistas/ Surrounding Development		
All developments in areas surrounding Heritage Grade-I shall be regulated and controlled by ensuring that it does not mark the grandeur of or view from Heritage Grade-I		

43.9 Signs and outdoor display structures

No display or advertising signs and outdoor display structures on listed building and / or the Heritage Precincts shall be permitted except accordance with part X (sign and outdoor display structure) National Building Code of India.

Prohibition of advertising signs and outdoor display structure in certain cases :

Notwithstanding the provisions mentioned above no advertising sign or outdoor display structures shall be permitted on buildings of architectural aesthetic historic or heritage importance as may be decided by the Metropolitan Commissioner, Committee or on Government buildings, save that in the case of Government buildings only advertising signs or outdoor display structures may be permitted if they relate to the activities for the said buildings' own purposes or related programs.

Provided that, if the Heritage Conservation Committee so advises, the Metropolitan Commissioner shall refuse permission for any sign or outdoor display structure.

43.10 Composition of Heritage Conservation Committee

There shall be Heritage Conservation Committee for the PMR. This Committee shall be constituted by the Metropolitan Commissioner. The committee shall comprise of the following members:

i)	Chairman Appointed by the Government	Chairman
ii)	Divisional/ District officer of Archaeological Survey of India	Member
iii)	Divisional/ District officer of Archaeological Survey of Maharashtra	Member
iv)	Joint Director, Town Planning, Pune Division	Member
v)	Conveyor INTAC Pune Chapter	Member
vi)	Heritage Conservation Architect having 10 years of experience and membership of the Council of Architecture	Member

vii)	Historian having experience of 10 years in the field of History.	Member
viii)	Structural Engineer having experience of 10 years and member of Institution of Engineers.	Member
ix)	Chief Engineer, PMRDA	Member
x)	Metropolitan Planner, PMRDA	Member secretary

The tenure of the Members of categories (vi) to (viii) above shall change after every three years provided however that, the same person shall be eligible for reappointment as Member.

The Heritage Conservation Committee shall come into existence with effect from the date of its publication in the official Gazette.

No act of the Committee done in good faith, shall be deemed to be invalid by reason only of some defect subsequently discovered in the organization of the Committee or in the Constitution of the Committee or in the appointment of the Member or on the ground that such member was disqualified for being appointed.

The Chairman and in his absence the chosen Member of the Committee shall preside over the meeting of the Committee.

43.11 The Terms of reference of the Committee :-

- (i) To consider whether development permission should be granted under this Regulation and the conditions of such permission.
- (ii) To prepare a list or supplementary list of building artefacts, structures, areas precincts of historic aesthetic architectural cultural significance and a supplementary list of natural features of environmental significance including scared groves, hills, hillocks etc. water bodies (and the areas adjoining the same) to which this regulation would apply.
- (iii) To consider whether any relaxation, modification, alteration, or variance of any of the Development Control and Promotion Regulations is called for.
- (iv) To suggest amendments, changes or special regulations or modification to regulations for listed buildings and the heritage precincts regulated under these regulations
- (v) To consider on the extent of Development Rights to be granted to the owners of listed Building of the Heritage Precincts.
- (vi) To consider whether Development Rights Certificates may be allowed to be consumed in a heritage precinct.
- (vii) To consider whether to allow commercial /office user of any listed building of Heritage Precincts and when to terminate the same.
- (viii) To regulate erection of outside advertisement/bill boards.
- (ix) To recommend guidelines to be adopted by those private parties who sponsor beautification schemes at public intersection and elsewhere.
- (x) To evaluate the cost of repairs to be given to the owners to bring the existing building back to the original condition. For this purpose, the Committee may suggest ways to raise funds through private sources.
- (xi) To prepare special designs and elements and guidelines for listed buildings and control of height and essential façade characteristics such as maintenance of the buildings and to suggest suitable design adopting new materials for replacements keeping the old form intact to the extent possible.
- (xii) To prepare guideline relating to design elements and conservation principles to be adhered to and to prepare other guideline for the purpose of this regulation.
- (xiii) To consider any other issue as may be required from time to time during course of scrutiny of development permissions and in overall interest of heritage/environmental conservation.

In the absence of Heritage Conservation Committee, the Metropolitan Commissioner shall accord development permissions based on these Regulations.

43.12 Heritage Conservation Fund

1. Heritage buildings included in the said list shall be maintained by the owners of the said buildings themselves, with a view to give monetary help for such maintenance/repairs a separate fund may be created which would be kept at the disposal of the Metropolitan Commissioner, PMRDA, who will utilise these funds on the advice of the Heritage conservation Committee. The commissioner may, in such cases disburse appropriate amount to the owner or may get maintenance/ repair work done through PMRDA.
2. 2% of total development charges collected shall be transferred to the Heritage conservation fund.
3. The Metropolitan Commissioner shall have right to remove any unauthorized construction in the property enlisted as heritage property as an encroachment for the PMR land and recover the expenses of such removal/ demolition work from the owner as arrears of land revenue.
4. The Metropolitan Commissioner shall have right to enter into any such heritage property to repair such property to avoid any damage or injury, and the amount shall be spent from Heritage Conservation Fund and shall be recovered from the owner as arrears of Land Revenue.
5. If Heritage structure listed in Grade I needs conservation, preservation and immediate repairs and if the structure is affected due to vandalism by occupier/ owner, then the Metropolitan commissioner shall have right to acquire such heritage property and conserve its heritage value.

44.0 Mining or Quarrying Operations: With the prior approval of the Metropolitan Commissioner, PMRDA, Mining or Quarrying operations may be permitted in Agriculture/No Development Zone on following conditions:

- i) In areas within the region such pits and holes created in the process of mining and quarrying should be appropriately filled up and not left open.
- ii) The site shall be restored so as to make it safe either by raising a garden or in addition by planting fruit growing trees around it or by making it a water reservoir.
- iii) Mining & quarrying operation should be in a controlled manner, such as starting operation initially on a site away from crowded areas and later gradually extending it to the other
- iv) Hill tops and hill slopes from which rain water flow should not be allowed to be used for mining and quarrying.
- v) The natural landscape and environment are not to be adversely affected.
- vi) Quarrying shall be regulated in accordance with the method to be prescribed by the Metropolitan Commissioner, PMRDA
- vii) Regulations prescribed by the Revenue authorities regarding the resettlement and restoration of environment shall be strictly followed.
- viii) Quarrying shall not be permitted within 500m from the gaathan / village settlements and from the rivers, forts, historical places and places of tourist interest.
- ix) The conditions prescribed under Maharashtra Minor Mineral Extraction Rules and Regulations shall be observed.

45.0 ERECTION OF MOBILE TOWERS:

Regulation for setting up of Telecommunication Cell Site(s)/Base Station(s) and installation of the equipments for Telecommunication Network in PMR area shall be as per **Appendix-O**.

PART – X

ACQUISITION / DEVELOPMENT OF RESERVED SITES IN REGIONAL / DEVELOPMENT PLAN

46.0 TRANSFERABLE DEVELOPMENT RIGHTS (TDR)

46.1 Transferable Development Rights (TDR) is compensation in the form of Floor Space Index (FSI) or Development Rights which shall entitle the owner for construction of built-up area subject to provisions in this regulation. This FSI credit shall be issued in a certificate which shall be called as Development Right Certificate (DRC).

Development Rights Certificate (DRC) shall be issued by Metropolitan Commissioner under his signature and endorse thereon in writing in figures and in words, the FSI credit in square meters of the built-up area to which the owner or lessee is entitled, the place from where it is generated and the rate of that plot as prescribed in the Annual Statement of Rates issued by the Registration Department for the concerned year.

46.2 CASES ELIGIBLE FOR TRANSFERABLE DEVELOPMENT RIGHTS (TDR):-

Compensation in terms of Transferable Development Rights (TDR) shall be permissible for:

- i) lands under various reservations for public purposes, new roads, road widening etc. which are subjected to acquisition, proposed in Draft or Final Regional/Development Plan, prepared under the provisions of the Maharashtra Regional and Town Planning Act, 1966;
- ii) lands under any deemed reservations according to any regulations prepared as per the provisions of Maharashtra Regional & Town Planning Act, 1966;
- iii) lands under any new road or road widening proposed under the provisions of PMRDA;
- iv) development or construction of the amenity on the reserved land;
- v) unutilized FSI of any structure or precinct which is declared as Heritage structure or Precinct under the provisions of Development Control and Promotion Regulations, due to restrictions imposed in that regulation;
- vi) in lieu of constructing housing for slum-dwellers according to regulations prepared under the Maharashtra Regional & Town Planning Act, 1966;
- vii) The purposes as may be notified by the Government from time to time, by way of, modification to, new addition of, any of the provisions of sanctioned Development Control and Promotion Regulations.

46.3 CASES NOT ELIGIBLE FOR TRANSFERABLE DEVELOPMENT RIGHTS (TDR):-

It shall not be permissible to grant Transferable Development Rights (TDR) in the following circumstances: -

- i) For earlier land acquisition or development for which compensation has been already paid partly or fully by any means;
- ii) where award of land has already been declared and which is valid under the Land Acquisition Act, 1894 or the Right to Fair Compensation & Transparency in Land Acquisition, Rehabilitation and Resettlement Act, 2013 unless lands are withdrawn from the award by the Appropriate Authority according to the provisions of the relevant Acts;
- iii) in cases where layout has already been sanctioned and layout roads are incorporated as Regional/Development Plan roads prior to these regulations;
- iv) in cases where layout is submitted along with proposed Regional/Development Plan Road, in such cases TDR shall not be permissible for the width of road that would be necessary according to the length as per Development Control and Promotion Regulations;
- v) if the compensation in the form of FSI / or by any means has already been granted to the owner;
- vi) where lawful possession including by mutual agreement /or contract has been taken;
- vii) for an existing user or retention user or any required compulsory open space or recreational open space or recreational ground, in any layout;
- viii) For any designation, allocation of the use or zone which is not subjected to acquisition.

46.4 GENERATION OF THE TRANSFERABLE DEVELOPMENT RIGHTS (TDR)

46.4.1 Transferable Development Rights (TDR) against surrender of land: -

- a) For Surrender of the gross area of the land which is subjected to acquisition, free of cost and free from all encumbrances, the owner shall be entitled for TDR or DR irrespective of the FSI permissible or development potential of the very said land to be surrendered and also that of land surrounding to such land at the rate as given below:-

Area Designated on DP	Entitlement for TDR/DR
Non-congested Area	2 times the area of surrendered land.
Congested Area	3 times the area of surrendered land.

(Explanation: Above entitlement may also be applicable to the compensation paid in the form of FSI to the owner to be utilised on unaffected part of same land parcel and in such cases the procedure of DRC shall not be insisted.)

Provided that, if levelling of land and construction/erection of the compound wall / fencing as per Clause No.46.4.1.b to the land under surrender is not permissible as per the prevailing Development Control and Promotion Regulations, the quantum of TDR shall be reduced to 1:1.85 and 1:2.85 in non-congested area and congested area respectively.

Provided also that Additional / incentive Transferable Development Rights (TDR) to the extent of 20 %, 15 %, 10 % and 5% of the surrendered land area shall also be allowed to the land owners who submit the proposal for grant of Transferable Development Rights (TDR) within 1, 2, 3 years and 5 years from the TDR notification respectively.

Provided that the quantum of generation of TDR as prescribed above, shall not be applicable for TDR generated from construction of amenity or construction of reservation/roads, Slum TDR, and Heritage TDR. Also the quantum of Transferable Development Rights (TDR) generated for reservation in CRZ/BDP/HTHS areas or in areas which have some natural or legal constraint on development shall be as decided by the Government separately.

- b) DRC shall be issued only after the land is surrendered to the PMRDA, free of cost and free from encumbrances and after levelling the land to the surrounding ground level and after constructing / erecting a 1.5 m. high compound wall / fencing i.e. brick/stone wall up to 0.60 m. above ground level and fencing above that up to remaining height with a gate, at the cost of the owner and to the satisfaction of the Metropolitan Commissioner. Provided that, if on certain lands such construction / erection of compound wall / fencing is prohibited or restricted by any regulation, then quantum of Transferable Development Rights (TDR) shall be reduced as prescribed in proviso to Clause 46.4.1.a.

Provided further that, such construction / erection of compound wall/ fencing shall not be necessary for area under Regional/Development Plan roads. In such cases TDR equivalent to entitlement as mentioned in Regulation No. 46.4.1.a shall be granted without any reduction.

- c) If any contiguous land of the same owner/developer, in addition to the land under surrender for which Transferable Development Rights (TDR) is to be granted, remains unbuildable, the Metropolitan Commissioner may grant Transferable Development Rights (TDR) for such remaining unbuildable land also if the owner / developer hands it over free of cost and free from all encumbrance and encroachment. If such land is from the proposed roads then such land shall be utilised for road side parking, garden, open space or road side amenities including bus bays, public toilets or any compatible user as the Commissioner may decide and if the such land is from the proposed reservation then same shall be included in such proposed reservation and shall be developed for the same purpose. The Metropolitan Commissioner shall quarterly report such cases to Government.

- d) In case of lessee, the award of Transferable Development Rights (TDR) shall be subject to lessee paying the lessor or depositing with the Planning Authority for payment to the lessor, an amount equivalent to the value of the lessors' interest to be determined by the Planning Authority on the basis of Land Acquisition Act, 1894 or the Right to Fair Compensation and Transparency in Land Acquisition, Rehabilitation and Resettlement Act, 2013 against the area of land surrendered free of cost and free from all encumbrances.

46.4.2 Transferable Development Rights (TDR) against Construction of Amenity-

When an owner or lessee with prior approval of Metropolitan Commissioner, may develop or construct the amenity on the surrendered plot or on the land which is already vested in the Planning Authority, at his own cost subject to such stipulations as may be prescribed and to the satisfaction of the Metropolitan Commissioner and hands over the said developed/constructed amenity free of cost to the Metropolitan Commissioner then he may be granted a Transferable Development Rights (TDR) in the form of FSI as per the following formula:-

$$\text{Construction Amenity TDR in sq.m.} = A/B * 1.25$$

Where,

A= cost of construction of amenity in rupees as per the rates of construction mentioned in Annual Statement of Rates (ASR) prepared by the Inspector General of Registration for the year in which construction of amenity is commenced.

B = land rate per sq.m. as per the Annual Statement of Rates (ASR) prepared by the Inspector General of Registration for the year in which construction of amenity is commenced.

46.5 UTILISATION TRANSFERABLE DEVELOPMENT RIGHTS (TDR):--

- 46.5.1 A holder of DRC who desires to use FSI credit therein on a particular plot of land shall attach valid DRCs to the extent required with his application for development permission. Proposal for Transferable Development Rights (TDR) utilisation shall be submitted alongwith the documents as may be prescribed by the Commissioner or by the Government from time to time.
- 46.5.2 With an application for development permission, where an owner seeks utilisation of DRC, he shall submit the DRC to the Metropolitan Commissioner who shall endorse thereon in writing in figures and words, the quantum of the TDR proposed to be utilised, before granting development permission. Before issuance of Occupation Certificate, the Commissioner shall endorse on the DRC, in writing in figures and words, the quantum of TDR/DRs actually used and the balance remaining if any.
- 46.5.3 The Transferable Development Rights (TDR) generated from any land use zone shall be utilised on any receiving plot irrespective of the land use zone and anywhere in congested or non-congested area earmarked on Regional/Development Plan. The equivalent quantum of Transferable Development Rights (TDR) to be permitted on receiving plot shall be governed by the formula given below:-

$$\text{Formula: } X = (R_g / R_r) \times Y$$

Where, X = Permissible Utilisation of TDR/DR in sq.m. on receiving plot

R_g = Rate for land in Rs. per sq.m. as per ASR of generating plots in generating year

R_r = Rate for land in Rs. per sq.m. as per ASR of receiving plot in generating year

Y = TDR debited from DRC in sq.m.

Provided that, the areas or zones where the utilisation of TDR is permitted shall be declared subject to the availability of urban infrastructure by the Metropolitan Commissioner, PMRDA from time to time with prior approval of the Government. The permissible TDR shall not exceed 0.2 in any case. The additional TDR according to the road width as mentioned in regulation 46.5.4 shall also be permissible with prior approval of Government after publication of Development Plan of PMRDA along with the regulations.

46.5.4 Utilisation of Transferable Development Rights (TDR) and Road Width Relation:-

- 1) Notwithstanding anything contained in any regulation, the total maximum permissible built-up area and utilisation of Transferable Development Rights (TDR) on receiving plot shall be, subject to the road width, as prescribed below:-

Sr. No.	Plots Fronting on Road width	Maximum permissible TDR Loading
1	2	3
1	Below 9mt	0.00
2	9 mt and up to but less than 12mt	0.20
3	12mt and above but less than 15mt	0.30
4	15 mt and above but less than 24 mt	0.40
5	24 mt and above but less than 30 mt.	0.50
6	30 mt and above	0.60

Note:-

- Column No.3 shows the maximum permissible TDR that can be utilised on any plot;
 - Maximum Building potential mentioned in Table No. 4 and 7 Column No.6 shall includes the basic FSI, allowable TDR, Additional FSI if any, Road widening FSI of the very said plot if any. However, the Metropolitan Commissioner shall not grant any relaxation due to such allowable loading potential unless he himself satisfied that there is constraint on development;
 - If a plot is situated on internal road having dead end within 60 mt. from the main road, then such plot shall be treated as fronting on main road for the purpose of utilisation of TDR.
- Provided that, the restrictions of total maximum permissible built up area in terms of FSI with respect to road width mentioned above shall not be applicable in cases where, the permissible FSI is more than the basic FSI in various schemes, like Metro Influence Zone BRTs, TODs etc. where specific provisions which are sanctioned by the Government shall apply.
 - Provided that, the additional FSI permissible in certain categories of buildings such as, Educational building, Registered Charitable Institutional/ Medical / Hospital Building, Star Category Hotel, Religious Building etc. as per prevailing Development Control and Promotion Regulations, if any, can be availed either by full or part utilization of TDR or full or part utilization of additional FSI at the option of owner. However, the restriction of road width mentioned as above shall not be applicable when the owner exercises his option of availing utilization of additional FSI and in such cases limitation of maximum building potential as mentioned above shall not be applicable.
 - The utilisation of Transferable Development Rights (TDR) shall be permissible by considering Gross Plot Area excluding area affected by reservations or deemed reservation, if any.

5) Areas Restricted from Utilisation of Transferable Development Rights (TDR):-

Utilisation of Transferable Development Rights (TDR) shall not be permitted in following areas:-

- a) Agricultural / no development / Green belt/ Afforestation/ HTHS Zone in the Regional Plan provided that lands developable as per Gaothan Expansion and Zone Change Policy shall be eligible for utilization of TDR.
- b) Area within the flood control line i.e. blue line (prohibitive zone) as specified by Irrigation Department.
- d) Where the permissible basic Zonal FSI is less than 0.75.
- e) Area having developmental prohibition or restrictions imposed by any notification issued under the provisions of any Central/State Act (Defence restriction areas etc.) or under these regulations.

46.6 GENERAL STIPULATION:-

46.6.1 Development Rights (DRs) will be granted to an owner or lessee, only for reserved lands which are retainable and not vested or handed over to the Government /Urban Local Bodies and not exempted under section 20 or 21 of the then Urban Land (Ceiling and Regulations) Act, 1976 and undertaking to that effect shall be obtained, before a Development Right is granted. In the case of schemes sanctioned under section 20 or 21 of the said Act, the grant of Development Rights (DRs) shall be to such extent and subject to the conditions mentioned in section-20 scheme and such conditions as the Government may prescribe. In case of non-retainable land, the grant of Development Rights shall be to such extent and subject to such conditions as the Government may specify. The provisions of this Regulation shall be subject to the orders issued by the Government from time to time in this regard.

Provided that, in case of lands having tenure other than Class-I, like Inam lands, tribal lands etc., N.O.C. from Competent Authority, mentioning

- i) share of Government and land holder
- ii) transfer of such land in the name of Planning / Appropriate Authority, shall be produced by the land holder at the time of submission of application for grant of TDR.

46.6.2 DRC shall be issued by the Metropolitan Commissioner as a certificate printed on bond paper in an appropriate form prescribed by him. Such a certificate shall be a —transferable and negotiable instrument□ after the authentication by the Metropolitan Commissioner. The Metropolitan Commissioner shall maintain a register in a form considered appropriate by him of all transactions, etc. relating to grant of, or utilisation of, DRC.

46.6.3 The Metropolitan Commissioner shall issue DRC within 180 days from the date of application or reply from the applicant in respect of any requisition made by him, whichever is later.

46.6.4 Transfer of DRC-

- 1) The Metropolitan Commissioner shall allow transfer of DRC in the following manner
 - i) In case of death of holder of DRC, the DRC shall be transferred only on production of the documents as may be prescribed by him from time to time, after due verification and satisfaction regarding title and legal successor;
 - ii) If a holder of DRC intends to transfer it to any other person, he shall submit the original DRC to the Metropolitan Commissioner with an application alongwith relevant documents as may be prescribed by the Metropolitan Commissioner and a registered agreement which is duly signed by Transferor and Transferee, for seeking endorsement of the new holders name, i.e., the transferee, on the said certificate. The transfer shall not be valid without endorsement by the Metropolitan Commissioner and in such circumstances the Certificate shall be available for use only to the holder /transferor.
- 2) The utilisation of TDR from certificate under transfer procedure shall not be permissible, during transfer procedure.

46.6.5 The Metropolitan Commissioner may refrain the DRC holder from utilizing the DRC in the following circumstances:-

- i. Under direction from a competent Court.

- ii. Where the Metropolitan Commissioner has reason to believe that the DRC is obtained
 - a) by producing fraudulent documents;
 - b) by misrepresentation.

46.6.6 Any DRC may be utilised on one or more plots or lands whether vacant, or already developed fully or partly by erection of additional storeys, or in any other manner consistent with the prevailing Development Control and Promotion Regulations.

46.6.7 DRC may be used on plots/land having Regional/Development Plan reservations of buildable nature, whether vacant or already developed for the same purpose, or on the lands under deemed reservations, if any, as per prevailing Regulations.

46.6.8 Infrastructure Improvement Charges-

The utilizer shall pay to the PMRDA, an infrastructure improvement charges, for a proposed quantum of TDR to be utilised, at the rate of 5% of construction cost as per the prevailing Annual Statement of Rates.

47.0 VESTING OF LAND :-

47.1 The Metropolitan Commissioner, before issuing DRC, shall verify and satisfy himself that the ownership and title of the land proposed for surrender is with the applicant, and get the Record of Right to be corrected in the name of PMRDA.

**PART XI
SUPPLEMENTARY AND MISCELLANEOUS PROVISIONS**

48.0 CLARIFICATION

If any question or dispute arises with regards to interpretation of any of these regulations, the matter shall be referred to the Government, who after considering the matter and after giving hearing to the parties, if necessary, shall give a decision on the interpretation of the provisions of these Regulations. The decision of the Government, on the interpretation of these Regulations, shall be final and binding on the concerned party or parties.

49.0 Power to delegate: The Metropolitan Commissioner, PMRDA may, by an order, delegate any of the powers under these Regulations, exercisable by him, subject to such conditions, as he may consider appropriate, to any officer of the PMRDA not below the rank of Town planner, PMRDA.

50.0 Appeals:

Deleted.

APPENDICES, PROFORMAS AND ANNEXURES

APPENDIX A-1

FORM FOR CONSTRUCTION OF BUILDING OR LAYOUT OF BUILDING / GROUP HOUSING

Application for permission for development under Section 44 / 58 of The Maharashtra Regional and Town Planning Act, 1966.

From _____
(Name of the owner)

To,

The Metropolitan
Commissioner, PMRDA

Sir,

I intend to carry out the under mentioned development in the site/plot of land, on Plot No..... Town and Revenue S.No.....City Survey No.....Mauje situated at Road / Street Society in accordance with Section 44 / 58 of the Maharashtra Regional and Town Planning Act, 1966.

I forward herewith the following plans and statements (Item i to ix) wherever applicable, in quadruplicate, signed by me (Name in block letters) and the Architect / Licensed Engineer / Structural Engineer / Supervisor, (License No.....), who has prepared the plans, designs and a copy of other statements /documents as applicable

- i) Key Plan (Location Plan), (to be shown on first copy of the set of plans)
- ii) Site Plan showing the surrounding land and existing access to the land proposed to be developed; (to be shown on first copy of the set of plans)
- iii) A detailed building plan showing the plan, section and elevations of the proposed development work along with existing structure to be retained/ to be demolished, if any;
- iv) Particulars of development in Form enclosed (to be submitted for development other than individual buildings);
- v) Copy of sanctioned layout plan if any;
- vi) An extract of record of rights, property register card (any other document showing ownership of land to be specified) alongwith consent of co-owners where third party interest is created;
- vii) Attested copy of receipt of payment of scrutiny fees;
- viii) Latest property tax receipt;
- ix) No Objection Certificate(s), wherever required.

I request that the proposed development/ construction may be approved and permission be accorded to me to execute the work.

Signature of the Licensed /
Surveyor/Architect
Name
License No.
Contact No.
Dated

Signature of Owner
Name of Owner
Address of Owner
Contact No.
Dated

FORM GIVING PARTICULARS OF DEVELOPMENT
(Item iv of Appendix A-1)

1.	(a) (i) Full Name of Applicant	-----
	(ii) Address of applicant	-----
	(iii) e-mail ID	-----
	(iv) Contact / Mobile No.	-----
	(b)(i) Name and address of Architect/ licensed Engineer/ Structural Engineer/ Supervisor employed.	-----
	(ii) No. and date of issue of License	-----
2.	(a) Is the plot of, a City Triangulation Survey Number, Revenue Survey Number or Hissa Number of a Survey Number or a Final Plot Number of a Town Planning Scheme or a plot of an approved layout?	
	(b) Please state Sanction Number and Date of Sub-division / Layout	
	(c) Whether the land is situated in Core Area or Outside Core Area?	
3.	(a) What is the total area of the plot according to the ownership document and measurement plan?	-----
	(b) Does it tally with The Revenue/CTS Record	-----
	(c) What is the actual area available on site measured by Architect/licensed Engineer/Structural Engineer / Supervisor? (The permission shall be based on the area whichever is minimum.)	-----
	(d) Is there any deduction in the original area of the plot on account of D.P. Roads, or reservation(s). If so, are they correctly marked on the site plan? Please state the total area of such deductions?	-----
	(e) Is there any water stream in the land? State the area of such land.	
	(e) What is the area remained for development after above deduction(s)?	-----
	(f) What is the area proposed for recreational open space? (in case of land having original holding more than 0.4 hectore) Please mention the area.	
	(g) Whether amenity space as required under Regulation no.13.4 is left? Please mention the area.	
	(f) What is the net plot area as per Regulation no.13.8? (excluding (g) above)	
4.	Are all plans as required under Regulation no.6.2 enclosed?	
5.	(a) In what zone does the plot fall?	-----
	(b) For what purpose the building is proposed? Is it permissible according to the land use	

	classification?	
6.	(a) Is road available as an approach to the land? What is the average existing width of the road? (If the plot abuts on two or more roads, the above information in respect of all roads should be given)	
	(b) Is the land fronting on D.P. road? If so, width of the D.P. road	
	(c) Is the land fronting on National or State highway? If so, is the Building line / control line maintained? Please state the distance.	
	(c) What is the height of the building above the average ground level of the plot?	
	(d) Is it within permissible limit of height specified in Regulation no. 15.9 i.e. 1.5 times of the road width plus front margin?	
	(e) Does height exceed the limit specified in (d) above? If so, is height approved by Director of Fire Services, M.S.?	
7.	Is the land subject to restrictions of blue / red flood line, airport, railway, electric line, land fill sites, archaeology, etc.? Please state the details along with _No objection certificate 'if any.	
8.	(a) If there are existing structures on the plot	
	(i) Are they correctly marked and numbered on the site plan?	
	(ii) Are those proposed to be demolished immediately and hatched in yellow colour?	
	(iii) What is the plinth area and total floor area of all existing structures to be retained? (Please give details confirming to the plan submitted)	
9.	Is balcony area within the permissible limit of 15 %? State said balcony area and area counted in FSI.	
10.	Are double height terrace within the limit of 20%? Are they of supported type? State said double height terrace area and area counted in FSI.	
11.	(a) Please state the total built up area, (existing + proposed + extra balconies + extra double height terraces.)	
	(b) What is the basic permissible F.S.I. of the zone according to front road width?	
	(c) What is the premium FSI proposed to be consumed?	
	(d) What is the area of TDR proposed to be consumed?	
	(e) What is the additional FSI proposed to be consumed?	
	(f) Please state the overall F.S.I. utilised in the proposal?	

	(g) Is built-up area of each flat / unit mentioned on the plan?			
12.	Whether area for inclusive housing is required as per Regulation no.13.7? Please state the details.			
13.	(a) What is the width of the front marginal distance (s)? If the building abuts two or more roads, does the front marginal distance comply with Regulation?			
14.	(a) What is :	Permissible	Proposed	
	(i) the side marginal distance (s)?			
	(ii) the rear marginal distance (s)?			
	(iii) the distance between buildings?			
15.	(a) What are the dimensions of the inner or outer chowk?			
	(b) Is / are room (s) dependent for its light and ventilation on the chowk? If so, are the dimensions of the chowk as required?			
16.	(a) Whether sizes of the rooms comply with the dimensions mentioned in the regulations?			
	(b) Whether use of every room / part mentioned on the plan?			
	(c) Whether every room derives light and ventilation required under the regulations?			
17.	If the height of the building is more than 15 meter above the average ground level, is provision for lifts made?			
	(a) If so, give details of lift.	Passenger Capacity	No. of Lifts	
	(b) Details of Fire Lift.	Passenger Capacity	No. of Lifts	
18.	(a) Does the building fall under purview of Regulation no.6.2.6.1?			
	(b) If so, is fire escape staircase provided in addition to regular staircase?			
	(c) Whether the ramps to the basement are provided leaving 6 m marginal distance for movement of fire fighting vehicle?			
	(d) If podiums are proposed, does it allow the movement of fire fighting vehicle properly?			
19.	(a) What are the requirements of parking spaces under the Regulation no.20? How many are proposed?		Required	Proposed
		Car		
		Scooter		
		Cycle		
	(b) (i) Are loading-unloading spaces necessary?			
	(ii) If so, what is the requirement?			
	(iii) How many are proposed?			

20.	Is the sanitary arrangement provided as per the regulation?	
21.	Details of the source of water to be used in the construction	
22.	Distance from the sewer.	
23.	Please explain in detail in what respect the proposal does not comply with the Development Control and Promotion Regulations and the reasons there for, attaching a separate sheet if necessary.	

I hereby declare that I am the Architect/ licensed Engineer/ Structural Engineer/ Supervisor employed for the proposed work and that the statements made in this form are true and correct to the best of my knowledge.

Date : / /

Signature of the Architect/ licensed Engineer/ Structural Engineer/ Supervisor employed.

FORM OF STATEMENT 1 (to be printed on plan) [Sr. No. 8 (a) (iii)] Existing Building to be retained				
Existing Building No.	Floor No.	Plinth Area	Total Floor Area of Existing Building	Use / Occupancy of Floors.
(1)	(2)	(3)	(4)	(5)

FORM OF STATEMENT 2 (to be printed on plan) [Sr. No. 11 (a)] Proposed Building							
Building No.	Floor No.	Total Built-up Area of floor.	Balcony area within 15%	Excess balcony area counted in FSI.	Double height terrace area within 20%	Excess Double height terrace area counted in FSI.	Total FSI (3+5+7)
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)

FORM OF STATEMENT 2 (to be printed on plan) [Sr. No. 11 (g)] Area details of Flat / unit						
Building No.	Floor No.	Flat / unit No.	Built up area of flat / unit along with Share of Common areas like staircase / passages	Area of Balcony attached to flat / unit	Area of Double height terraces attached to flat / unit	Total area of flat / unit (4 + 5 + 6)
1	2	3	4	5	6	7

Note :

1) Built up area of all flats / units on the respective floor shall tally with the total built up of that floor.

2) Above statements may vary, wherever required.

PROFORMA - I		
(At Right Hand top Corner of Plans)		
PROPOSED ----- COMPLEX ON C.T.S. NO./PLOT NO. / S.NO. / F.P.NO.----- OF VILLAGE MAUJE -----		Drawing Sheet No. X/Y
Stamps of Approval of Plans:		
A	AREA STATEMENTS	
1.	Area of plot (Minimum area of a, b, c to be considered)	
	a) As per ownership document (7/12, CTS extract)	
	b) as per measurement sheet	
	c) as per site	
2.	Deductions for	
	(a) Proposed D.P./ D.P. Road widening Area	
	(b) Any D.P. Reservation area	
	(Total a+b)	
3.	Gross Area of Plot (1-2)	
4.	Recreational Open space	
	(a) Required	
	(b) Proposed	
5.	Amenity Space -	
	(a) Required -	
	(b) Proposed -	
6.	Service road and Highway widening	
7.	Internal Road area	
8.	Net Area of Plot = [3 - 5(b)]	
9.	Built up area with reference to Basic F.S.I. as per front road width (sr. no. 8 X 1.1)	
10.	Addition of area for F.S.I.	
	(a) In-situ area against D.P. road [1.85x sr. no. 2 (a)], if any	
	(b) In-situ area against Amenity Space [2.00 or 1.85 x sr. no. 5 (b)],	
	(c) Premium FSI area (subject to maximum of 0.3 of sr. no. 8)	
	(d) TDR area	
	(e) Additional FSI area under chapter VIII	
	(Total of a+b+c+d+e)	
11.	Total area available (9+10)	
12.	Maximum utilization of F.S.I. Permissible as per Road width (as per Regulation no. 15.4)	
13.	Total Built-up Area in proposal. (excluding area at Sr.No. 15.b)	
	a) Existing Built-up Area.	
	b) Proposed Built-up Area	
	c) Excess Balcony area counted in F.S.I.	
	d) Excess Double Height terraces area counted in F.S.I.	
	Total (a+b+c+d)	
14.	F.S.I. Consumed (13/8) (should not be more than serial no. 12 above.)	
15.	Area for Inclusive Housing, if any	
	a) Required (20% of sr.no.9)	
	b) Proposed	

Certificate of Area:

Certified that the plot under reference was surveyed by me on _____ and the dimensions of sides etc. of plot stated on plan are as measured on site and the area so worked out tallies with the area stated in document of Ownership/ T.P. Scheme Records/ Land Records Department/City Survey records.

Signature

(Name of Architect/Licensed Engineer/Supervisor.)

Owner's declaration –

I/We undersigned hereby confirm that I/We would abide by plans sanctioned by PMRDA. I/We would execute the structure as per sanctioned plans. Also I/We would execute the work under supervision of proper technical person so as to ensure the quality and safety at the worksite.

Owner (s) name and signature

Architect/ Licensed Engineer/ Supervisor name and signature

Job No.	Drawing No.	Scale	Drawn by	Checked by	Registration / License no. of Arch./ Lic.Eng./ Supervisor

APPENDIX A-2

FORM FOR SUB-DIVISION OF LAND AS PLOTTED LAYOUT

Application for permission for development under Section 44 / 58 of The Maharashtra Regional and Town Planning Act, 1966.

From

(Name of the owner)

To,

The Metropolitan
Commissioner, PMRDA.

Sir,

I intend to carry out the under mentioned development in the site/plot of land, bearing S.No./Gut No. City Survey No....., Mouje, situated at Road/ Street in accordance with Section 44/58 of The Maharashtra Regional and Town Planning Act, 1966.

I forward herewith the following plans and statements (Item 1 to 6) wherever applicable, in quadruplicate, signed by me (Name in block letters) and the Architect / Licensed Engineer / Structural Engineer / Supervisor (License No.....), who has prepared the plans, designs and a copy of other statements /documents as applicable (Items 7 to 10).

- (1) Key Plan (Location Plan);(to be shown on first copy of the set of plans)
- (2) Site Plan showing the surrounding land and existing access to the land included in the layout;(to be shown on first copy of the set of plans)
- (3) A layout plan showing,
 - (i) sub-divisions of the land or plot with dimensions and area of each of the proposed sub-divisions and its use according to prescribed regulations;
 - (ii) width of the proposed streets; and
 - (iii) dimensions and area of recreational open spaces provided in the layout.
 - (iv) dimensions and area of amenity space provided in the layout.
- (4) An extract of record of rights property register card (any other document showing ownership of land to be specified) alongwith consent of co-owners where third party interest is created.
- (5) Particulars of development in Form enclosed.
- (6) Attested copy of Receipt for payment of scrutiny fees.
- (7) No Objection Certificate, wherever required.

I request that the proposed layout may please be approved and permission accorded to me to execute the work.

Signature of the Licensed /
Surveyor/Architect

Name

License No.

Contact No.

Dated

Signature of Owner

Name of Owner

Address of Owner

Contact No.

Dated

**FORM GIVING PARTICULARS OF DEVELOPMENT
(PART OF APPENDIX 1.....ITEM 5)**

1.	(a) (i) Full Name of Applicant	
	(ii) Address of applicant	
	(iii) e-mail ID	
	(iv) Mobile No.	
	(b) (i) Name and address of Architect/licensed Engineer employed.	
	(ii) No. and date of issue of License	
2.	(a) Is the plot of, a City Triangulation Survey Number, Revenue Survey Number or Hissa Number of a Survey Number or a Final Plot Number of a Town Planning Scheme?	
	(b) Whether the land is situated in Core Area or Outside Core Area?	
3.	(a) What is the total area of the plot according to the ownership document and measurement plan?	
	(b) Does it tally with the Revenue/CTS Record	
	(c) What is the actual area available on site measured by Architect/ licensed Engineer/ Structural Engineer / Supervisor? (The permission shall be based on the area whichever is minimum.)	
	(d) Is there any deduction in the original area of the plot on account of D.P.Roads, or reservation(s). If so, are they correctly marked on the site plan? Please state the total area of such deductions?	
	(e) Is there any water stream in the land? State the area of such land and state whether it is excluded?	
	(e) What is the area remained for development after above deduction(s)?	
	(f) What is the area proposed for recreational open space? (in case of land having original holding more than 0.4 hector) Please mention the area.	
	(g) Whether amenity space as required under Regulation no.13.4 is left? Please mention the area.	
	(f) What is the net plot area as per Regulation no.13.9? (excluding (g) above)	
5.	Are all plans as required under Regulation no.6.2 enclosed?	
6.	(a) In what zone does the plot fall?	
	(b) For what purpose the layout is proposed? Is it permissible according to the land use classification?	
7.	(a) Is road available as an approach to the land? What is the average existing width of the road? (If the plot abuts on two or more roads, the above information in respect of all roads should be given)	

	(b) Is the land fronting on D.P. road? If so, width of the D.P. road	
	(c) Is the land fronting on National or State highway? If so, is the Building line / control line maintained? Please state the distance.	
8.	Is the land subject to restrictions of blue / red flood line, airport, railway, electric line, land fill sites, archaeology, etc.? Please state the details along with 'No objection certificate' if any.	
9.	Whether the internal roads proposed in the layout conform to the Regulation no.12.	
10	Whether roads in the layout are co-ordinated with the roads in the surrounding layout?	
11	Whether the area and dimensions of plots are proposed as per prescribed regulations?	
11.	Whether area for inclusive housing is required as per Regulation no. 13.7? Please state the details.	

I hereby declare that I am the Architect/ licensed Engineer employed for the proposed work and that the statements made in this form are true and correct to the best of my knowledge.

Date : / /

Signature of the Architect/ licensed Engineer/
Structural Engineer/ Supervisor employed.

PROFORMA - I

(At Right Hand top Corner of Plans)

**PROPOSED ----- LAYOUT ON C.T.S. NO./PLOT NO. / S.NO. /
F.P.NO.----- OF VILLAGE MAUJE -----**

**Drawing Sheet
No.**

X/Y

Stamps of Approval of Plans:

A AREA STATEMENTS

1. Area of land

(Minimum area of a, b, c to be considered)

- a) As per ownership document (7/12, CTS extract)
- b) as per measurement sheet
- c) as per site

2. Deductions for

- (a) Proposed D.P./ D.P. Road widening Area
- (b) Any D.P. Reservation area

(Total a+b)

3. Gross Area of Plot (1-2)

4. Recreational Open space

- (a) Required -
- (b) Proposed -

5. Amenity Space

- (a) Required -
- (b) Proposed -

6. Service road and Highway widening

7. Internal Road area

8. Area under layout plots

9. Net area of plots for FSI Calculations = (3-5b)

10. Permissible FSI factor for layout plots = (9/8)

11. Area for inclusive housing

- (a) Required -
- (b) Proposed -

Certificate of Area:

Certified that the plot under reference was surveyed by me on _____ and the dimensions of sides etc. of plot stated on plan are as measured on site and the area so worked out tallies with the area stated in document of Ownership/ T.P. Scheme Records/ Land Records Department/City Survey records.

Signature

(Name of Architect/License Engineer/Supervisor.)

Owner (s) name and signature

Architect/ Licensed Engineer/ Supervisor name and signature

Statement of distribution of FSI on each plot (to be printed at suitable place on plan)							
Plot no.	Plot area (sq.m.)	Rounding area of Road (if any) (sq.m.)	Remaining Plot area (b-c) (sq.m.)	Built up area on pro-rata basis i.e. (d x Pro-rata FSI factor)	Front Road width (m.)	basic FSI	Permissible Built-up area on Basic FSI (e x g) (sq.m.)
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)

APPENDIX 'B'

FORM FOR SUPERVISION

To,

The Metropolitan
Commissioner PMRDA.

Sir,

I hereby certify that the development/erection/re-erection/demolition or material alteration in/ or Building No _____ on / in Plot No. _____ in Block No. _____ situated at Road / street _____ City Survey No. _____ shall be carried out under my

supervision and I certify that all the materials (types and grade) and the workmanship of the work shall be generally in accordance with the general specifications and that the work shall be carried out according to the sanctioned plans. I shall be responsible for the execution of the work in all respects.

Signature and name of the Architect or Licensed _____
Engineer/Structural Engineer/ Supervisor

License No. _____

Date :

APPENDIX 'C'

QUALIFICATION, COMPETENCE, DUTIES AND RESPONSIBILITIES ETC. OF LICENSED TECHNICAL PERSONNEL OR ARCHITECT FOR PREPARATION OF SCHEMES FOR DEVELOPMENT PERMISSION AND SUPERVISION

C-1	General
C-1.1	The qualifications of the technical personnel and their competence to carry out different jobs for building permit and supervision for the purpose of licensing by the Authority shall be as given in Regulation no. C-2 to C-6. The procedure for licensing the technical personnel is given in Regulation no.C-6.
C-2	ARCHITECT
C-2.1	Qualifications- The minimum qualifications for an architect shall be the qualifications as provided for in the Architects Act, 1972for registration with the Council of Architecture. Such registered Architects shall not be required to again register their names with the PMRDA. However, he shall submit the registration certificate to the PMRDA.
C-2.2	Competence of Architect: To carry out work related to development permission as given below and shall be entitled to submit - (a) All plans and information connected with development permission. (b) Structural details and calculations for building on plot upto 500 sq. m. and upto 3 storeys or 11 m. height and (c) Certificate of supervision and completion for all buildings.
C-3	A)ENGINEER
C-3.1	Qualifications- 1) The qualifications for Licensing Engineer will be the corporate membership (Civil) of the Institution of Engineers or such Degree or Diploma in Civil or Structural Engineering or equivalent; 2) Diploma in Civil Engineering or equivalent, having experience of 10 years in the field of land and building planning.
C-3.2	Competence- To carry out work related to development permission as given below and shall be entitled to submit- (a) All plans and related information connected with development permission. (b) Structural details and calculations for building on plot upto 500 sq.m. and upto 3 storeys or 11 m.height, and (c) Certificate of supervision and completion for all building.
C-4	STRUCTURAL ENGINEER
	C-4.1 Qualifications- Qualifications for Licensing of structural engineers shall be as given below, with minimum 3 years of experience of structural engineering practice in designing and field work; (a) Graduate in Civil Engineering of recognised Indian or Foreign University and Chartered Engineer or Associated Member in Civil Engineering Division of Institution of Engineers (India)

	or equivalent Overseas Institution; and (b) Shall have post graduate degree in structural engineering. In the case of doctorate in structural engineering the experience shall not be required.		
C-4.2	Competence —he shall be entitled to submit the structural details and calculations for all buildings and supervision.		
C-4.2.1	Complicated buildings and sophisticated structures, as decided by the Metropolitan Commissioner, which are not within the horizontal areas and vertical limits under C-2.2 (b), C-3.2 (b), C-5.2 (a) (i) & C-5.2 (b) (i) shall be designed only by Structural Engineer.		
C-5	SUPERVISOR:		
C-5.1	Qualification (a) For Supervisor 1 :- (i) Three years architectural assistantship or intermediate in architecture with two years' experience, or (ii) Diploma in Civil engineering <i>or equivalent qualifications</i> with two years' experience. (iii) Draftsman in Civil Engineering from ITI or equivalent qualifications with Ten years' experience out of which five year shall be under Architect/Engineer. (b) For Supervisor - 2:- (i) Draftsman in Civil Engineering from ITI <i>or equivalent qualifications</i> with five years' experience under Architect / Engineer.		
C-5.2	Competence (a) For Supervisor-1: he shall be entitled to submit - (i) All plans and related information connected with development permission on plot upto 500 sq.m.; and (ii) Certificate of supervision of buildings on plot upto 500 sq. m. and completion thereof. (b) For Supervisor-2 : he shall be entitled to submit - (i) All Plans and related information upto 200 sq. m. built up area, and (ii) Certificate of supervision for limits at (i) above and completion thereof.		
C-6.	LICENSING-		
C-6.1	Technical Personnel to be licensed:- The Qualified technical personnel or group as given in regulations; No C-3, C-4, C-5 shall be licensed with the authority and the license shall be valid for three calendar years ending 31 st December after which it shall be renewed annually or every three years.		
C-6.2	Fees for Licensing- The annual licensing fees shall be as follows:-		
	For Engineer and structural Engineer	1000 p.a.	
	For supervisor (1)	500 p. a.	
	For supervisor (2)	300 p. a	
	The Metropolitan Commissioner may revise above fees from time to time, if necessary.		

C-6.3	Duties and Responsibilities of Architects / Licensed Technical Personnel: The duties and responsibilities of architects / licensed technical personnel shall be as follows:- (1) It will be incumbent on every architect / licensed technical personnel, in all matters in which he may be professionally consulted or engaged, to assist and co-operate with the Metropolitan Commissioner and other Officers in carrying out and enforcing the provisions of Maharashtra Regional & Town Planning Act, 1966 and of any regulations for the time being in force under the same. (2) Every architect / licensed technical personnel shall be responsible for due compliance with the provisions of Maharashtra Regional & Town Planning Act, 1966 and of any regulations for the time being in force under the said Act. It shall be obligatory on him to satisfy himself that a qualified and competent Mistry or Inspector of Works is constantly employed and present on the work to supervise the execution of all work and to prevent the use of any defective material therein and the improper execution of any such work. (3) Every architect / licensed technical personnel shall be responsible for carrying out work according to sanctioned plan. (4) Every architect / licensed technical personnel shall be responsible for correctness of the calculations and dimensions mentioned on the plan and shall be liable for consequences arising thereof. (5) Architect / licensed technical personnel shall not involve himself in any unauthorised development. He shall also make aware the client about legal provisions in respect of proposed development and consequences thereof. (6) When an architect / licensed technical personnel cease to be in the employment for the development work, he shall report the fact forthwith to the Metropolitan Commissioner.
---------------------	---

APPENDIX 'D-1'

**FORM FOR SANCTION OF BUILDING PERMISSION AND
COMMENCEMENT CERTIFICATE**

To,

Sir,

With reference to your application No _____, dated _____ for the
grant of sanction of Commencement Certificate under Section 44 of The Maharashtra Regional and Town
Planning Act, 1966 to carry out development work / Building on Plot No _____ Revenue Survey
No _____, City Survey No _____,
mauja _____ situated at Road /Street _____, Society _____ the

Commencement Certificate/Building Permit is granted under Section 45 of the said Act, subject to the
following conditions:

1. The land vacated in consequence of the enforcement of the set-back rule shall form part of the public street.
2. No new building or part thereof shall be occupied or allowed to be occupied or used or permitted to be used by any person until occupancy permission has been granted.
3. You will have to handover the amenity space to the PMRDA before approval of final layout as per Regulation no.13.4. (wherever applicable)
4. You will have to submit an undertaking in respect of recreational open spaces as stipulated in Regulation.(wherever applicable)
5. The Commencement Certificate/ Building permit shall remain valid for a period of one year commencing from the date of its issue unless the work is not commenced within the valid period.
6. This permission does not entitle you to develop the land which does not vest in you.
7. -----
8. -----
9. -----

Office No.

Office Stamp

Date :

Yours faithfully,

Metropolitan Commissioner,
Pune or an officer appointed by

him

APPENDIX 'D-2'

FORM FOR TENTATIVE APPROVAL FOR DEMARCATION OF LAND / SUB-DIVISION LAYOUT

To,

Sir,

With reference to your application No., dated _____ for the land sub-division approval, under Section 44 of The Maharashtra Regional and Town Planning Act, 1966 to carry out development work in respect of land bearing Revenue Survey No _____, City Survey No _____, mauje _____ situated at Road _____/Street _____, Society _____, it is to inform you that, land sub-division layout is hereby tentatively approved and recommended for demarcation, subject to the following conditions:

1. You will get the land sub-division layout demarcated on the site by the Land Records Department and submit the certified copy to that effect for final approval.
2. It shall be the responsibility of the owner to carry out all the development work including construction of roads, sewer lines, water supply lines, culverts, bridges, street lighting, etc. and hand it over to the PMRDA after developing them to the satisfaction of the Metropolitan Commissioner.
3. If you wish that the PMRDA has to carry out these development works, then you will have to deposit the estimated expenses to the PMRDA in advance, as decided by the Metropolitan Commissioner.
4. You will have to handover the amenity space to the PMRDA before approval of final layout as per Regulation no.13.4. (applicable in case where owner is not allowed to develop)
5. You will have to submit an undertaking in respect of recreational open spaces as stipulated in Regulation.
6. This permission does not entitle you to develop the land which does not vest in you.
7. -----
8. -----

Office No.

Office Stamp

Yours faithfully,

Metropolitan Commissioner,
Pune or an officer appointed by
him

APPENDIX 'D-3'

FORM FOR FINAL APPROVAL TO THE LAND SUB-DIVISION / LAYOUT

To,

Sir,

With reference to your application No. _____, dated _____ for the land sub-division approval, under Section 44 of The Maharashtra Regional and Town Planning Act, 1966 to carry out development work in respect of land bearing Revenue Survey No _____, City Survey No _____, mauje _____ situated at Road /Street _____, Society _____, the land sub-division layout is finally approved as demarcated under Section 45 of the Maharashtra Regional & Town Planning Act, 1966, subject to the following conditions:

1.	It shall be the responsibility of the owner to carry out all the development work including construction of roads, sewer lines, water supply lines, culverts, bridges, street lighting, etc. and hand it over to the PMRDA after developing them to the satisfaction of the Metropolitan Commissioner.
2.	If you wish that the PMRDA should carry out these development works, then you will have to deposit the estimated expenses to the PMRDA in advance, as decided by the Metropolitan Commissioner.
3.	As per the undertaking submitted by you in respect of recreational open space as stipulated in Regulation no.13.3, the said open space admeasuring ----- sq.m. stand vested in the name of plot holders of the layout or society of the plot holders and you have no right of ownership or interest in the said recreational open space.
	Since you have handed over the amenity space to the PMRDA, you shall be entitled for FSI equivalent to TDR, on the remaining land. (wherever applicable)
4.	This permission does not entitle you to develop the land which does not vest in you.
5.	-----
6.	-----
7.	-----
8.	-----

Office No. -----Office Stamp

-----Date : -----

Yours faithfully, Metropolitan

Commissioner, Pune
or an officer appointed by him

APPENDIX 'E-1'

FORM FOR REFUSAL OF BUILDING PERMIT / COMMENCEMENT CERTIFICATE

To,

Sir,

With reference to your application No. _____ dated _____ for the grant of sanction for the development work / the erection of a building / execution of work on Plot No. _____, Revenue Survey No. _____, City Survey No. _____, mauje _____, I regret to inform you that the proposal has been refused under Section 45 of the Maharashtra Regional and Town Planning Act, 1966, on the following grounds.

1. -----
2. -----
3. -----
4. -----
5. -----
6. -----

Office Stamp

Yours faithfully,

Metropolitan Commissioner,
Pune or an officer appointed by

him

APPENDIX 'E-2'

FORM FOR REFUSAL OF LAND SUB-DIVISION / LAYOUT

To,

Sir,

With reference to your application No. _____ dated _____ for the grant of sanction for the development work bearing Revenue Survey No. _____, City Survey No. _____, mauje _____, I regret to inform you that the proposal has been refused under Section 45 of the Maharashtra Regional and Town Planning Act, 1966, on the following grounds.

1. -----
2. -----
3. -----
4. -----
5. -----
6. -----

Office Stamp

Yours faithfully,

Metropolitan Commissioner,
Pune or an officer appointed by
him

APPENDIX 'F'

FORM FOR INTIMATION OF COMPLETION OF WORK UPTO PLINTH LEVEL

To,

The Metropolitan
Commissioner, PMRDA

Sir,

The construction up to plinth / column up to plinth level has been completed in Building No _____Plot No_____, Revenue Survey No._____, City Survey No._____, Village_____Sector No._____,Ward No._____, situated at Road/Street_____,Society_____in accordance with your permission No_dated _____under my supervision and in accordance with the sanctioned plan.

Please check the completed work and permit me to proceed with the rest of the work.

Yours faithfully

Signature of Architect /Licensed Engineer/
Structural Engineer/Supervisor

Name : _____

(In Block Letters)_____

Address : _____

E-mail ID : _____

Mobile No.: _____

Date: _____

APPENDIX 'G'

FORM OF APPROVAL / DISAPPROVAL OF DEVELOPMENT WORK UPTO PLINTH LEVEL

To,

Sir,

Please refer to your intimation No _____ dated _____

regarding the completion of construction work upto plinth / column upto plinth level in Building No

_____ Plot No _____, Revenue Survey No. _____, City Survey No. _____,
Village _____ Sector No. _____ Ward No. _____, situated at _____ Road/Street
_____, Society _____ You may proceed / are not allowed to proceed with the further
work as per sanctioned plans / as the construction upto plinth level does / does not confirm to the sanctioned
plans.

Yours faithfully,

Metropolitan Commissioner,
PMRDA

Office _____ No _____

Office _____ Stamp _____

Date : _____

APPENDIX 'H'

FORM FOR COMPLETION CERTIFICATE

To,

The Metropolitan Commissioner,

PMRDA

Sir,

I hereby certify that the erection / re-erection or part/ full development work in / on building / part building No _____ Plot No _____, Revenue Survey No. _____, City Survey

No. _____, mauje _____, has been supervised by me and has been completed on _____ according to the plans sanctioned, vide office communication No _____ dated _____. The work has been completed to the best of my satisfaction. The workmanship and all the materials (type and grade) have been strictly in accordance with general and detailed specifications. No provisions of the Act or the building Regulations, no requisitions made, conditions prescribed or orders issued there under have been transgressed in the course of the work. I am enclosing three copies of the completion plans. The building is fit for occupancy for which it has been erected/ re-erected or altered, constructed and enlarged.

I have to request you to arrange for the inspection & grant permission for the occupation of the building.

Yours faithfully

Signature and name of Architect /Licensed Engineer/
Structural Engineer/Supervisor

Encl : As above.

Date :

(Signature of Owner)

Name of Owner (in Block Letters)

APPENDIX 'I'

FORM FOR OCCUPANCY CERTIFICATE

To,

i) Owner:

ii) Architect, Licensed Engineer Structural Engineer / Supervisor

Sir,

The part / full development work / erection re-erection / or alteration in of building / part building No _____ Plot No _____, Revenue Survey No. _____, City Survey No. _____, mauje _____, completed under the supervision of _____ Architect, Licensed Engineer/ Structural Engineer / Supervisor, / License No _____ may be occupied on the following conditions-

1. _____
2. _____
3. _____
4. _____

A set of certified completion plans is returned herewith.

Encl : As above.

Yours faithfully,

Metropolitan Commissioner,
PMRDA or an officer appointed
by him

APPENDIX 'J'

FORM FOR REFUSAL OF OCCUPANCY CERTIFICATE

To,

i) Owner:

ii) Architect, Licensed Engineer Structural Engineer / Supervisor

Sir,

The part / full development work / erection re-erection / or alteration in of building / part building No _____ Plot No _____, Revenue Survey No. _____, City Survey No. _____, mauje _____, completed under the supervision of _____ Architect, Licensed Engineer/ Structural Engineer / Supervisor, / License No _____ is not allowed to be occupied because of the following reasons -

1. The construction carried out by you does not conform to the sanctioned plans.

2. _____

3. _____

A set of completion plan is retained with the PMRDA and remaining sets are regretfully returned herewith.

Encl : As above.

Yours faithfully, Metropolitan

Commissioner, PMRDA
or an officer appointed by him

APPENDIX 'K'

FORM OF INDEMNITY FOR PART OCCUPANCY CERTIFICATE

(On Stamp Paper)

(Of such value as decided by the Metropolitan
Commissioner.)

To,

Metropolitan Commissioner,

PMRDA.

Subject:-

Sir,

While thanking you for letting me occupy a portion of the above building before acceptance of the Completion Certificate of the whole building for the plans approved in communication No _____, dated _____ I hereby indemnify the PMRDA against any risk,

damage and danger which may occur to occupants and users of the said portion of the building and also undertake to take necessary security measures for their safety. This undertaking will be binding on me /us, our heirs, administrators and our assignees.

Yours faithfully,

Signature and name of Owner

Witness:

Address:

Date:

Appendix 'L'					
SCHEDULE FOR SERVICE INDUSTRIES					
Sr. No.	Category of Industry	Service Industry Class -A (Permitted in R2 and C) Criteria for Classification and special conditions			
		Maximum Permissible			
(1)	(2)	Power requirement (in H.P.)	Employment (in persons)	Floor area (in sq. m.)	Special Conditions if any
(3)	(4)	(5)	(6)		
I. Food Product					
1.	Preservation of meat, canning preserving and processing of fish crust aces and similar foods	-	-	-	Not permissible
2.	Manufacture of milk and dairy products such as butter, ghee, etc.	10	9	50	-
3.	Canning & preservation of Fruits & Vegetables including production of Jam, Jelly, Sauce, etc.	-	-	-	-
4.	(a) Rice huller (b) Groundnut decorticators (c) Grain Mill for production of flour (d) Manufacture of supari and Masala grindings. (e) Baby oil expellers	10 10 10 10 10	9 9 9 9 9	50 50 50 50 50	-
5.	Manufacture of bakery products with no Floor above	10	9	75	(i) Operation shall be permitted only between 8.00 hrs. to 20.00 hrs. (ii) Fuel used shall be electricity, gas or smokeless coal.
6.	Manufacture of cocoa, chocolate, Sugar confectionary	-	-	-	Not permissible
7.	Coffee, curing roasting and grinding	2	9	50	-
8.	Cashew nut processing like drying, shelling, roasting, salting etc.	-	-	-	Not permissible

9.	Manufacture of Ice	45	20	250	-
10.	Sugarcane crushing & Fruit Juice	2	9	25	-
II. BEVERAGES & TOBACCO					
11.	Manufacture of soft drinks and carbonated water	-	-	-	Not permissible
12.	Manufacture of bidi	No Power to be used	as permitted	250	May also be permitted in R-1 zone
III. TEXTILE & TEXTILE PRODUCTS					
13.	Handloom / power-loom of yarn for a maximum of 4 looms.	5	9	50	May also be permitted in R-1 zone in areas designated by the Metropolitan Commissioner.
14.	Printing dyeing & bleaching cotton, woollen & silk textiles	-	-	-	Not permissible
15.	Embroidery & making of crape laces & fringes	5	9	50	-
16.	Manufacture of all types of textile garments including wearing apparel.	3	9	50	-
17.	Manufacture of made up textiles goods such as curtains, mosquito net, mattresses, bedding material pillow cases, textile bags. etc.	3	9	50	-
IV. WOOD PRODUCTS AND FURNITURE					
18.	Manufacture of wooden & cane boxes & packing cases.	-	-	-	Not permissible
19.	Manufacture of structural wooden goods such as beams, posts, doors and windows	-	-	-	Not permissible
20.	Manufacture of wooden furniture and fixtures	1	9	50	i) Shall not be permitted adjoining a dwelling unit. ii) Operation shall be permitted only between 8.00 hrs. to 20.00 hrs.
21.	Manufacture of bamboo and cane furniture and fixtures	1	9	50	
22.	Manufacture of wooden products such as utensils, toys, art wares etc	-	-	-	Not permissible

V. PAPER PRODUCTS AND PRINTING PUBLISHING					
23.	Manufacture of cartons and boxes from papers and paper board, paper pulp,	5	9	50	Manufacture with paper pulp not permissible.
24.	Printing & Publishing newspaper.	5	9	50	-
25.	Printing & Publishing periodicals, books journals, atlases, maps, envelope, printing picture, post-card, embossing				i) Operation shall be permitted only between 8.00 hrs. and 20.00 hrs. ii) No restrictions of power, number of employees, area of hours of operation shall apply if located in a building, in separate plot not less than 500 sq. m. and if special permission of the Metropolitan Commissioner is obtained
26.	Engraving etching block making etc.	10	9	120	Operation shall be permitted only between 8.00 hrs. to 20.00 hrs.
27.	Book binding	10	9	120	-
VI. LEATHER PRODUCTS					
28.	Manufacture of leather footwear	-	-	-	Not permissible
29.	Manufacture of wearing apparel like coats, gloves etc.	-	-	-	Not permissible
30.	Manufacture of leather consumers goods such as upholstery suitcases, pocket books, cigarette and key cases, purses etc.	-	-	-	Not permissible
31.	Repair of footwear and other leather	5	9	50	
VII. RUBBER AND PLASTIC :					
32.	Re-treading and vulcanizing works	2	9	50	
33.	Manufacture of rubber balloons, hand gloves and allied products	2	9	50	
VIII. NON-METALLIC MINERAL PRODUCTS					
34.	Manufacture of structural stone goods, stone dressing, stone crushing and polishing	-	-	-	Not permissible

35.	Manufacture of earthen & plaster states and images, toys and art wares.	-	-	-	-	Not permissible
36.	Manufacture of cement concrete building components, concrete jellies, septic tank, plaster or paris work lime mortar etc.	-	-	-	-	Not permissible
IX.	METAL PRODUCTS :					
37.	Manufacture of furniture and fixtures primarily of metal.	-	-	-	-	Not permissible
38.	Plating & Polishing and buffing of metal products	-	-	-	-	Not permissible
39.	Manufacture of metal building components such as grills, gates. Doors and window frames, water tanks, wire nets, etc.	5	9	50		
40.	Manufacture and repair of sundry ferrous engineering products done by jobbing concerns such as mechanical works, shops with lathes, drills, grinders, welding equipment etc	-	-	-	-	Not permissible
41.	Total sharpening and razor sharpening works	1	6	25		Operation shall be permitted only between 8.00 hrs. to 20.00 hrs.
X	ELECTRICAL GOODS :					
42.	Repairs of household electrical appliances such as radio set. Television set, tape recorders, heaters, irons, shavers, vacuum cleaners, refrigerators, air-conditioners, washing machines, electric cooking ranges, motor rewinding works etc.	3	9	50		(i) Operation shall be permitted only between 8.00 hrs. 20.00 hrs. (ii) No spray painting permitted.
XI	TRANSPORT EQUIPMENT					
43.	Manufacturing of push cart, hand cart, etc.	10	9	50		
44.	(a) Servicing and repairing of bicycle, rickshaws, motor cycle and motor vehicles (b) Battery charging and repairs.	10 5	9 6	50 25		Operation shall be permitted only between 8.00 hrs. to 20.00 hrs. No spray painting permitted

XII. OTHER MANUFACTURING AND REPAIR INDUSTRIES AND SERVICES						
46.	Manufacture of jewellery and related articles	3	9	50		Operation shall be permitted only between 8.00 hrs. to 20.00 hrs.
47.	Repair of watch, clock and jewellery	3	9	50		Operation shall be permitted only between 8.00 hrs. to 20.00 hrs.
48.	Manufacture of sports and athletic goods	-	-	-		Not permissible
49.	Manufacture of Musical instruments and its repair.	3	9	50		Operation shall be permitted only between 8.00 hrs. to 20.00 hrs.
50.	Mass manufacture of miscellaneous Products such as costume, jewellery, costume novelties, feather, plumes, artificial flowers, brooms, brushes, lamp shades, tobacco, pipes, cigarette holders, ivory goods, bandages, wigs and similar articles.	-	-	-		Not permissible
51.	(a) Repairs of locks, stoves, umbrellas, sewing machines, gas burners, buckets & other sundry household equipment. (b) Optical glass grinding and repairs	3	9	50		Operation shall be permitted only between 8.00 hrs. to 20.00 hrs.
52.	Petrol filling stations/ CNG stations	10	9	(i) 30.5x16.75m. (ii) 36.5x30.5m		Plot size - without service bay Plot size - with service bay
53.	Laundries, Laundry service and cleaning, dyeing, bleaching and dry cleaning	5	9	50		(i) Cleaning & dyeing fluid used shall not have flash point lower than 138 ⁰ F. (ii) Operation shall be permitted between 8.00 hrs. to 20.00 hrs. (iii) Machinery having day load capacity of 20 kg and above.
54.	Photo processing laboratories.	5	9	50		Operation shall be permitted between 8.00 hrs. to 20.00 hrs.
55.	Electronic Industry of assembly type (and not of manufacturing type including heating load).	10	20	250		In independent structure on independent plot with special permission of the Metropolitan Commissioner
56.	Bio-technology Unit	--	--	--		As per Regulation no.23.8
57.	Information Technology Unit	--	--	--		As per Regulation no.23.9

Sanitation Requirements - Office Buildings

Sr. No.	Fixtures	Public Toilets		Staff Toilets	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Executive Rooms and Conference Halls in Office Buildings Toilet suite comprising one WC, one washbasin (with optional shower stall if building is used round the clock at user's option) Pantry optional as per user requirement	Unit could be common for Male / Female or separate depending on the number of user of each facility		For individual officer rooms	
ii)	Main Office Toilets for Staff and Visitors				
	a) Water-closet	1 per 25	1 per 15	1 per 25	1 per 15
	b) Ablution tap with each water-closet	1 in each water-closet			
	c) Urinals	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	-	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	-
		101-200		101-200	
		Over 200		Over 200	
	d) Washbasins	1 per 25	1 per 25	1 per 25	1 per 25
	e) Drinking water fountain	1 per 100	1 per 100	1 per 100	1 per 100
	f) Cleaner's sink	1 per floor			

Sanitation Requirements – Factories

Sr. No.	Fixtures	Offices/Visitors		Workers	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Water-closets (Workers & Staff)	1 for up to 25 2 for 16-35 3 for 36-65 4 for 66-100	1 for up to 15 2 for 16-25 3 for 26-40 4 for 41-57 5 for 58-77 6 for 78-100	1 for up to 15 2 for 16-35 3 for 36-65 4 for 66-100	1 for up to 12 2 for 13-25 3 for 26-40 4 for 41-57 5 for 58-77 6 for 78-100
	For persons 101-200 add	3 %	5 %	3 %	5 %
	For persons over 200 add	2.5 %	4 %	2.5 %	4 %
	ii) Ablution tap	1 in each WC	1 in each WC	1 in each WC	1 in each WC
	iii) Urinals	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	-	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	-
	For persons 101-200 add	3 %		3 %	
	For persons over 200 add	2.5 %		2.5 %	
iv)	Washbasins Washbasins in rows or troughs and taps spaced 750 mm c/c	1 per 25 or part thereof	1 per 25 or part thereof	1 per 25 or part thereof	1 per 25 or part thereof
v)	Drinking water fountain	1 per every 100 or part thereof on each floor	1 per every 100 or part thereof with minimum one on each floor	1 per every 100 or part thereof on each floor	1 per every 100 or part thereof with minimum one on each floor
vi)	Cleaner's sink	1 on each floor	1 on each floor	1 on each floor	1 on each floor
vii)	Showers/Bathing rooms	As per trade requirements			
viii)	Emergency shower and eye wash fountain	-	-	-	1 per every shop floor per 500 persons
NOTE – For factories requiring workers to be engaged in dirty and dangerous operations or requiring them to being extremely clean and sanitized conditions additional and separate (if required so) toilet facilities and if required by applicable Industrial and Safety Laws and the Factories Act must be provided in consultation with the user.					

Sanitation Requirements - Cinema, Multiplex Cinema, Concerts and Convention Halls, Theatres

Sr. No.	Fixtures	Public		Staff	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Water-closets	1 per 100 up to 400 Over 400, add at 1 per 250 or part thereof	3 per 100 up to 200 Over 200, add at 2 per 100 or part thereof	1 for up to 15 2 for 16 - 35	1 for up to 12 2 for 13 - 25
ii)	Ablution tap	1 in each water-closet	1 in each water-closet	1 in each water-closet	1 in each water-closet
iii)	Urinals	1 per 25 or part thereof	-	Nil up to 6 1 for 7-20 2 for 21-45	-
iv)	Washbasins	1 per 200 or part thereof		1 for up to 15 2 for 16-35	1 for up to 12 2 for 13-25
v)	Drinking water fountain	1 per 100 persons or part thereof			
vi)	Cleaner's sink	1 per floor			
vii)	Showers/Bathing rooms	As per trade requirements			

NOTES - 1) Some WC's may be European style if desired

2) Male population may be assumed as two-third and female population as one-third.

Sanitation Requirements - Art Galleries, Libraries and Museums

Sr. No.	Fixtures	Public		Staff	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Water-closets	1 per 200 up to 400 Over 400 add at 1 per 250 or part thereof	1 per 100 up to 200 Over 200 add at 1 per 150 or part thereof	1 for up to 15 2 for 16-35	1 for up to 12 2 for 13-25
ii)	Ablution tap	One in each water-closet	One in each water-closet	One in each water-closet	One in each water-closet
		1 water tap with draining arrangements shall be provided for every 50 persons or part thereof in the vicinity of water-closets and urinals			
iii)	Urinals	1 per 50	-	Nil up to 6 1 per 7-20 2 per 21-45	-
iv)	Washbasins	1 for every 200 or part thereof. For over 400, add at 1 per 250 persons or part thereof	1 for every 200 or part thereof. For over 200, add at 1 per 150 persons or part thereof	1 for up to 15 2 for 16-35	1 for up to 12 2 for 13-25
v)	Drinking water fountain	1 per 100 persons or part thereof			
vi)	Cleaner's sink	1 per floor, Min			
vii)	Showers/Bathing rooms	As per trade requirements			
NOTES -		1) Some WC's may be European style if desired. 2) Male population may be assumed as two-third and female population as one-third.			

Sanitation Requirements - Hospitals with Indoor Patient Wards

Sr. No.	Fixtures	Patient Toilets		Staff Toilets	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Toilet suite comprising one WC and one washbasin and shower stall	Private room with up to 4 patients		For individual doctor's / officer's rooms	
For General Wards, Hospital Staff and Visitors					
ii)	Water-closets	1 per 8 beds or part thereof	1 per 8 beds or part thereof	1 for up to 15 2 for 16-35	1 for up to 12 2 for 13-25
iii)	Ablution tap	1 in each WC	1 in each WC	1 in each WC	1 in each WC
1 water tap with draining arrangements shall be provided for every 50 persons or part thereof in the vicinity of water-closets and urinals					
iv)	Urinals	1 per 30 beds	-	Nil up to 6 1 for 7 to 20 2 for 21-45	-
v)	Washbasins	2 for every 30 beds or part thereof. Add 1 per additional 30 beds or part thereof		1 for up to 15 2 for 16-35	1 for up to 12 2 for 13-25
vi)	Drinking water fountain	1 per ward		1 per 100 persons or part thereof	
vii)	Cleaner's sink	1 per ward		-	
viii)	Bed pan sink	1 per ward		-	
ix)	Kitchen sink	1 per ward		-	

NOTES -

- 1) Some WC's may be European style if desired.
- 2) Male population may be assumed as two-third and female population as one-third.
- 3) Provision for additional and special hospital fittings where required shall be made.

Sanitation Requirements - Hospitals - Outdoor Patient Department

Sr. No.	Fixtures	Patient Toilets		Staff Toilets	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Toilet suite comprising one WC and one washbasin (with optional shower stall if building used for 24 h)	For up to 4 patients		For individual doctor's/officer's rooms	
ii)	Water-closets	1 per 100 persons or part thereof	2 per 100 persons or part thereof	1 for up to 15 2 for 16-35	1 for up to 12 2 for 13-25
iii)	Ablution tap	1 in each WC	1 in each WC	1 in each WC	1 in each WC
		1 water tap with draining arrangements shall be provided for every 50 persons or part thereof in the vicinity of water-closets and urinals			
iv)	Urinals	1 per 50 persons or part thereof	-	Nil up to 6 1 per 7 to 20 2 per 21-45	-
v)	Washbasins	1 per 100 persons or part thereof	2 per 100 persons or part thereof	1 for up to 15 2 for 16-35	1 for up to 12 2 for 13-25
vi)	Drinking water fountain	1 per 500 persons or part thereof		1 per 100 persons or part thereof	

notes - 1) Some WC's may be European style if desired.

- 2) Male population may be assumed as two-third and female population as one-third.
- 3) Provision for additional and special hospital fittings where required shall be made.

Sanitation Requirements - Hospitals' Administrative Buildings

Sr. No.	Fixtures	Staff Toilets	
		Male (3)	Female (4)
(1)	(2)		
i)	Toilet suite comprising one WC and one washbasin (with optional shower stall if building used for 24 h)	For individual doctor's/officer's rooms	
ii)	Water-closets	1 per 25 persons or part thereof	1 per 15 persons or part thereof
iii)	Ablution tap	One in each water-closet	One in each water-closet
		1 water tap with draining arrangements shall be provided for every 50 persons or part thereof in the vicinity of water-closets and urinals	
iv)	Urinals	Nil up to 6 1 per 7 to 20 2 per 21-45	-
v)	Washbasins	1 per 25 persons or part thereof	1 per 25 persons or part thereof
vi)	Drinking water fountain	1 per 100 persons or part thereof	
vii)	Cleaner's sink	1 per floor, Min	
viii)	Kitchen sink	1 per floor, Min	

note - Some WC's may be European style if desired.

Sanitation Requirements -Hospitals' Staff Quarters and Nurses Homes

Sr. No.	Fixtures	Staff Quarters		Nurses Homes	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Water-closets	1 per 4 persons or part thereof	1 per 4 persons or part thereof	1 per 4 persons or part thereof 2 for 16-35	1 per 4 persons or part thereof 2 for 16-35
ii)	Ablution tap	One in each water-closet	One in each water-closet	One in each water-closet	One in each water-closet
1 water tap with draining arrangements shall be provided for every 50 persons or part thereof in the vicinity of water-closets and urinals					
iii)	Washbasins	1 per 8 persons or part thereof	1 per 8 persons or part thereof		
iv)	Bath (Showers)	1 per 4 persons or part thereof	1 per 4 persons or part thereof		
v)	Drinking water fountain	1 per 100 persons or part thereof, minimum 1 per floor	1 per 100 persons or part thereof, minimum 1 per floor		
vi)	Cleaner's sink	1 per Floor	1 per Floor		

NOTES - 1) Some WC's may be European style if desired.

2) For independent housing units fixtures shall be provided as for residences.

Sanitation Requirements -Hotels

Sr. No.	Fixtures	Public Rooms		Non-Residential Staff	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Toilet suite comprising one WC, washbasin with shower or a bath tub	Individual guest rooms with attached toilets		-	
Guest Rooms with Common Facilities					
ii)	Water-closets	1 per 100 persons up to 400 Over 400 add at 1 per 250 or part thereof	2 per 100 persons up to 200 Over 200 add at 1 per 100 or part thereof	1 for up to 15 2 for 16-35 3 for 36-65 4 for 66-100	1 for up to 12 2 for 13-25 3 for 26-40 4 for 41-57 5 for 58-77 6 for 78-100
iii)	Ablution tap	1 in each WC	1 in each WC	1 in each WC	1 in each WC
1 water tap with draining arrangements shall be provided for every 50 persons or part thereof in the vicinity of water-closets and urinals					
iv)	Urinals	1 per 50 persons or part thereof	Nil, upto 6 persons 1 for 7-20 persons 2 for 21-45 persons 3 for 46-70 persons 4 for 71-100 persons	Nil up to 6 1 for 7 to 20 2 for 21-45 3 for 46-70 4 for 71-100	-

v)	Washbasins	1 per WC/Urinal	1 per WC	1 for up to 15 2 for 16-35 3 for 36-65 4 for 66-100	1 for up to 12 2 for 13-25 3 for 26-40 4 for 41-57
vi)	Bath (Showers)	1 per 10 persons or part thereof		-	-
vii)	Cleaner's sink	1 per 30 rooms, minimum 1 per floor			
viii)	Kitchen sink	1 per kitchen			
NOTE	1) Some WC's may be European style if desired. 2) Male population may be assumed as two-third and female population as one-third. 3) Provision for additional and special hospital fittings where required shall be made.				

Sanitation Requirements – Restaurants

Sr. No.	Fixtures	Public Rooms		Non-Residential Staff	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Water-closets	1 per 50 seats up to 200 Over 200 add at 1 per 100 or part thereof	2 per 50 seats up to 200 Over 200 add at 1 per 100 or part thereof	1 for up to 15 2 for 16-35 3 for 36-65 4 for 66-100	1 for up to 12 2 for 13-25 3 for 26-40 4 for 41-57 5 for 58-77 6 for 78-100
ii)	Ablution tap	1 in each WC	1 in each WC	1 in each WC	1 in each WC
1 water tap with draining arrangements shall be provided for every 50 persons or part thereof in the vicinity of water-closets and urinals.					
iii)	Urinals	1 per 50 persons or part thereof	----	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	----
iv)	Washbasins	1 per WC	1 per WC	1 per WC	1 per WC
v)	Cleaner's sink	1 per restaurant			
vi)	Kitchen sink /Dish washer	1 per kitchen			

NOTES: 1) Some WC's may be European style if desired.

2) Male population may be assumed as two-third and female population as one-third.

3) Provision for additional and special fittings where required shall be made.

Sanitation Requirements –Schools and Educational Institutions

Sr. No.	Fixtures	Nursery School	Non-Residential		Residential	
			Boys	Girls	Boys	Girls
(1)	(2)	(3)	(4)	(5)	(6)	(7)
i)	Water-closets	1 per 15 pupils or part thereof	1 for 40 pupils or part thereof	1 per 25 pupils or part thereof	1 per 8 pupils or part thereof	1 per 6 pupils or part thereof
ii)	Ablution tap	1 in each WC	1 in each WC	1 in each WC	1 in each WC	1 in each WC
1 water tap with draining arrangements shall be provided for every 50 persons or part thereof in the vicinity of water-closets and urinals.						
iii)	Urinals	----	1 per 20 pupils or part thereof	----	1 per 25 pupils or part thereof	----
iv)	Washbasins	1 per 15 pupils or part thereof	1 per 60 pupils or part thereof	1 per 40 pupils or part thereof	1 per 8 pupils or part thereof	1 per 6 pupils or part thereof
v)	Bath/Showers	1 per 40 pupils or part thereof	----	----	1 per 8 pupils or part thereof	1 per 6 pupils or part thereof
vi)	Drinking water fountain or taps	1 per 50 pupils or part thereof	1 per 50 pupils or part thereof	1 per 50 pupils or part thereof	1 per 50 pupils or part thereof	1 per 50 pupils or part thereof
vi)	Cleaner's Sink	1 per floor				

NOTES:

1) Some WC's may be European style if desired. 2) For teaching staff, the schedule of fixtures to be provided shall be the same as in case of office building.

Sanitation Requirements – Hostels

Sr. No.	Fixtures	Resident		Non-Resident		Visitor/Common Rooms	
		Male (3)	Female (4)	Male (5)	Female (6)	Male (7)	Female (8)
(1)	(2)						
i)	Water-closet	1 per 8 or part thereof	1 per 6 or part thereof	1 for upto 15 2 for 16-35 3 for 36-65 4 for 66-100	1 for upto 12 2 for 13-25 3 for 26-40 4 for 41-57 5 for 58-77 6 for 78-100	1 per 100 up to 400 Over 400 add at 1 per 250	1 per 200 up to 200 Over 200 add at 1 per 100
ii)	Ablution tap	1 in each WC	1 in each WC	1 in each WC	1 in each WC	1 in each WC	1 in each WC
1 water tap with draining arrangements shall be provided for every 50 persons or part thereof in the vicinity of water-closets and urinals.							
iii)	Urinals	1 per 25 or part thereof	----	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	----	1 per 50 or part thereof	----
iv)	Washbasins	1 per 8 persons or part thereof	1 per 6 persons or part thereof	----	----	----	----
v)	Bath/Showers	1 per 8 persons or part thereof	1 per 6 persons or part thereof	----	----	----	----
vi)	Cleaner's Sink	1 per floor					

NOTE: Some WC's may be European style if desired.

Sanitation Requirements – Mercantile Buildings, Commercial Complexes, Shopping Malls, Fruit & Vegetable Markets

Sr. No.	Fixtures	Shop Owners		Common Toilets in Market/ Mall Building		Public Toilet for Floating Population	
		Male	Female	Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
i)	Water-closets	1 per 8 persons or part thereof		1 for up to 15 2 for 16-35 3 for 36-65 4 for 66-100	1 for up to 12 2 for 13-25 3 for 26-40 4 for 41-57 5 for 58-77 6 for 78-100	1 per 50 (Minimum 2)	1 per 50 (Minimum 2)
ii)	Ablution tap	1 in each WC	1 in each WC	1 in each WC	1 in each WC	1 in each WC	1 in each WC
		1 water tap with draining arrangements shall be provided in receiving / sale area of each shop and for every 50 persons or part thereof in the vicinity of water-closets and urinals.					
iii)	Urinals	----	----	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	----	1 per 50	----
iv)	Washbasins	1 per 8 persons or part thereof		1 for up to 15 2 for 16-35 3 for 36-65 4 for 66-100	1 for up to 12 2 for 13-25 3 for 26-40 4 for 41-57	----	----
v)	Bath / Showers	1 per 8 persons or part thereof	1 per 6 persons or part thereof	----	----	1 per 50 persons	1 per 50 persons

NOTES: 1) Toilet facilities for individual buildings in a market should be taken same as that for office buildings.

2) Common toilets in the market buildings provide facilities for persons working in shops and their regular visitors.

Sanitation Requirements – Airports and Railway Stations

Sr. No.	Fixtures	Junction Stations, Intermediate Stations and Bus Stations		Terminal Railway and Bus Stations		Domestic and International Airports	
		Male	Female	Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
i)	Water-closet	3 for up to 1000 Add 1 per additional 1000 or part thereof	4 for up to 1000 Add 1 per additional 1000 or part thereof	4 for up to 1000 Add 1 per additional 1000 or part thereof	5 for up to 1000 Add 1 per additional 1000 or part thereof	Minimum 2 for 200 2 For 400 9 For 600 12 For 800 16 For 1000 18	Minimum 2 For 200 2 For 400 9 For 600 12 For 800 16 For 1000 18
ii)	Ablution tap	1 in each WC	1 in each WC	1 in each WC	1 in each WC	1 in each WC	1 in each WC
1 water tap with draining arrangements shall be provided for every 50 persons or part thereof in the vicinity of water-closets and urinals.							
iii)	Urinals	4 for up to 1000 Add 1 per additional 1000	----	6 for up to 1000 Add 1 per additional 1000	----	1 per 40 or part thereof	----
iv)	Washbasins	1 per WC / Urinal	1 per WC	1 per WC / Urinal	1 per WC	1 per WC / Urinal	1 per WC
v)	Bath/Showers	2 per 1000		3 per 1000		4 per 1000	
vi)	Drinking water fountain or taps (in common lobby	2 per 1000 or part thereof		3 per 1000 or part thereof		4 per 1000 or part thereof	

	for male/ female)					
vii)	Cleaner's sink	1 per toilet compartment with 3 WC's	1 per toilet compartment with 3 WC's	1 per toilet compartment with 3 WC's	1 per toilet compartment with 3 WC's	1 per toilet compartment with 3 WC's
viii)	Toilet for Disabled	1 per 4000	1 per 4000	1 per 4000	1 per 4000 (Minimum 1)	1 per 4000 (Minimum 1)

NOTES:

1) Some WC's may be European style if desired. 2) Male population may be assumed as three-fifth and female population as two-fifth. 3) Separate provision shall be made for staff and workers.

APPENDIX 'N '

PROVISIONS FOR BARRIER FREE ACCESS

Provisions for Barrier Free access in buildings for differently abled persons shall be as given below

1 Definitions

- 1.1 Non-ambulatory Disabilities:** – Impairments that, regardless of cause or manifestation, for all practical purposes, confine individuals to wheelchairs.
- 1.2 Semi - ambulatory Disabilities:** - Impairments that cause individuals to walk with difficulty or insecurity, individuals using braces or crutches, amputees, arthritics, spastics, and those with pulmonary and cardiac ills may be semi-ambulatory.
- 1.3 Hearing Disabilities:-** Deafness or hearing handicaps that might make an individual insecure in public areas because he is unable to communicate or hear warning signals.
- 1.4 Sight Disabilities:** - Total blindness or impairments, which affect sight to the extent that the individual, functioning in public areas, is insecure or exposed to danger.
- 1.5 Wheel Chair:** - Chair used by disabled people for mobility. The standard size of wheel chair shall be taken as 1050 mm x 750 mm.

- 2 Scope:-**These regulations are applicable to all buildings and facilities used by the public such as educational, institutional, assembly, commercial, business, mercantile buildings constructed on plot having an area of more than 2000 sq.m. It does not apply to private and public residences.

- 3 Site development:-**Level of the roads, access paths and parking areas shall be described in the plan along with specification of the materials.

- 3.1 Access Path / Walk Way:** - Access path from plot entry and surface parking to building entrance shall be minimum 1800 mm wide having even surface without any steps. Slope, if any, shall not have gradient greater than 5%. Selection of floor material shall be made suitably to attract or to guide visually impaired persons (limited to coloured floor material whose colour and brightness is conspicuously different from that of the surrounding floor material or the material that emits different sound to guide visually impaired persons; hereinafter referred to as —guiding floor material□). Finishes shall have a non-slip surface with a texture traversable by a wheel chair. Curbs wherever provided should blend to a common level.

- 3.2 Parking:** For parking of vehicles of differently abled people, the following provisions shall be made-

- i) Surface parking for two car spaces shall be provided near entrance, with maximum travel distance of 30.0 m. from building entrance.
- ii) The width of parking bay shall be minimum 3.6 meter.
- iii) The information stating that the space is reserved for wheel chair users shall be conspicuously displayed.
- iv) Guiding floor materials shall be provided or a device, which guides visually impaired persons with audible signals, or other devices, which serves the same purpose, shall be provided.

4 Building requirements

The specified facilities for the buildings for differently abled persons shall be as follows:

- i) Approach to plinth level
- ii) Corridor connecting the entrance/exit for the differently abled.
- iii) Stair-ways
- iv) Lift
- v) Toilet
- vi) Drinking Water

4.1 Approach to plinth level - Every building should have at least one entrance accessible to the differently abled and shall be indicated by proper signage. This entrance shall be approached through a ramp together with the stepped entry.

4.1.1 Ramped Approach – Ramp shall be finished with non-slip material to enter the building. Minimum width of ramp shall be 1800mm with maximum gradient 1:12. Length of ramp shall not exceed 9.0 meter having 800mm high hand rail on both sides extending 300mm beyond top and bottom of the ramp. Minimum gap from the adjacent wall to the hand rail shall be 50mm.

4.1.2 Stepped Approach:- For stepped approach size of tread shall not be less than 300mm and maximum riser shall be 150mm. Provision of 800mm high hand rail on both sides of the stepped approach similar to the ramped approach.

4.1.3 Exit/Entrance Door:- Minimum & clear opening of the entrance door shall be 900mm and it shall not be provided with a step that obstructs the passage of a wheel chair user. Threshold shall not be raised more than 12mm.

4.1.4 Entrance Landing:- Entrance landing shall be provided adjacent to ramp with the minimum dimension 1800mm x 2000mm. The entrance landing that adjoins the top end of a slope shall be provided with floor materials to attract the attention of visually impaired persons (limited to coloured floor material whose colour and brightness is conspicuously different from that of the surrounding floor material or the material that emits different sound to guide visually impaired persons hereinafter referred to as —guiding floor material□). Finishes shall have a non-slip surface with a texture traversable by a wheel chair. Curbs wherever provided should blend to a common level.

4.2 Corridor connecting the entrance / exit for the differently abled: The corridor connecting the entrance / exit for differently abled, leading directly outdoors to a place where information concerning the overall use of the specified building can be provided to visually impaired persons either by a person or by signs, shall be provided as follows:

- a) ‘Guiding floor materials’ shall be provided or device that emits sound to guide visually impaired persons.
- b) The minimum width shall be 1500mm.
- c) In case there is a difference of level, slope ways shall be provided with a slope of 1:12.
- d) Hand rails shall be provided for ramps/slope ways.

4.3 Stair-ways - One of the stair-ways near the entrance / exit for the differently abled shall have the

following provisions:

- The minimum width shall be 1350 mm.
- Height of the riser shall not be more than 150 mm and width of the tread 300mm. The steps shall not have abrupt (square) nosing.
- Maximum number of risers on a flight shall be limited to 12.
- Hand rails shall be provided on both sides and shall extend 300 mm on the top and bottom of each flight of steps.

- 4.4 Lifts** -Wherever lift is required as per regulations, provision of at least one lift shall be made for the wheel chair user with the following cage dimensions of lift recommended for passenger lift of 13 person capacity of Bureau of Indian Standards.

Clear internal width	1100 mm
Clear internal width	2000 mm
Entrance door width	900 mm

- A hand rail not less than 600mm long at 1000mm above floor level shall be fixed adjacent to the control panel.
 - The lift lobby shall be of an inside measurement of 1800 mm x 1800 mm or more.
 - The time of an automatically closing door should be minimum 5 seconds and the closing speed should not exceed 0.25 m/ sec.
 - The interior of the cage shall be provided with a device that audibly indicates the floor, the cage has reached indicates that the door of the cage of entrance/exit is either open or closed.
- 4.5 Toilets** - One special W.C. in a set of toilets shall be provided for the use of differently abled with essential provision of washbasin near the entrance for them.
- The minimum size shall be 1500 mm x 1750 mm.
 - Minimum clear opening of the door shall be 900mm and the door shall swing out.
 - Suitable arrangement of vertical/horizontal handrails with 50mm clearance from wall shall be made in the toilet.
 - The W.C. seat shall be 500mm from the floor.
- 4.6 Drinking Water**:-Suitable provision of drinking water shall be made for the differently abled near the special toilet provided for them.
- 4.7 Designing for Children** - In the buildings meant for the pre-dominant use of the children, it will be necessary to suitably alter the height of the handrail and other fittings & fixtures, etc.

Explanatory notes:

Guiding / Warning Floor Material:

The floor material to guide or to warn the visually impaired persons with a change of colour or material with conspicuously different texture and easily distinguishable from the rest of the surrounding floor materials is called guiding or warning floor material. The material with different texture gives audible signals with sensory warning when a person moves on this surface with walking stick. The guiding/warning floor material is meant to give the directional effect or warn a person at critical places. This floor material shall be provided in the following areas:

- a) The access path to the building and to the parking area.
- b) The landing lobby towards the information board, reception, lifts, staircases and toilets.
- c) Immediately at the beginning/end of walkway where there is a vehicular traffic.
- d) At the location abruptly changing in level or beginning/end of a ramp.
- e) Immediately in front of an entrance/exit and the landing.

Proper signage:

Appropriate identification of specific facilities within a building for the differently abled persons should be done with proper signals. Visually impaired persons make use of other senses such as hearing and touch to compensate for the lack of vision, whereas visual signals benefit those with hearing disabilities.

Signs should be designed and located so that they are easily legible by using suitable letter size (not less than 20 mm high). For visually impaired persons, information board in brail should be installed on the wall at a suitable height and it should be possible to approach them closely. To ensure safe walking, there should not be any protruding sign which creates obstruction in walking. Public Address System may also be provided in busy public areas.

The symbols/information should be in contrasting colour and properly illuminated because people with limited vision may be able to differentiate amongst primary colours. International Symbol Mark for wheel chair be installed in a lift, toilet, staircase, parking areas, etc., that have been provided for the differently abled.

Appendix 'O'

REGULATIONS FOR ERECTION OF MOBILE TOWERS

1.1 ERECTION OF MOBILE TOWERS:

Regulation for setting up of Telecommunication Cell Site(s)/Base Station(s) and installation of the equipments for Telecommunication Network in PMR area.

1.2 Applicability:

This Regulation, shall apply to all existing and/or proposed Telecommunication Cell Sites/Base Stations installed or to be installed in PMR area.

1.3 Control Over Development

No Telecommunication Cell Site/Base Station shall be setup or installed without the previous permission in writing of the Metropolitan Commissioner. The permission shall be granted in the same manner as prescribed under Sections 44 to 47 of the Maharashtra Regional and Town Planning Act, 1966.

If the Metropolitan Commissioner does not dispose of the application within a period of 60 days from the date of submission, the said application by the Telecom Service Provider/Infrastructure Provider (TSP/IP) shall be deemed to have been approved as per the provisions under Section 45 of the Maharashtra Regional and Town Planning Act, 1966.

1.4 Procedure for Obtaining Development Permission

- A** All the applications for setting up or installation of any Telecommunication Cell Site/ Base Station (TCS/BS) or erection of a part thereof, shall be made to the Metropolitan Commissioner by the concerned Telecom Service Provider (TSP) or the concerned Infrastructure Provider (IP), in such form and containing such particulars as may be prescribed by the Metropolitan Commissioner.
- B** The application to the Metropolitan Commissioner for obtaining the aforesaid development permission shall be accompanied by the following documents-
 - (a) All the documents as otherwise required to be attached for any development permission under the sanctioned Development Control Regulations for the area in which the site under application is located.
 - (b) Plans showing Location Map, Key Plan, Site Plan, Block Plan and Plans of the proposed work. In case of roof-top tower, the copy of Occupation Certificate or copy of sanctioned building plans or copy of Commencement Certificate issued by the Metropolitan Commissioner or any other valid proof, in respect of the building on which the erection of roof-top tower is proposed, showing that such building is authorised.
 - (c) Notarised consent of the Owner of premises, which shall mean and include consent of the owner of property or no-objection certificate of the concerned registered Co-op Housing Society or notarised consent of 70% of the total number legal occupants in case of Apartments or Condominium or no-objection certificate of the lessor in case of a lease -hold property.
 - (d) Copy of agreement between the TSP/IP and the Owner of premises.
 - (e) Copy of Access Service License/ Infrastructure Provider (IP) Registration Certificate, granted

to the TSP/IP by the Department of Telecommunications (DoT), Government of India (GoI).

- (f) Copy of clearance from the Standing Advisory Committee for Frequency Allocations (SACFA) or copy of application made to SACFA for the said Location submitted to Wireless Planning Commission (WPC) wing of the Department of Telecommunications (DoT), with registration number as WPC Acknowledgement, along with an undertaking that in case of any objection/ rejection, TSPs/IPs will take corrective actions or remove the TCS/BS.
- (g) Acknowledgement receipt issued by Telecom Enforcement Resource and Monitoring (TERM) Cells in respect of the self-certificate submitted by TSP/IP regarding mobile towers/Base Transceiver Station (BTS) (Ground-based or Roof-Top or Pole/wall-mounted) in the format as prescribed by Telecom Engineering Centre (TEC), DoT, establishing/certifying that all General Public areas around the TCS/BS will be within safe Electro-Magnetic Radiation (EMR) exposure limit as per peak traffic measurement after the antennae starts radiating.
- (h) Copy of Structural Stability Certificate for any ground-based Base Transceiver Station (BTS).

OR

In case of any roof-top BTS tower, Structural Stability Certificate for the building, based on written approval of any authorized Structural Engineer of the State/local Body/Central Building Research Institute (CBRT), Roorkee/ IIT/ NIT or any other Agency, authorized by the Metropolitan Commissioner.

Provided that such NOC shall not be required for the single pole antennae or cellular signal boosters.

- (i) Copy of the type test certificate issued by Automotive Research Association of India (ARAI) to the manufacturers of the Diesel Generator (DG) Sets.
- (j) Notarised undertaking from the Applicant/Owner of premises :-
 - (i) That the cabin will not be utilized for any purpose other than the Telecommunication Cell Site/Base Station.
 - (ii) That if the said activity is discontinued by the Applicant, the said cabin will be demolished forthwith by the Applicant /Owner of premises.
- (k) No objection certificate from the Authority concerned under the Civil Aviation Ministry (hereinafter referred to as the said Authority) in case of any building falling in any area where such no objection certificate of the said Authority is required under the relevant rules or law.
- (l) No objection certificate of the Maharashtra Pollution Control Board regarding compliance with the norms prescribed for noise levels and smoke levels for the power generating sets having capacity above 100 kw, to be provided for Base Transceiver Stations.
- (m) No objection certificate of the Chief Fire Officer of the PMRDA only in case of High Rise buildings having height of 15 mtr. or more measured from ground level.
- (n) Copy of clearance from the State Environment Department as well as the Forest Department, in case of forest, protected areas, if applicable.
- (o) Data Sheet containing the information regarding –
 - (a) Name of Telecom Service Provider/ Infrastructure Provider,
 - (b) Location,
 - (c) Tower Reference-

- (i) Height and Weight of Tower,
- (ii) Ground Based Tower/Roof Top Tower,
- (iii) Number of Antennae planned on Tower,
- (iv) Permissible maximum EMF Radiation Level,
- (v) Proposed maximum EMF Radiation Level.
- (p) Requisite fees, charges, as applicable.
- C** In case of a listed Heritage building/ Heritage precinct and/or in case of cessed buildings and/or in case of area under Environmentally Sensitive Zone (ESZ), notified by the Ministry of Environment and Forest (MoEF), Government of India (GoI), all the applications for installation of any TCS/BS or erection of a part thereof, shall be made to the concerned Metropolitan Commissioner, which will forward it to the Heritage Conservation Committee concerned and/or High Level Monitoring Committee (HLMC) appointed/constituted by MoEF respectively.
- D** The erection of the Base Station including tower, shall be commenced within 90 days from the date of receipt of permission from the Metropolitan Commissioner and report of erection shall be made to the Metropolitan Commissioner.

1.5 Leviable charges

The Metropolitan Commissioner, while granting permission under sub regulation (3) hereinabove, shall levy and collect the following charges:-

- (a) Development Charge.-Development charge shall be levied and collected by the Metropolitan Commissioner as per the provisions under section L24-B of The Maharashtra Regional and Town Planning Act, 1966. For the purpose of assessing the development charge, the setting up of Base Station on land and on roof-tops shall be classified under commercial category, calculated over the foot print area occupied by the Telecommunication Cell Site/Base Station.
- (b) Administrative Fee.-Over and above the development charge as stipulated in clause 4 (a) above, TSP/IP shall pay to the PMRDA, a onetime non-refundable Administrative fee of Rs.30000, or as per the rates revised from time to time by the Government.

1.6 Planning Norms For Erection of TCS/BS

- (a) Notwithstanding the land use provisions under these regulations, subject to the compliance of other provisions of these Regulations, it shall be permissible to install TCB/BS, on
 - (i) all land uses as earmarked in Regional/Development Plan,
 - (ii) all lands which are designated for non-buildable reservations in Regional/Development Plan, subject to the condition that the maximum permissible area for installation of such TCS/BS shall not be more than 5% of the area of the reserved site or 100 sq.m., whichever is less, and shall be located in one corner of the reserved site.
 - (iii) all lands which are designated as open spaces/recreational open spaces/recreational grounds in a sanctioned layout, where such installation shall be permissible only with the no-objection certificate of the concerned registered co-operative housing society or consent of 70% of the total number of legal occupants/plot holders of such layout, subject to the condition that the maximum permissible area for installation of such TCS/BS shall not be more than 5% of such area or 100 sq.m, whichever is less, and the same shall be located in one corner of such area.

- (iv) all buildable reservations in Regional/Development Plan, except for buildings of uses mentioned in Regulation no.36.5(f), where such installation shall be permissible on the roof top, but only after development of the said reservation.
 - (v) all open lands in slum areas belonging to the Government/public Authority planning Authority, where only ground-based TCS/BS shall be permissible and no Roof-Top Tower shall be permissible, save as provided in Regulation no.36.5(a)(vi) herein below.
 - (vi) public buildings in slum areas, like public toilets, community centres etc., constructed by any Public Authority or to be constructed by the TSP/IP, where construction of Roof Top Towers shall be permissible, subject to maintenance and compliance of other terms and conditions specified by the Metropolitan Commissioner.
- (b) No permission for installation of TCS/BS shall be granted in ecologically important areas, without ecological impact assessment and review of installation site. The Forest Department should be consulted before installation of TCS/BS in and-around protected areas and Zoos.
- (c) The TCS/BS must have clear access by means of an existing road having minimum width of 6 mtr. for locations falling in Congested area as earmarked on DP and 9 mtr., for locations falling outside such Congested area. However, in exceptional circumstances, the Metropolitan Commissioner may relax such road width suitably, but in no case, shall it be less than 5 mtr.
- (d) In case of both ground-based towers and roof-top towers, there shall be no nearby buildings right in front of the antenna(e) of equivalent height, taking into account the tilt of the lowest antenna on tower, as per the details in the **Table No. 28** below:-

Table No. 28

Sr. No.	Number of Antenna(e) Pointed in the Same Direction	Building/ Structure Safe Distance from the Antenna(e) at the Same Height (in mtr.)
(1)	(2)	(3)
1	1	20
2	2	35
3	4	45
4	6	55

Provided that the antennae at the same height only are to be counted, as the beam width of mobile antennae, in the vertical direction, is very narrow.

(Explanation.-The distance figures in the above Table are based on empirical estimation considering that all the antennae are emitting at their maximum RF power of 20 Watts and exactly in the same direction with the same height.)

Provided further that above norms shall automatically stand revised as per the latest guidelines, issued by the DoT from time to time.

- (e) In case of Wall Mounted/Pole Mounted Antenna(e) :-
- (i) Wherever the antennae are mounted on the wall of a building or pole or along the road, their height should be at least 5 mtr., above ground level/road level. Provided that such installations shall have to comply with the prescribed radiation limits.

- (ii) As far as safe distance of buildings from antenna(e) is concerned, guidelines as in Regulation no.36.5 (d) above shall apply.
- (f) Installation of Base Station antenna(e) shall not be permissible within the premises of schools, colleges, and hospitals as well as on the adjoining land /building within 3 mtr., from the boundary of premises of schools, colleges and hospitals. Also antenna(e) shall not be directed/ positioned towards any school/college/ hospital building.
- (g) The existing Base Station antenna(e) approved earlier on any school/college/ hospital, building shall not be renewed further after the expiry of period of approval and the same shall be removed immediately thereafter, subject to the provisions of Regulation no.36.7 (d).
- (h) Access to Base Station Antenna site shall be prohibited for the general public, by putting in place suitable measures such as wire-fencing, locking of the door to the roof, etc.
- (i) The roof-top TCS, IBS towers shall be put only on buildings which are declared structurally strong enough to bear the load of such installation. The base connection to the building should be got designed from a qualified structural engineer. Structural safety certificate of the composite structure [Building + Tower(s)] shall have to be obtained from any of therecognized Government Institutes.
- (j) While according permission for installation of TCS/BS, permissible for erection of a cabin at ground level may be granted. However, the same shall not be allowed in the prescribed marginal distances. The area of such cabin shall not be more than 20 sq. mt. for each TSP/IP, subject to the certificate of structural safety. Built-up area of such cabin(s) shall not be counted towards built-up area or FSI.
- (k) No permission for installation of TCS/BS shall be granted on buildings which are unauthorized and structurally unsafe. If permission for installation of such structures is granted on a building, which is declared as unauthorized at a later point of time, the Metropolitan Commissioner shall first take recourse to the provisions of sections 52, 53, 54 and 55 of the Maharashtra Regional and Town Planning Act, 1966 or other relevant laws, as the case may be, against such unauthorized building and in case the Metropolitan Commissioner, after completing the due process of law, decides to undertake any action of demolition against such unauthorised building then such decision shall also be conveyed to the concerned TSP/IP with a direction to relocate the TCS/BS within a period of 90 days, after which the Metropolitan Commissioner shall not be under any obligation to send any further intimation to the TSP/IP concerned before demolishing such unauthorised building, and it shall not be liable to pay compensation for the loss of the Base Station as a consequence of the demolition of the unauthorised building. The TSP/IP shall indemnify the Metropolitan Commissioner to this effect, while seeking permission for installation of TCS/BS.
- (l) Permission for installation of TCS/BS, once granted shall remain valid for next 5 years. The TSP/IP shall apply for renewal of permission to the Metropolitan Commissioner. The Metropolitan Commissioner, while considering renewal, shall insist upon submission of fresh structural stability certificate for buildings more than 30 years of age. Administrative fee shall be levied and collected as prescribed in Regulation no.36.4 (b) hereinabove, for every such renewal. If TSP/IP fails to apply for renewal alongwith all necessary documents before the expiry of earlier permission, then such TSP/IP shall be liable for action under the provisions of the Maharashtra Regional and Town Planning Act, 1966.
- (m) In case of any existing TCS/BS on a slum structure, every effort shall be made to relocate such

TCS/BS on a nearby suitable public building or any other authorised structure or open land in the slum. If such relocation is not possible, then such TCS/BS may be allowed to be continued on such slum structure subject to its structural suitability, till the TCS/BS is shifted to any other authorised structure or till the redevelopment of the slum, whichever is earlier.

- (n) While granting permission for TCS/BS, the Metropolitan Commissioner shall stipulate that TSP/IP shall conduct regular audit in accordance with the directions/guidelines issued by TERM Cell or DoT from time to time.

1.7 Electro-Magnetic Field (EMF) Radiation Norms

- (a) Prior to installation of TCS/BS, the TSP/IP shall have to obtain Site clearance from the Standing Advisory Committee on Frequency Allocation (SACFA) of the Department of Telecommunication (DoT) for every site from the point of view of interference with other wireless users, aviation hazards and obstruction to any other existing microwave links.
- (b) The Electro-Magnetic Field (EMF) radiation from BTS towers shall be subject to the regulations framed by the DoT from time to time. The TSP/IP shall periodically conduct audit and monitor EMF radiation in Urban localities, hospitals and educational/industrial /residential / recreational premises, especially around the Protected Areas (PAs) and ecologically sensitive areas, in accordance with the guidelines issued by DoT in this regard. It shall be binding on TSP/ IP to follow the mechanism prescribed by the DoT/TERM Cell at local level for ensuring control on the EMF radiation and for notifying on continual basis the radiation level at critical location. For all the existing as well as new BTSs/Towers, TSPs are required to submit self-certificates periodically in the format prescribed by TEC, DoT, in order to ensure that normally all general public areas around the TCS/BS site are within the safe EMR exposure limits. Audit of the self-certification furnished by the TSPs shall be done by the TERM Cell periodically. TERM Cell shall carry out test audit of the BTS sites on random basis as per the guidelines received from DoT and also in respect of all cases where there is a public complaint. The TERM Cell shall have due regard to the instructions issued by DoT regarding technical audit of TCS/BS, including radiation of towers within safe limits. These shall include Roof Top/Ground Based./Pole Mounted/Wall Mounted Towers. The TERM Cell shall also verify antenna orientation, safe distance from the Tower (exclusion zone) etc. For non-compliance of EMF standards, Telecom Service Provider shall be liable for penal action by the TERM Cell and/or Department of Telecommunication (DoT). Any violation noticed may attract heavy penalties on TSPs and may also lead to shut down of TCS/ BS, in case the violation persists.

1.8 Miscellaneous Provisions

- (a) Any complaint concerning illegal installation of TCS/BS on any building or any query of any nature regarding the installation of telecommunication equipment, shall be addressed to the Metropolitan Commissioner which shall intimate the concerned TSP/IP about the same with a direction to resolve the issue under intimation to the Metropolitan Commissioner, within such period as may be prescribed by the Metropolitan Commissioner.
- (b) The TSP/IP, who has erected TCS/BS without due permission, shall apply to the concerned Metropolitan Commissioner for regularization within 180 days from the date of coming into force of this Regulation. In case such application is made within the prescribed period, then the offence, if any, registered against the TSP/IP may be compounded by the Metropolitan Commissioner under section 143 of the Maharashtra Regional and Town Planning Act, 1966, subject to the provisions of these regulations.

- (c) The TSPs/IPs who have earlier erected TCS/BS with due permission, shall apply afresh, for validation of the previous permission, to the Metropolitan Commissioner within a period of 90 days from the date of commencement of this Regulation, in order to ensure due compliance of this Regulation. However Administrative fee in such cases shall not be leviable if appropriate fee/ Development charge, not less than the amount prescribed under Regulation no.36.4 (b)above, has already been paid. In case the amount paid is less than what is prescribed hereinabove, the difference in amount shall be recovered from the TSP/IP.
- (d) Any existing TCS/BS not conforming to any of the above provisions shall have to be removed within one year from the date of commencement of this Regulation, unless the same is specifically regularized by the Metropolitan Commissioner following due compliance by TSP/IP. However, operation of such non-conforming Telecommunication Cell Site/Base station shall be discontinued within a period of 30 days from the date of receipt of notice from the Metropolitan Commissioner to that effect, which shall however be issued only after obtaining the consent of the TERM Cell of DoT.
- (e) The Licensees shall try to share the tower for fixing their respective antennae provided the prescribed conditions are duly fulfilled, so as to ensure curtailing of multiple towers and optimizing the use of the existing ones.
- (f) Sign boards and Warning signs ("Danger", "RF Radiation", "Restricted Area", "Don't Enter" etc.) shall be provided at TCS/BS antenna sites which are clearly visible and identifiable.
- (g) The TSP/IP shall display the details of the following on a board (minimum size 24" x 48") separately or prominently on the cabin, for the perusal of general public in such a way that the same shall be clearly visible and identifiable.
 - i. Name of TSP/IP :-
 - ii. Location :-
 - iii. Tower Reference :-
 - (a) Height, (b) Weight (c) Number of antennae planned on tower, (d) Permissible EMF radiation level (e) Proposed EMF radiation level.
 - iv. Due date for next renewal.
 - v. Contact Person's name, address and Telephone Number
 - vi. Address of Complaint Redressing Authority with Telephone Numbers
 - vii. Police Control Room- 100
 - viii. Fire Control Room – 101
 - ix. Ambulance – 102
 - x. Other important information, if any.

Provided that in case of Telecommunication Cell Site/Base station on roof-top, the aforesaid information shall be displayed on the ground floor of the building.
- (h) The Metropolitan Commissioner shall display the list of authorized TCS/BS on their official web site, along with the date of permission and due date for renewal of permission.
- (i) TCS/BS Tower shall be inspected for distortion of members, torques of nuts and bolts at least once in five years. However, in case of areas affected by any natural calamity, such as cyclone,

earthquake, flood, etc., such inspection shall be carried out immediately after such incident suo motu or on being directed by the Metropolitan Commissioner. Such inspection shall be carried out only by a qualified structural engineer and a certificate to that effect shall be submitted to the Metropolitan Commissioner.

(j) TCS/BS Towers located in highly corrosive environment shall be painted every year. Other towers shall be painted at least once in five years to give additional protection.

(k) The Metropolitan Commissioner shall make efforts to provide Single Window clearance to TSP/ IP for disposal of their applications in a time bound manner.

1.9 Notwithstanding anything contained hereinabove, all the Regulations/Bye-Laws/ Memorandum /Directions /Guidelines in this regard, issued or to be issued from time to time, by the Department of Telecommunications, Government of India, shall prevail and be binding on TSP/IP and also on the PMRDA, in which case, this Regulation shall stand modified to that extent.

1.10 Powers of Interpretation and Removal of Doubt.-

If any interpretation is required regarding the clauses of this Regulation, then the matter shall be referred to the Urban Development Department, Government of Maharashtra, whose decision shall be final.

APPENDIX 'P'
SITE VISIT REPORT

Date of Site visit			
Site Visit By			
Proposed Project:			
Proposed Land use (Residential -R1 / R2, Commercial / Industrial / Agriculture / No Development / Afforestation Zone).			
Site Details		By Owner / PAH	By TP
a.	Survey no / Gut No.		
b.	Village		
c.	Taluka		
d.	Plot area as per 7/12 extract		
e.	Location (Lat/Lon)		
f.	Land use zone.		
g.	NA Status		
h.	Environmental clearance		
Details of Site Visit		By Architect	By TP
a.	Existing approach road width		
	Type of existing road (Tar/Wbm/Concrete)		
b.	Proposed approach road width as per RP/DP		
c.	Classification of approach road as per RP/DP		
d.	Existing nature of ground		
	contours gentle than 1 in 5 slope		
	contours steeper than 1 in 5 slope		
e.	Any existing structure on the site, if any, are they correctly marked on the plan.		
	Plinth area of the existing structure.		
	Existing structure (To be demolished / Retained)		
f.	Existing water course (Y/N)		
	Minimum distance from the Blue HFL line.		
	Minimum distance from the Red HFL line.		

g.	Drainage system available (Y/N)		
h.	Distance of site from electric line (If adjacent or within the site)		
	Type of electrical line (Low / Medium /High / Extra High Voltage line)		
i.	Distance of site from railway property (if adjacent)		
j.	Insanitary conditions (free from caucuses / exacter / Filth)		
k.	Whether site is affected by Airport proximity zone as per RP /DP.		
l.	Drinking Water Availability		
m.	Distance from adjacent industrial plot		
n.	Checked demarcation map with site conditions and validated (Yes/No)		
k.	Whether site is affected by airport proximity zone as per RP / DP		
l.	Drinking water availability		
m.	Abutting industrial Plot (Y / N)		

APPENDIX 'Q'
SITE VISIT CERTIFICATE

Ref: 1. Application no. _____, dated _____.

2, Site Visit conducted on dated _____.

This is to certify that, status of the site is as follows and is suitable for the proposed land use.

Date of Site visit			
Site Visit By			
Proposed Project:			
Proposed Land use (Residential -R1 / R2, Commercial / Industrial / Agriculture / No Development / Afforestation Zone).			
Site Details		By Owner / PAH	By TP
a.	Survey no / Gut No.		
b.	Village		
c.	Taluka		
d.	Plot area as per 7/12 extract		
e.	Location (Lat/Lon)		
f.	Land use zone.		
g.	NA Status		
h.	Environmental clearance		
Details of Site Visit		By Architect	By TP
a.	Existing approach road width		
	Type of existing road (Tar/Wbm/Concrete)		
b.	Proposed approach road width as per RP/DP		
c.	Classification of approach road as per RP/DP		
d.	Existing nature of ground		
	contours gentle than 1 in 5 slope		
	contours steeper than 1 in 5 slope		
e.	Any existing structure on the site, if any, are they correctly marked on the plan.		
	Plinth area of the existing structure.		
	Existing structure (To be demolished / Retained)		

f.	Existing water course (Y/N)		
	Minimum distance from the Blue HFL line.		
	Minimum distance from the Red HFL line.		
g.	Drainage system available (Y/N)		
h.	Distance of site from electric line (If adjacent or within the site)		
	Type of electrical line (Low / Medium / High / Extra High Voltage line)		
i.	Distance of site from railway property (if adjacent)		
j.	Insanitary conditions (free from caucuses / exacter / Filth)		
k.	Whether site is affected by Airport proximity zone as per RP /DP.		
l.	Drinking Water Availability		
m.	Distance from adjacent industrial plot		
n.	Checked demarcation map with site conditions and validated (Yes/No)		

(This certificate is valid for three months from the date of issue)

Certificate Issued by

Metropolitan Commissioner PMRDA

APPENDIX - R
REGULATIONS FOR LONAVALA-KARLA-MALAVALI
PLANNING AREA OF SECTOR R OF RP OF PUNE
REGION

No plots in these zones shall be less than 500 sqm; provided that smaller plots in these zones admeasuring not less than 300 sqm existing before the date of publication of regional plan shall be recognized for the purpose of granting development permissions; provided further that plots directly abutting on Mumbai-Pune road shall not admeasure less than 1000 sqm. Development in such 1000 sqm plot, shall be governed by development control rules in Lonavala Regional/Development Plan, applicable to 10 are zone.

Built up areas, number of storeys, tenements, marginal open spaces and room sizes, the maximum built up areas, the maximum number of storeys, the maximum number of tenements, the minimum marginal open spaces and the minimum room sizes permissible in these zones shall be as indicated in the statement "AAA" annexed hereto. As regards rules for layout plots and group housing schemes and buildings of various users other than residential; other items of building construction, such as balcony, sanitation, height, ventilation and parking etc shall be governed by development control regulations for these items incorporated in Regional/Development Plan of Lonavala as amended from time to time and *subject to these regulations*.

Statement 'AAA'

	Plot Size group	Maximum built up area	Max.n o. of storeys	Max. no of tenements	Min.marginal open space			Min habitable room sizes	Min. sizes for kitchen	Min sizes for shops & other rooms for commercial use
					Road side	Side	Rear			
1.	Between 300 sqm and less than 500 sqm	25%	Ground plus one floor only	2	3m	2.5m	3m	9.0 sqm with no side less than 3m	7.5 sqm with no side less than 2.5m	15 sqm with no side less than 3m
2.	500 sqm and above	25%	Ground plus one upper	4	4.5m	3m	4.5m			

- 1) A ground floor on stilts or columns without enclosing walls (except retaining walls, where such floor is constructed by cutting the sloping ground) intended to be used as parking space shall not be counted as ground floor.
- 2) In case of classified roads, the minimum marginal open spaces to be observed from roads, shall be as prescribed above or as prescribed by Government from time to time under the ribbon development rules, whichever is more. However, on Mumbai-Pune National highway, no construction of any sort shall be allowed within a distance of 75m from the centre line of this road.
- 3) Sr.no. 1 is applicable to the plots existing on or before the date of publication of the notification in the official gazette.

APPENDIX –S
REGULATIONS FOR KUNE-PANGALOLI-KURWANDE
PLANNING AREA OF SECTOR R OF RP OF PUNE
REGION

Development in this area shall be governed by the regulations applicable to 10 Are zone in the Lonavala Regional/Development Plan. The maximum built up areas, the maximum number of storeys, the maximum number of tenements, the minimum marginal open spaces and the minimum room sizes permissible in these zones shall be as indicated in the statement “BBB” annexed hereto. As regards rules for layout plots and group housing schemes and buildings of various users other than residential; other items of building construction, such as balcony, sanitation, height, ventilation and parking etc shall be governed by development control regulations for these items incorporated in Regional/Development Plan of Lonavala as amended from time to time and *subject to these regulations.*

Statement "BBB"

Sr. no.	Plot Size group	Maximum built up area	Max.no . of storeys	Max. no of tenement s	Min.marginal open space			Min habitable room sizes	Min. sizes for kitchen
					Road side	Side	Rear		
1.	Between 500 sqm and less than 1000 sqm	25%	Ground plus one floor only	2	4.5m	3m	4.5m	9.0 sqm with no side less than 3m	7.5 sqm with no side less than 2.5m
2.	1000 sqm and above	25%	Ground plus one upper	4	4.5m	3m	4.5m	11 sqm with no side less than 3m	

- 1) A ground floor on stilts or columns without enclosing walls (except retaining walls, where such a floor is constructed by cutting the sloping ground) intended to be used as parking space shall not be counted as ground floor.
- 2) In case of classified roads, the minimum marginal open spaces to be observed from roads, shall be as prescribed above or as prescribed by Government from time to time under the ribbon development rules, whichever is more. However, on Mumbai-Pune National highway, no construction of any sort shall be allowed within a distance of 75m from the centre line of this road.
- 3) Sr.no. 1 is applicable to the plots existing on or before the date of publication of the notification in the official gazette.

APPENDIX –T

REGULATIONS FOR DEVELOPMENT OF TOURISM AND HOSPITALITY SERVICES UNDER COMMUNITY NATURE CONSERVANCY AROUND WILD LIFE SANCTUARIES AND NATIONAL PARKS OF RP OF PUNE REGION.

Applicability: These regulations shall apply to the privately owned (not applicable to forest land) lands falling in Agriculture I No Development Zone situated within 5 km distance from the boundaries of wildlife sanctuaries and national parks in the PMRDA area . The provisions of existing Regional Plans I Development Plans with prevail over these regulation.s, wherever lands are earmarked for urbanisable zones in such plans.

Regulation:- For the lands situated within 5 km distance (or up to limit of notified eco - sensitive zone whichever is more) from the boundaries of wildlife sanctuaries and national parks, if the land owner applies for development permission, for development of eco-tourism, nature tourism, adventure tourism, same may be allowed; provided the land under consideration has minimum area of one hectare in contiguous manner.

Permissible users and built up area:-

The users permissible in Agricultural Zone/No Development Zone shall be as follows:-

- a) Agriculture, Farming, development of wild animal shelters, plantation and allied uses.
- b) Tourist homes, resorts, hotels etc. with rooms/suites, support areas for reception, kitchen, utility services etc. alongwith ancillary structures like covered parking, watchman's quarter, guard cabin, landscape element, and only one observation tower per tourist resort upto the height 15 mt. with platform area upto 10 sq.mt. in permanent/semi -permanent structural components.

The norms for building will be as follows:-

- i) The construction activities shall be as per Zonal Master Plan of concerned protected area.
- ii) The maximum permissible total built up area shall not exceed 10% of gross area with only G+1 structure having height not more than 9m. and it should blend with the surrounding.
- iii) The fencing/fortification may be permissible for only 10 % of total land area around built up structure in the form of chain link without masonry walls thereby keeping the remaining area free for movement of wild life.
- iv) Tourism infrastructure must confirm to environment friendly, low height, aesthetic architecture, natural cross-ventilation: no use of asbestos, no air pollution, minimum outdoor lighting and merging with the surrounding landscape. They should generate at least 50% of their total energy and fuel requirement from nonconventional energy sources like solar and biogas etc.
- v) The owner shall establish effective sewage disposal and recycling system during the construction and operational phase of the development. Not 1 ltr. of sewage shall go into the natural stream;

If in cases, where lack of compliance is observed, the PMRDA shall issue a notice to the resort owner/operator for corrective action within 15 days, failing to do so or having not been satisfy with the action taken or reply/justification received, any decision to shut down the unit may be taken by the PMRDA.

- vi) The owner shall establish effective systems for collection, segregation, composting

and/or reuse of different types of solid waste collected during the construction and operational phase of the development.

- vii) The plastic components used within the area shall be recycled; failing which the resort shall be closed down within 48 hours.
- viii) Natural streams/slopes/terrain shall be kept as it is, except for the built up area.
- ix) On the area other than 10% area, only local trees shall be planted and only natural vegetation shall be allowed.
- x) For the development such type already taken place, condition no (iii) above shall be applicable retrospectively to the extent of restricting the fencing and keeping the remaining area free for movement of wild life.
- xi) While allowing such development, principles given in the National Tiger Conservation Authority New Delhi Notification No. 15-31/2012-NTCA, dated 15/10/2012 published in the gazette of India Ext. pt. III S-4 dated 08/11/2012 and Government of Maharashtra as amended from time to time shall be used as guidelines.
- xii) All regulation prescribed in Eco- Sensitive Zone Notification of concerned National Park/ Wild Life Sanctuary should be strictly followed and all clearances required should be taken.

APPENDIX –U

Approvals of Building Permission on Fast Track based on Risk Based categorization

Notwithstanding Anything Contains in DCPR of the PMRDA, the Regulations Regarding Approval Of Building Permission by the **Architect /L.S./Engineer** at the Stage of Commencement , Plinth Checking and Completion cum Occupancy shall be as per **Risk Based Classification** of Building given in Table below:-

Sr. No.	Parameters to be consider for Risk Base.	Risk Category	
		Low Risk Category	Moderate Risk Category
1	Plot Area considered for Risk Based Assessment.	Buildings on a Plot Area upto 150 sq.mt.	Buildings on a Plot Area between 151 Sq mtr and upto 200 sq.mt.
2	Permissibility In Development Plan Zone	Residential Zone, Commercial zone and Public-Semi-public Zone	Residential Zone, Commercial zone and Public-Semi-public Zone
3	Plot status	The plot should be vacant . The Plot Status ,Plot criteria and permissibility in above land use zone shall be as per respective DCPR.	The plot should be vacant . The Plot Status ,Plot criteria and permissibility in above land use zone shall be as per respective DCPR.
4	Type of building	Residential and other buildings as per DCPR	Residential and other buildings as per DCPR
5	Proposed Structure of Building/Storey	G.F. / P+1 RCC./Load Bearing	G.F.+1 / P+2 RCC./Load Bearing
6	Front and side open spaces, Provision of Basement, Parking requirement and other requirements.	As per the provisions of DCPR.	As per the provisions of DCPR.
7	Tree cutting/ Tree replantation.	Not permitted.	Not permitted
8	Experience Criteria for Architect /L.S./Engineer for self-certification and all approval mentioned in this regulation.	As per Appendix-C of the respective DCPR regarding licensing and qualifications of the technical person.	As per Appendix-C of the respective DCPR regarding licensing and qualifications of the technical person.
9	NOCs and Documents	Wherever required as per the respective DCPR	Wherever required as per the respective DCPR
10	Site inspection and Computer based allocation of inspector for site inspection.	No site inspection is necessary by the PMRDA at any stage. Approval Procedure is to be followed as mentioned in Point No.11 excluding point no 11 (c).	Site inspection at Plinth level is necessary by the PMRDA. Approval Procedure is to be followed as mentioned in Point No.11 including point no 11 (c).

11. Procedure for Building Permission

Architect/ Licence Surveyor (L.S.)/Engineer (Architect registered with Council of Architecture & License Surveyor & Engineer registered with the PMRDA) are empowered to grant provisional approval **with self-certification** to the building proposal plans categorised as **Low Risk & Moderate Risk** in Table given above, subject to the following:-

Building Permission/Commencement Certificate:-

a) Submission of Proposal:-The proposal shall comprise of application u/s 44/69 of MR&TP Act, 1966, in format prescribed by the Metropolitan Commissioner, along with documents and undertakings required for the proposal as per regulation & required by the Metropolitan Commissioner from time to time. All the required documents shall be **certified and signed** by the Architect /L.S./Engineer confirming with the original documents. The documents required shall be as per the DCPR of the PMRDA.

b) Commencement Certificate (CC) :- After receipt of the application, the Demand Note regarding payment of Scrutiny Fee, Development Charges and other Charges based on the proposed Plans / Drawing submitted shall be given by the concern Engineer of the authority within 10 days. The owner / Architect /L.S./Engineer shall deposit the Charges as demanded. Upon deposit of such Charges with the PMRDA, the concerned Architect/ Licence Surveyor (L.S.)/Engineer are empowered to grant provisional approval in the form of **self- certification** certifying that the plan / entire building proposal is strictly in conformity with the DCPR. This **self-certification** shall be treated as **Commencement for the** construction work.

The owner/concern Architect/ Licence Surveyor (L.S.)/Engineer shall submit the said **self-certified plan** to the PMRDA **within 10 days**. Upon such submission, the concerned Officer, authorized by the Metropolitan Commissioner shall **countersign the plans without any scrutiny** and issue Commencement Certificate Under Section-45 of Maharashtra Regional and Town Planning Act, 1966 **within 10 days** from the receipt of such plan. The Scrutiny at the PMRDA level need not be necessary. Concern Architect /L.S./Engineer is **empowered/Authorised** to issue the copies of such *approved* plans & Certificates with his signature.

c) Plinth Checking For Moderate Risk building proposal:- The concern Architect /L.S./Engineer shall apply for certificate of plinth checking in prescribed application for Moderate Risk building proposal only. The inspection shall be done by the concerned Officer of the PMRDA. The inspection report shall be prepared and uploaded within 48 hours. The Plinth checking certificate shall be grant within the period of 7 days from the receipt of the application, if found as per the sanctioned plan.

d) Building completion certificate:- On completion of work, the concern Architect/L.S./Engineer shall issue the Building completion certificate and Occupation certificate, as required as per the provision of DCPR to the completed building/structure and submit two set of completion plan along with the required certificate and all site inspection report to the authority. The concerned Officer authorised by the Metropolitan Commissioner shall countersign the said Completion Plan along with Occupancy Certificate within 10 days **without any scrutiny and site inspection**.

12. Responsibility of the Architect/L.S./Engineer

- a) The work shall be supervised by the concerned Architect/L.S./Engineer who will ensure that the same is carried out strictly as per the approval. Confirmation of ownership of land / plot area and land boundaries in the name of applicant shall be jointly responsibility of concerned Architect/L.S./Engineer and the owner.
- b) It will be the responsibility of the concern Architect /L.S./Engineer, Site Supervisor & Structural Engineer appointed for the proposed development, jointly or severally to ensure that all plans shall be in consonance with provisions of the DCPR. All the requirements of the DCPR shall have to be complied with due care and the work is carried out as per the approval only. Any deviation required during the construction shall be approved by Architect/L.S./Engineer before execution. The concerned Architect /L.S./Engineer shall be empowered for any amendments in the plan in process of construction within the purview of DCPR.

- c) Frequency of Inspection By the Architect/L.S./Engineer:-_The Architect/L.S./Engineer shall inspect and submit the site inspection report along with photographs/video clips, at stages while submitting the building proposal, after completion of plinth work, and finally at the time of Building completion certificate to the authority. Such inspection reports shall be submitted and uploaded within 48 hours from the date of inspection.
- d) After submitting the application or during the construction of building if the Architect/L.S./Engineer are changed, he shall intimate the PMRDA immediately that he is no longer responsible for the project from the date of intimation. The construction work shall have to be suspended until the new Architect/L.S./Engineer as the case may be appointed by the owner. Owner's intimation regarding change of licensee shall be considered to be final. After intimation of the new appointed licensee shall then undertakes and start the project.


13. Authorisation to PMRDA :-

- a) In case of any deviations/irregularities noticed in the process or after completion, the PMRDA may immediately issue notice to the owner and or to the concerned licensee to suspend the further work and rectify the deviations/irregularities. Only after satisfaction of rectification made by the owner or concerned licensee, the PMRDA may issue intimation to start the work. In major violations, the PMRDA shall authorise to take appropriate action against Architect/L.S./Engineer as the case may be, as per the DCPR or as per respective Acts and Laws.
- b) The Metropolitan Commissioner, as the case may be, of the PMRDA is authorised to prepare common application forms, proformas, affidavit etc. wherever required for the smooth implementation of this regulation.
- c) The above procedure shall be integrated with the Online Building Permission Management System (BPMS) by the PMRDA.


14. Exceptions from this Procedure:-The above Procedure for Building Permission shall not bar the owner/ Architect/L.S./Engineer to obtain development permission as per Regular provisions of the DCPR.

ANNEXURE I TYPICAL ROAD CROSS-SECTIONS


ANNEXURE I




15 M WIDE SECTION



12 M WIDE SECTION






9 M WIDE SECTION



6 M WIDE SECTION

ALL DIMENSIONS ARE IN METER

ANEXURE II



THE UNIVERSITY OF CHICAGO

मंगळवार, सप्टेंबर ११, २०१८ / भाद्र २०, शके १९४०

जिल्हाधिकारी यांजकडून

प्रपत्र-ड

विशेष कार्यकारी अधिकारी यांच्या नेमणुका

जिल्हाधिकारी, पुणे (गृहशाखा) आदेश

क्रमांक पगम/एसआर-१५/२०१८.--जिल्हाधिकारी, पुणे जिल्हा, पुणे ह्या आदेशाद्वारे सोबत जोडलेल्या अनुसूचीमध्ये विनिर्दिष्ट केलेल्या पात्र व्यक्तींची पुणे जिल्ह्याचे "विशेष कार्यकारी अधिकारी" म्हणून नियुक्ती कशीत आहे. ही नियुक्ती सामान्यतः हा निर्णय निर्गमित केलेल्या तारखेपासून ५ वर्षांकरिता अथवा पुढील आदेश होईपर्यंत अस्तित्वात राहील. तसेच राज्य शासनास विशेष कार्यकारी अधिकारी यांची ही नियुक्ती वरील कालावधी पूर्ण होण्यापूर्वी केव्हाही, कोणतीही कारणे न देता संपुष्टात आणण्याचा अधिकार राहील.

२. विशेष कार्यकारी अधिकारी, पुढे उल्लेख केलेली कर्तव्ये पार पाडण्यास सक्षम राहतील.--

(एक) साक्षांकनाचे काम.--विशेष कार्यकारी अधिकारी हे केवळ "साक्षांकनाचे" काम करतील. मूळ कागदपत्रे प्रत्यक्ष पाहिल्याशिवाय त्यांनी साक्षांकन करू नये. तसेच परिशिष्ट "५" मधील रबरी शिक्क्यासह मूळ कागदपत्रांच्या छायांकित प्रतींवर न चुकता दिनांकासहित साक्षांकन करावे. मूळ कागदपत्रांपेक्षा वेगळी माहिती नमूद असलेल्या कागदपत्रांवर विशेष कार्यकारी अधिकारी यांनी साक्षांकन करू नये. वेगळी माहिती असलेल्या कागदपत्रांवर जर "सत्य प्रत" म्हणून साक्षांकन केल्यास त्यामुळे होणाऱ्या सर्व प्रकारच्या परिणामांकरिता "विशेष कार्यकारी अधिकारी" म्हणून साक्षांकन करणारी व्यक्ती जबाबदार राहील. अशी घटना उघडकीस आल्यास त्या व्यक्तीची विशेष कार्यकारी अधिकारी म्हणून करण्यात आलेली नियुक्ती रद्द करण्यात येईल व तो/ती विशेष कार्यकारी अधिकारी म्हणून पुनर्नियुक्तीस अपात्र असेल.

(दोन) विशेष कार्यकारी अधिकारी म्हणून केलेली नियुक्ती "मानसेवी" असल्यामुळे विशेष कार्यकारी अधिकार्याला कोणतेही मानधन अथवा वेतन/भत्ते अनुज्ञेय असणार नाहीत.

(तीन) विशेष कार्यकारी अधिकारी म्हणून नियुक्त झालेल्या व्यक्तीने घरावर, दुकानावर, कार्यालयावर स्वतःच्या नावासह "विशेष कार्यकारी अधिकारी" असा फलक लावावा. त्यांच्या नियुक्तीबाबत कालावधी संपुष्टात आल्यावर लागलीच त्यांनी सदर फलक काढावेत. तथापि, त्यांनी त्यांच्या कुठल्याही वाहनावर "विशेष कार्यकारी अधिकारी" असा उल्लेख करू नये.

(चार) "ओळख परेड" तसेच "मृत्युपूर्व जबानी" यासाठी विशेष कार्यकारी अधिकार्यांनी उपस्थित राहू नये.

(पाच) "उत्पन्नाचे प्रमाणपत्र" देण्याचे अधिकार विशेष कार्यकारी अधिकार्यांना नसतील.

(सहा) नियुक्तीचा कालावधी संपुष्टात आल्यानंतर विशेष कार्यकारी अधिकार्याने साक्षांकनाचे काम करू नये व सर्व साहित्य जिल्हाधिकारी यांचेकडे तात्काळ परत करावे. अन्यथा अशी व्यक्ती विशेष कार्यकारी अधिकारी म्हणून पुनर्नियुक्तीसाठी अपात्र ठरेल.

(सात) नियुक्त करण्यात आलेल्या विशेष कार्यकारी अधिकार्यांनी मोहोर उमटविण्यासाठी शिक्का नजीकच्या तहसीलदार कार्यालयाकडून उपलब्ध करून घ्यावा. तसेच साक्षांकित केलेल्यांची माहिती एका नोंदवहीत न चुकता नमूद करावी व ज्या वेळेस या नोंदवहीची अवलोकनासाठी मागणी संबंधित पोलीस आयुक्त/जिल्हा पोलीस अधीक्षक यांचेकडून केली जाईल त्यावेळी ती तात्काळ उपलब्ध करून देण्यात यावी.

अनुसूची

अ. क्र. १ पूर्वीच्या	उमेदवारांची नावे	पत्ता
क्र. गॅझेटलगत		
यादीनुसार		
अ. क्र.		
१ २	३	४
१ १३२२	हेमा सुहास अवसरे	रा. २९०, शनिवार पेठ, पुणे-३०.
२ १३२३	सौ. राणी सतीश दांगट	रा. चंद्रभागा निवास, देशमुखवाडी, स. नं. ६/१, एनडीए रोड, शिवणे, तालुका हवेली, जिल्हा पुणे.

अनुसूची--चालू

१	२	३	४
३	१३२४	श्री. आकाश हरिदास कोंडे	रा. खेड-शिवापूर, तालुका हवेली, जिल्हा पुणे.
४	१३२५	सौ. प्राजक्ता निलेश तापकिर	रा. चोविसावाडी, काळी भिंत, चन्होली बु., तालुका हवेली, जिल्हा पुणे.
५	१३२६	सौ. शैला दामोदर मोळक	रा. चोविसावाडी, चन्होली बु., तालुका हवेली, जिल्हा पुणे.
६	१३२७	श्री. विराज सुरेश भोसले	रा. चन्होली बु., तालुका हवेली, जिल्हा पुणे.
७	१३२८	कल्याणी हिम्मत ताजणे	रा. चन्होली बु., तालुका हवेली, जिल्हा पुणे.
८	१३२९	श्री. महेश काळूराम भालेकर	रा. ज्योतिबानगर, तळवडे, तालुका हवेली, जिल्हा पुणे.
९	१३३०	श्री. नरेंद्र महादेव भालेकर	रा. ज्योतिबानगर, तळवडे, तालुका हवेली, जिल्हा पुणे.
१०	१३३१	डॉ. पाटील धनंजय संभाजीराव	रा. भोसरी, पुणे.
११	१३३२	सौ. विमल ज्ञानेश्वर गोरडे	रा. भोसरी, पुणे.
१२	१३३३	सौ. सुरेखा अमोल सुकाळे	रा. भोसरी, पुणे.
१३	१३३४	श्रीमती आशा सुनिल पोटवडे	रा. भोसरी, पुणे.
१४	१३३५	श्री. आरीफ रज्जाक आतार	रा. भोसरी, पुणे.
१५	१३३६	श्री. दत्तात्रय कृष्णराव फुले	रा. भोसरी, पुणे.
१६	१३३७	श्री. किशोर बाळासाहेब गवळी	रा. आळंदी रोड, माऊली कृपा बिल्डिंग, भोसरी, पुणे.
१७	१३३८	श्री. नंदु विष्णू लोंडे	रा. चौगुले कडलनी, हुतात्मा चौक, आळंदी रोड, भोसरी, पुणे.
१८	१३३९	श्री. अविनाश अशोकराव नाईक	रा. भोसरी, पुणे.
१९	१३४०	श्री. निलेश वामन मारणे	रा. भोसरी, पुणे.
२०	१३४१	श्री. शेषराव प्रकाशराव कुलकर्णी	रा. धावडे वस्ती, भोसरी, पुणे.
२१	१३४२	श्री. संजयकुमार पोपटलाल बोरा	रा. गीतांजली, शास्त्री चौक, आळंदी रोड, भोसरी, पुणे.
२२	१३४३	श्री. श्रीकांत सुभाष डुंगरवाल	रा. भोसरी, पुणे.
२३	१३४४	श्री. प्रकाश यशवंत बिराजदार	रा. स. नं. ५१, प्लॉट नं. १४२, भैरवनगर, धानोरी, पुणे.
२४	१३४५	श्री. संतोष साहेबराव खांदवे	रा. लोहगाव, साहेबमाला कॉम्प्लेक्स, पुणे.
२५	१३४६	श्री. बापुसाहेब सदाशिव शिवले	रा. तुळापूर, तालुका हवेली, जिल्हा पुणे.
२६	१३४७	श्री. सचिन नबाजी वाघमारे	रा. तुळापूर, तालुका हवेली, जिल्हा पुणे.
२७	१३४८	श्री. शिवाजी सोपान गोते	रा. शिरसवाडी, तालुका हवेली, जिल्हा पुणे.
२८	१३४९	श्री. सचिन हनुमंत मचाले	रा. शिंदेवणे, तालुका हवेली, जिल्हा पुणे.
२९	१३५०	श्री. राहुल अशोक बनकर	रा. तरडे, तालुका हवेली, जिल्हा पुणे.
३०	१३५१	सौ. श्रिया सचिन रहाळकर	रा. लोणावळा, तालुका मावळ, जिल्हा पुणे.

नवल किशोर राम,
जिल्हाधिकारी, पुणे.

पुणे, १० सप्टेंबर २०१८.